UPS SAV TENANT IMPROVEMENT

[redacted]

UNITED PARCEL SERVICE INC.

[redacted]

Stratus Project No.2025-1073

ADDENDUM 1 - 03/18/2026

PERMITTING AGENCY:

CITY OF SAVANNAH

CONSTRUCTION TYPE:

TYPE IIB - NON-COMBUSTIBLE,SPRINKLERED

OCCUPANCY:

PRIMARY - LIFE SAFETY CODE NFPA 101 2024

SUPPLEMENTAL - INTERNATIONAL BUILDING CODE 2024
BUSINESS GROUP B OCCUPANCY

ALLOWABLE HEIGHTS & AREA:

PRIMARY - INTERNATIONAL BUILDING CODE 2024

APPLICABLE CODES:

INTERNATIONAL BUILDING CODE (IBC), 2024 W/ STATE OF GEORGIA AMENDMENTS
NFPA 101, LIFE SAFETY CODE, 2024 W/ STATE OF GEORGIA AMENDMENTS
INTERNATIONAL FIRE CODE 2024 W/ STATE OF GEORGIA AMENDMENTS
INTERNATIONAL MECHANICAL CODE 2024 W/ STATE OF GEORGIA AMENDMENTS
INTERNATIONAL PLUMBING CODE 2024 W/ STATE OF GEORGIA AMENDMENTS
NATIONAL ELECTRICAL CODE 2023
INTERNATIONAL FUEL GAS CODE 2024 W/ STATE OF GEORGIA AMENDMENTS
INTERNATIONAL ENERGY CONSERVATION CODE 2015 W/ STATE OF GEORGIA AMENDMENTS
AMERICANS WITH DISABILITIES ACT STANDARDS FOR ACCESSIBLE DESIGN, 2010
ANSI A117.1 2003

PRIMARY USE GROUP: S-1, B (Business)

CONSTRUCTION TYPE: IIB, NON-COMBUSTIBLE, SPRINKLERED

BUILDING AREA: PROPOSED GROSS AREA: NO CHANGE TO EXISTING

BUILDING HEIGHT: PROPOSED HEIGHT: NO CHANGE TO EXISTING
ALLOWABLE HEIGHT: NO CHANGE TO EXISTING

FIRE RESISTANCE RATING REQUIREMENTS FOR BUILDING ELEMENTS(TABLE 601)


PRIMARY STRUCUTRAL FRAME	0HR
BEARING WALLS (EXTERIOR)	0HR
BEARING WALLS (INTERIOR)	0HR
NONBEARING WALLS (EXTERIOR)	0HR
NONBEARING WALLS (INTERIOR)	0HR
FLOOR CONSTRUCTION	0HR
ROOF CONSTRUCTION	0HR

PORTABLE FIRE EXTINGUISHERS	PROVIDE EVERY 75' MAX TRAVEL DISTANCE
MANUAL ALARM	NOT REQUIRED PER 907.2.2
SMOKE DETECTORS	NOT REQUIRED PER 907.2.2

MEANS OF EGRESS (NFPA 101)

REQUIRED NUMBER OF EXITS	1 PER SPACE (38.2.4.3)
PROVIDED NUMBER OF EXITS	1 PER SPACE
REQUIRED EGRESS COMPONENT WIDTH	32" CLEAR (7.2.1.2.3.2)
PROVIDED EGRESS COMPONENT WIDTH	PER PLANS (32" MINIMUM)
MAXIMUM EXIT ACCESS TRAVEL DISTANCE	200' (38.2.6.3)

PROJECT INFORMATION



LOCATION MAP

SCOPE OF WORK

THIS PROJECT INCLUDES THE CONSTRUCTION OF

[redacted]

HEAD INTERNATIONAL AIRPORT.

ALL CONSTRUCTION WILL BE IN CONFORMANCE WITH JURISDICTION REQUIREMENTS & INTERNATIONAL BUILDING CODE.

PLEASE NOTE ALL DRAWINGS AND SPECIFICATIONS FOR THIS PROJECT WILL BE MADE AVAILABLE VIA THE CONSTRUCTION MANAGER.

STRATUS®

ARCHITECT
STRATUS®
3715 NORTHSIDE PARKWAY, NW
E 200
[redacted]

MEP
KILLIAN - A STRATUS COMPANY
[redacted]

OWNER
UNITED PARCEL SERVICE - UPS
NE
[redacted]

JACOB BABCOCK
UPS AIR REGION
BUILDING & SYSTEMS
PROJECT MANAGER
502-802-2678
JBABCOCK@UPS.COM

© 2025 STRATUS®

DRAWING INDEX

SHEET INFORMATION		REVISION INFORMATION		
SHEET NO.	SHEET NAME	Δ	DATE	NAME
GENERAL				
G-001	COVER SHEET	A	03/18/2026	ADDENDUM 1
G-002	SHEET INDEX & NARRATIVE	A	03/18/2026	ADDENDUM 1
G-003	GENERAL NOTES, SYMBOLS, & ABBREVIATIONS	A	03/18/2026	ADDENDUM 1
G-004	ADA DIAGRAMS & MOUNTING HEIGHTS	A	03/18/2026	ADDENDUM 1
G-005	ADA DIAGRAMS & MOUNTING HEIGHTS	A	03/18/2026	ADDENDUM 1
G-006	WALL TYPES	A	03/18/2026	ADDENDUM 1
G-101	OVERALL LIFE SAFETY PLAN	A	03/18/2026	ADDENDUM 1
DEMOLITION				
AD-101	EXISTING CONDITIONS & DEMOLITION FLOOR PLAN - FIRST FLOOR	A	03/18/2026	ADDENDUM 1
ARCHITECTURAL				
A-101	OVERALL FIRST FLOOR PLAN	A	03/18/2026	ADDENDUM 1
A-301	WALL SECTION	A	03/18/2026	ADDENDUM 1
A-401	ENLARGED OFFICE FIRST FLOOR PLAN	A	03/18/2026	ADDENDUM 1
A-402	ENLARGED OFFICE REFLECTED CEILING PLAN	A	03/18/2026	ADDENDUM 1
A-403	ENLARGED RESTROOM PLANS AND ELEVATIONS	A	03/18/2026	ADDENDUM 1
A-404	ENLARGED RESTROOM REFLECTED CEILING PLAN	A	03/18/2026	ADDENDUM 1
A-600	DOOR SCHEDULES & DETAILS	A	03/18/2026	ADDENDUM 1
A-701	ENLARGED OFFICE FIRST FLOOR FINISH PLAN	A	03/18/2026	ADDENDUM 1
A-702	ENLARGED RESTROOM FINISH PLAN	A	03/18/2026	ADDENDUM 1
FIRE PROTECTION				
FP-101	FIRE PROTECTION SUGGESTED HEAD LAYOUT	A	03/18/2026	ADDENDUM 1
PLUMBING				
P-001	PLUMBING NOTES	A	03/18/2026	ADDENDUM 1
P-002	PLUMBING SCHEDULES & DETAILS	A	03/18/2026	ADDENDUM 1
P-101	PLUMBING BUILDING 1 WASTE/VENT PLAN	A	03/18/2026	ADDENDUM 1
P-102	PLUMBING BUILDING 1 DOMESTIC SUPPLY PLAN	A	03/18/2026	ADDENDUM 1
P-103	PLUMBING ENLARGED PLANS	A	03/18/2026	ADDENDUM 1
P-201	PLUMBING RISERS	A	03/18/2026	ADDENDUM 1
MECHANICAL				
M-001	MECHANICAL NOTES	A	03/18/2026	ADDENDUM 1
M-101	OVERALL MECHANICAL PLAN	A	03/18/2026	ADDENDUM 1
M-102	ENLARGED OFFICE MECHANICAL PLAN	A	03/18/2026	ADDENDUM 1
M-103	ENLARGED OFFICE EXHAUST PLAN	A	03/18/2026	ADDENDUM 1
M-201	MECHANICAL SCHEDULES	A	03/18/2026	ADDENDUM 1
M-301	MECHANICAL DETAILS	A	03/18/2026	ADDENDUM 1
ELECTRICAL				
E-001	ELECTRICAL NOTES	A	03/18/2026	ADDENDUM 1
E-101	OVERALL LIGHTING PLAN	A	03/18/2026	ADDENDUM 1
E-102	ENLARGED OFFICE LIGHTING PLAN	A	03/18/2026	ADDENDUM 1
E-103	OVERALL POWER PLAN	A	03/18/2026	ADDENDUM 1
E-104	ENLARGED OFFICE POWER PLAN	A	03/18/2026	ADDENDUM 1
E-105	OVERALL LV CAMERA/ACCESS PLAN	A	03/18/2026	ADDENDUM 1
E-201	ELECTRICAL SCHEDULES	A	03/18/2026	ADDENDUM 1
E-301	ELECTRICAL PANEL SCHEDULES	A	03/18/2026	ADDENDUM 1
E-302	ELECTRICAL PANEL SCHEDULES AND POWER RISER	A	03/18/2026	ADDENDUM 1

CHANGE NARRATIVE - ADDENDUM 1

G-001	REMOVED DRAWING INDEX AND ADDED IT TO SHEET G-002
G-002	REVISED SHEET.
G-003	UPDATED PROJECT ADDRESS.
G-003	REVISED SHEET NUMBER.
G-004	UPDATED PROJECT ADDRESS.
G-004	REVISED SHEET NUMBER.
G-005	UPDATED PROJECT ADDRESS.
G-005	REVISED SHEET NUMBER.
G-006	UPDATED PROJECT ADDRESS.
G-006	REVISED SHEET NUMBER.
G-101	RELOCATED EYE WASH STATION TO EXTERIOR WALL.
G-101	UPDATED PROJECT ADDRESS.
AD-101	UPDATED PROJECT ADDRESS.
A-101	RELOCATED EYE WASH STATION TO EXTERIOR WALL.
A-101	ADDED SHEET NOTES 4 AND 5.
A-101	UPDATED PROJECT ADDRESS.
A-301	UPDATED PROJECT ADDRESS.
A-401	UPDATED PROJECT ADDRESS.
A-401	REVISED DIMENSION VALUE / SHIFTED WALL LOCATION.
A-402	UPDATED PROJECT ADDRESS.
A-403	UPDATED PROJECT ADDRESS.
A-403	REVISED DIMENSION VALUE / SHIFTED WALL LOCATION.
A-403	REVISED DIMENSION VALUE / SHIFTED WALL LOCATION.
A-403	REVISED DIMENSION VALUE / SHIFTED WALL LOCATION.
A-403	ADDED ENLARGED PLAN AND FIXTURE SCHEDULE.
A-404	UPDATED PROJECT ADDRESS.
A-404	REVISED DIMENSION FOR LIGHT LOCATIONS IN MENS RESTROOM (ROOM #104).
A-600	UPDATED PROJECT ADDRESS.
A-600	REVISED DOOR TYPE FOR DOORS 108A, 108B, 109, 110B, 113, 114, AND 115 IN DOOR SCHEDULE.
A-600	REVISED DOOR TYPE C AND ADDED DOOR TYPE CC TO DOOR TYPE LEGEND.
A-701	UPDATED PROJECT ADDRESS.
A-701	REVISED FLOOR FINISH FROM CARPET TO SEALED CONCRETE IN TRAINING ROOM (ROOM #113).
A-701	REMOVED CARPET FROM FINISH SCHEDULE.
A-702	UPDATED PROJECT ADDRESS.
A-702	REMOVED CARPET FROM FINISH SCHEDULE.
FP-101	UPDATED PROJECT ADDRESS.
P-001	UPDATED PROJECT ADDRESS.
P-002	UPDATED PROJECT ADDRESS.
P-101	UPDATED PROJECT ADDRESS.
P-101	RELOCATED EYE WASH STATION TO EXTERIOR WALL.
P-102	UPDATED PROJECT ADDRESS.
P-102	RELOCATED EYE WASH STATION TO EXTERIOR WALL.
P-103	UPDATED PROJECT ADDRESS.
P-103	REVISED WASTE, VENT, AND SUPPLY LINES TO PLUMBING FIXTURES IN WOMENS SHOWER, MENS SHOWER, AND MENS RESTROOM.
P-201	UPDATED PROJECT ADDRESS.
P-201	REVISED RISER DIAGRAM 3 AND 6.
M-001	UPDATED PROJECT ADDRESS.
M-101	UPDATED PROJECT ADDRESS.
M-102	UPDATED PROJECT ADDRESS.
M-102	REVISED MEHCANICAL LAYOUT IN WOMENS SHOWER, MENS SHOWER, AND MENS RESTROOM.
M-103	UPDATED PROJECT ADDRESS.
M-103	REVISED MEHCANICAL LAYOUT IN WOMENS SHOWER, MENS SHOWER, AND MENS RESTROOM.
M-201	UPDATED PROJECT ADDRESS.
M-301	UPDATED PROJECT ADDRESS.
E-001	UPDATED PROJECT ADDRESS.
E-101	UPDATED PROJECT ADDRESS.
E-102	UPDATED PROJECT ADDRESS.
E-102	REVISED ELECTRICAL LAYOUT IN WOMENS SHOWER, MENS SHOWER, AND MENS RESTROOM.
E-103	UPDATED PROJECT ADDRESS.
E-104	UPDATED PROJECT ADDRESS.
E-104	REVISED ELECTRICAL LAYOUT IN WOMENS SHOWER, MENS SHOWER, AND MENS RESTROOM.
E-105	UPDATED PROJECT ADDRESS.
E-105	REVISED BACKGROUND FOR WOMENS SHOWER, MENS SHOWER, AND MENS RESTROOM.
E-105	REVISED CAMERA AND ACCESS GENERAL NOTES.
E-201	UPDATED PROJECT ADDRESS.
E-301	UPDATED PROJECT ADDRESS.
E-302	UPDATED PROJECT ADDRESS.

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00
DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035254
REGISTERED ARCHITECT

SHEET INDEX & NARRATIVE

UPS SAV TENANT IMPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION


G-002

3/19/2026 4:45:26 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®

DRAWING CONVENTIONS


VIEW TITLE




GRAPHIC SYMBOLS



ELEVATION SYMBOLS




DIMENSION LINES




ROOM NAME / NUMBER SYMBOL




ELEVATION REFERENCES




BUILDING / WALL SECTION REFERENCES




DETAIL REFERENCES



PARTITION TYPE, DOOR, AND MISC SYMBOLS



MATERIAL SYMBOLS (SECTION)



ABBREVIATIONS

AB	- ANCHOR BOLT
AC	- AIR CONDITIONING
ACC	- ACCESSIBLE
ACOUS	- ACOUSTICAL
AD	- AREA DRAIN
ADD	- ADDITIONAL
ADJ	- ADJUSTABLE
AFF	- ABOVE FINISH FLOOR
AGGR	- AGGREGATE
ALT	- ALTERNATE
ALUM	- ALUMINUM
ANCH	- ANCHOR
ANNO	- ANODIZED
APC	- ACOUSTICAL PANEL CEILING
APPD	- APPROVED
APPROX	- APPROXIMATE
ARCH	- ARCHITECTURAL
ATC	- ACOUTSTICAL TILE CEILING
AUTO	- AUTOMATIC
AV	- AUDIO VISUAL
BEJ	- BRICK EXPANSION JOINT
BD	- BOARD
BLDG	- BUILDING
BLK	- BLOCK
BM	- BEAM
BOT	- BOTTOM
BRK	- BRICK
BSMT	- BASEMENT
BT	- BOLT
BUR	- BUILT-UP ROOFING
CAB	- CABINET
CAT	- CATEGORY
CB	- CATCH BASIN
CBD	- CHALK BOARD
CBU	- CEMENTITIOUS BACKER UNIT
CEM	- CEMENT
CER	- CERAMIC
CG	- CORNER GUARD
CH	- CHILLER
CHAN	- CHANNEL
CI	- CAST IRON
CIP	- CAST-IN-PLACE
CJ	- CONTROL JOINT / CONSTRUCTION JOINT
CL	- CENTER LINE
CLG	- CEILING
CLR	- CLEAR
CMU	- CONCRETE MASONRY UNIT
CNTR	- COUNTER
CO	- CLEANOUT
COL	- COLUMN
COMPART	- COMPARTMENT
CONC	- CONCRETE
COND	- CONDITION
CONN	- CONNECTION
CONT	- CONTINUOUS
CONTR	- CONTRACTOR
COORD	- COORDINATE
CORR	- CORRIDOR
CT	- CERAMIC TILE / COOLING TOWER
CTR	- CENTER
CTSK	- COUNTER SUNK
CW	- COLD WATER (PIPING)
D	- DEEP, DEPTH
DA	- DISABLED
DBL	- DOUBLE
DEG	- DEGREE
DEMO	- DEMOLITION
DEPT	- DEPARTMENT
DET	- DETAIL
DF	- DRINKING FOUNTAIN
DIA	- DIAMETER
DIFF	- DIFFUSER
DIM	- DIMENSION
DIS	- DISABLED
DISP	- DISPENSER
DMPF	- DAMPPROOFING
DMT	- DEMOUNTABLE
DN	- DOWN
DO	- DOOR OPENING
DP	- DIMENSION POINT
DPTN	- DEMOUNTABLE PARTITION
DR	- DOOR
DRN	- DRAIN
DS	- DOWNSPOUT
DW	- DISHWASHER
DWG	- DRAWING
DWR	- DRAWER
(E)	- EXISTING
E	- EAST
EA	- EACH
EB	- EXPANSION BOLT
EIFS	- EXTERIOR INSULATION & FINISH SYSTEM
EFS	- EXTERIOR FINISH SYSTEM
EJ	- EXPANSION JOINT
EL	- ELEVATION
ELEC	- ELECTRICAL
ELEV	- ELEVATOR
EMERG	- EMERGENCY
ENCLO	- ENCLOSURE
EP	- ELECTRICAL PANELBOARD
EQ	- EQUAL
EQUIP	- EQUIPMENT
ESCAL	- ESCALATOR
EWC	- ELECTRICAL WATER COOLER
EXH	- EXHAUST
EXP	- EXPANSION
EXIST	- EXISTING
EXT	- EXTERIOR
FA	- FIRE ALARM
FB	- FACE BRICK
FC	- FACE
FD	- FLOOR DRAIN
FDC	- FIRE DEPARTMENT CONNECTION
FE	- FIRE EXTINGUISHER
FEC	- FIRE EXTINGUISHER CABINET
FF&E	- FURNITURE, FINISHES & EQUIPMENT
FHC	- FIRE HOSE CABINET
FIN	- FINISH
FL	- FLOOR
FLASH	- FLASHING
FLUOR	- FLUORESCENT
FP	- FIRE PROTECTION
FPG	- FIREPROOFING
FR	- FRAME
FT	- FEET
FRTW	- FIRE RETARDANT TREATED WOOD
FURN	- FURNITURE
FURR	- FURRING
G	- GROUND
GA	- GAUGE / GAGE
GALV	- GALVANIZED
GB	- GRAB BAR
GC	- GENERAL CONTRACT(OR)
GRC	- GLASS FIBER REINFORCED CONCRETE
GRG	- GLASS FIBER REINFORCED GYPSUM
GL	- GLASS
GR	- GRADE
GRD	- GROUND
GYPBD	- GYPSUM WALLBOARD
H	- HIGH / HEIGHT
HB	- HOSE BIB
HC	- HOLLOW CORE
HCP	- HANDICAPPED
HDW	- HARDWARE
HDWD	- HARDWOOD
HS	- HEAT STRENGTHENED (GLASS)
HM	- HOLLOW METAL (STEEL FRAME)
HNDRL	- HANDRAIL
HO	- HOLD-OPEN
HORIZ	- HORIZONTAL
HPT	- HIGH POINT
HRC	- HOSE REEL CABINET
HR	- HOUR
HT	- HEIGHT
HVAC	- HEATING, VENTILATION, AIR CONDITIONING
HW	- HOT WATER
HYDR	- HYDRAULIC
ID	- INSIDE DIAMETER
IN	- INCH
INCAND	- INCANDESCENT
INCL	- INCLUDED / INCLUDING
INFO	- INFORMATION
INSUL	- INSULATION
INT	- INTERIOR
INTERM	- INTERMEDIATE
INV	- INVERT
IPS	- INTERNATIONAL PIPE STANDARD
IRMA	- INVERTED ROOF MEMBRANE ASSEMBLY
JAN	- JANITOR
JC	- JANITOR'S CLOSET
JST	- JOIST
JT	- JOINT
K	- KIP (1000 LBF)
KPL	- KICK PLATE
KG	- KILOGRAM
KIT	- KITCHEN
KO	- KNOCKOUT
L	- LONG OR LITER (METRIC DOCS)
LAB	- LABORATORY
LDG	- LANDING
LAM	- LAMINATE / LAMINATION
LAV	- LAVATORY
LB	- POUND
LF	- LINEAR FOOT
LKR	- LOCKER
LLH	- LONG LEG HORIZONTAL
LLV	- LONG LEG VERTICAL
LN	- LINE
LT	- LIGHT
LPT	- LOW POINT
M	- METER
MACH	- MACHINE
MAINT	- MAINTENANCE
MAS	- MASONRY
MATL	- MATERIAL
MAX	- MAXIMUM
MB	- MACHINE BOLT
MBL	- MARBLE
MDF	- MEDIUM DENSITY FIBERBOARD
MEP	- MECHANICAL, ELECTRICAL, PLUMBING
MDO	- MEDIUM DENSITY OVERLAY PLYWOOD
MECH	- MECHANICAL
MEMB	- MEMBRANE
MET	- METAL
MEZZ	- MEZZANINE
MFR	- MANUFACTURER
MH	- MANHOLE
MIN	- MINIMUM
MISC	- MISCELLANEOUS
MM	- MILLIMETER
MO	- MASONRY OPENING
MS	- MACHINE SCREW
MTD	- MOUNTED
MTG	- MOUNTING
MTL	- METAL
MULL	- MULLION
N	- NORTH
NA	- NOT APPLICABLE
NC	- NOISE CRITERIA
NIC	- NOT IN CONTRACT
NO	- NUMBER
NOM	- NOMINAL
NTS	- NOT TO SCALE
OA	- OUTSIDE AIR
OC	- ON CENTER
OCEW	- ON CENTER EACH WAY
OD	- OUTSIDE DIAMETER/DIMENSION
OFCI	- OWNER FURNISHED, CONTR INSTALLED
OFOI	- OWNER FURNISHED, OWNER INSTALLED
OFF	- OFFICE
OH	- OVER HEAD
OPH	- OPPOSITE HAND
OPNG	- OPENING
OPP	- OPPOSITE
OPPHD	- OPPOSITE HAND
ORD	- OVERFLOW ROOF DRAIN
OUTS	- OUTSIDE
OVHD	- OVERHEAD
PAV	- PAVING
PATD	- PAPER TOWEL DISPENSER
PBD	- PARTICLEBOARD
PC	- PRECAST CONCRETE
PDF	- POWER DRIVEN FASTENER
PERF	- PERFORATED
PERIM	- PERIMETER
PERP	- PERPENDICULAR
PL	- PLATE
PLAM	- PLASTIC LAMINATE
PLAS	- PLASTER
PLF	- POUNDS PER LINEAR FOOT
PLYWD	- PLYWOOD
PNL	- PANEL
POL	- POLISHED
PREFAB	- PREFABRICATED
Q	- QUARRY TILE
QTY	- QUANTITY
(R)	- RELOCATED
R	- RADIUS OR RISER (PIPING)
RA	- RETURN AIR
RAD	- RADIUS
RB	- RESILIENT BASE
RCP	- REFLECTED CEILING PLAN
RD	- ROOF DRAIN
RECOM	- RECOMMENDED
RECPT	- RECEPTACLE
REC	- RECESSED
REF	- REFERENCE
REFL	- REFLECTED / REFLECTIVE / REFLECT
REFR	- REFRIGERATOR
REG	- REGISTER
REINF	- REINFORCED / REINFORCING
REL	- RELOCATE
REM	- REMOVABLE
REQ	- REQUIRE / REQUIRED
RESIL	- RESILIENT
REV	- REVISION / REVISED
RM	- ROOM
RO	- ROUGH OPENING
RTD	- RATED
RTG	- RATING
RWL	- RAIN WATER LEADER
S	- SOUTH
SA	- SUPPLY AIR
SAN	- SANITARY
SC	- SOLID CORE
SCHED	- SCHEDULE
SD	- STORM DRAIN / SOAP DISPENSER
SECT	- SECTION
STS	- SELF TAP METAL SCREW
SF	- SQUARE FEET/FOOT
SH	- SPRINKLER HEAD
SHT	- SHEET
SHR	- SHOWER
SIM	- SIMILAR
SM	- SHEET METAL OR SQUARE METER (METRIC DOCS)
SND	- SANITARY NAPKIN DISPENSER
SP	- STANDPIPE
SPEC	- SPECIFICATION
SPR	- SPRINKLER
SPKR	- SPEAKER
SQ	- SQUARE
SSE	- STRUCTURE SLAB ELEVATION
SST	- STAINLESS STEEL
SSK	- SERVICE SINK
STA	- STATION
STD	- STANDARD
STL	- STEEL
STLJST	- STEEL JOIST
STOR	- STORAGE
STRG	- STRINGER
STRL	- STRUCTURAL
STRUC	- STRUCTURAL
SUBCAT	- SUBCATEGORY
SUSP	- SUSPENDED
SYMM	- SYMMETRICAL
SYS	- SYSTEM
T&G	- TONGUE AND GROOVE
T	- TREAD / THERMOSTAT
TB	- TOWEL BAR
TC	- TOP OF CURB
TCONC	- TOP OF CONCRETE
TEL	- TELEPHONE OR TELECOM
TEMP	- TEMPERATURE
TER	- TERRAZZO
TGB	- TOGGLE BOLT
THK	- THICKNESS
THRES	- THRESHOLD
THRU	- THROUGH
TKBD	- TACKBOARD
TMPD	- TEMPERED
TO	- TOP OF (SEE OTHER WORD)
TOS	- TOP OF SLAB, TOP OF STRUCTURE
TOSTL	- TOP OF STEEL
TP	- TOP OF PAVEMENT
TPD	- TOILET PAPER DISPENSER
TRACT	- TRACTION
TV	- TELEVISION
TW	- TOP OF WALL
TYP	- TYPICAL
UNFIN	- UNFINISHED
UON	- UNLESS OTHERWISE NOTED
UR	- URINAL
VAC	- VENTILATION AND AIR CONDITIONING
VCT	- VINYL COMPOSITION TILE
VERT	- VERTICAL
VEST	- VESTIBULE
VIF	- VERIFY IN FIELD
VR	- VAPOR RETARDER
VT	- VINYL TILE
VWC	- VINYL WALL COVERING
W/	- WITH
W	- WIDE, WIDTH/WEST
WC	- WATER CLOSET
WD	- WOOD
WDS	- WOOD SCREW
WDW	- WINDOW
W/O	- WITHOUT
WP	- WATERPROOFING
WPM	- WATERPROOF MEMBRANE
WPT	- WORK POINT
WR	- WATER RESISTANT/REPELLANT
WS	- WEATHERSTRIPPING
WSCT	- WAINSCOT
WT	- WEIGHT
WW	- WALL TO WALL

OVERALL PROJECT GENERAL NOTES

1 GENERAL PROVISIONS / SUPPLEMENTAL CONDITIONS

1.01 CONTRACTOR SHALL COMPLY WITH THE APPLICABLE BUILDING CODES, LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY HAVING JURISDICTION UPON THE PERFORMANCE OF THE WORK.

1.02 CONTRACTOR SHALL BE RESPONSIBLE FOR SECURING AND PAYING FOR ALL REQUIRED PERMITS, LICENSES, INSPECTIONS, FEES, CERTIFICATES, ETC AS MAY BE REQUIRED FOR THE CONSTRUCTION AND OCCUPANCY OF THE PROJECT.

1.03 THE WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS (WHICH INCLUDE BUT ARE NOT LIMITED TO THE CONSTRUCTION AGREEMENT, DRAWINGS, SPECIFICATIONS, ADDENDA AND MODIFICATIONS). THE CONTRACTOR SHALL REPORT DISCREPANCIES WITHIN OR BETWEEN THE CONTRACT DOCUMENTS TO THE ARCHITECT IN WRITING FOR CLARIFICATION PRIOR TO IMPLEMENTING THE WORK.

1.04 CONTRACTOR SHALL VISIT THE SITE AND VERIFY EXISTING CONDITIONS AND BUILDING SYSTEMS AFFECTED BY THE PROPOSED WORK, AS WELL AS EXISTING DIMENSIONS AND ELEVATIONS PRIOR TO COMMENCING WITH THE WORK. CONTRACTOR SHALL NOTIFY THE ARCHITECT IMMEDIATELY OF CONDITIONS THAT DEVIATE FROM THOSE INDICATED ON THE CONTRACT DOCUMENTS. COMMENCEMENT OF WORK CONSTITUTES ACCEPTANCE OF EXISTING CONDITIONS AS ACCEPTABLE TO PERFORM THE WORK.

1.05 THE ARCHITECT WILL NOT HAVE CONTROL OVER THE CHARGE OF AND WILL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, SHORING OR FOR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK, SINCE THESE ARE SOLELY THE CONTRACTOR'S RESPONSIBILITY.

1.06 IN THE EVENT THE CONTRACTOR ENCOUNTERS MATERIALS BELIEVED TO BE HAZARDOUS THAT HAVE NOT BEEN RENDERED HARMLESS, THE CONTRACTOR SHALL IMMEDIATELY STOP THE WORK IN THE AFFECTED AREA AND REPORT THE CONDITION TO THE BUILDING OWNER IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN AGREEMENT BETWEEN THE CONTRACTOR AND BUILDING OWNER.

1.07 SUBMITTALS, SUCH AS SHOP DRAWINGS, SAMPLES, PRODUCT DATA, ETC, WHEN REQUIRED SHALL BE SUBMITTED BY THE CONTRACTOR FOR APPROVAL BY ARCHITECT PRIOR TO FABRICATION OR CONSTRUCTION. REVIEW AND APPROVAL OR OTHER ACTION TAKEN WILL BE ONLY FOR THE LIMITED PURPOSE OF CHECKING FOR CONFORMANCE WITH THE INFORMATION GIVEN AND THE DESIGN CONCEPT EXPRESSED IN THE CONTRACT DOCUMENTS.

1.08 THE PROVISION OF AND/OR ENGINEERING OF SHORING AS MAY BE REQUIRED BY THE CONTRACTOR 'S DETERMINED MEANS AND METHOD OF CONSTRUCTION SHALL BE PROVIDED BY A STRUCTURAL ENGINEER LEGALLY REGISTERED TO PRACTICE IN THE STATE WHERE THE PROJECT IS LOCATED AND CONTRACTED BY THE CONTRACTOR.

1.09 SITE SHALL BE CLEANED THROUGHOUT THE DURATION OF THE PROJECT. REMOVE DUST, DEBRIS, OIL, STAINS, FINGERPRINTS AND LABELS FROM EXPOSED FINISHED SURFACES, INCLUDING GLAZING. CONTRACTOR SHALL BE RESPONSIBLE FOR THEIR OWN TRASH REMOVAL DURING CONSTRUCTION.

1.10 CONTRACTOR SHALL COORDINATE AND OBTAIN APPROVAL FROM THE GOVERNING JURISDICTION(S) AND AGENCY(S) FOR SPRINKLER AND FIRE SUPPRESSION SYSTEMS THROUGHOUT CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO, REQUIREMENTS FOR TEMPORARY MEASURES DURING CONSTRUCTION TO SATISFY THE SAFETY REQUIREMENTS OF THE AUTHORITIES HAVING REQUIREMENTS OF THE AUTHORITIES HAVING JURISDICTION SHALL BE PROVIDED WITHIN THE COST OF THE WORK AT NO EXTRA COST TO THE OWNER.

2 DRAWINGS

2.01 DO NOT SCALE DRAWINGS.

2.02 THREE DIMENSIONAL (3D) PERSPECTIVE VIEWS MAY BE PROVIDED FOR REFERENCE TO ASSIST THE CONTRACTOR IN UNDERSTANDING THE DESIGN CONCEPT FOR CERTAIN COMPONENTS. AS SUCH, THESE VIEWS ARE DIAGRAMMATIC IN NATURE AND ALL INFORMATION FOR CONSTRUCTION MAY NOT BE ILLUSTRATED IN THE PERSPECTIVE VIEW. CLARIFICATIONS AND/OR INTERPRETATIONS RELATING TO PERSPECTIVE VIEWS SHALL BE DIRECTED TO THE ARCHITECT.

2.03 BUILDING COMPONENTS AND/OR PORTIONS OF SYSTEMS AS MAY BE INDICATED ON THE ARCHITECTURAL DRAWINGS SUCH AS LIGHT FIXTURES, AIR DIFFUSERS/RETURNS, SPRINKLERS AND SPEAKERS, ETC ARE GENERALLY SHOWN TO DENOTE LOCATION AND LAYOUT PATTERN WHERE PLACEMENT IS CRITICAL TO APPEARANCE. THE ARCHITECTURAL DRAWINGS DO NOT REPRESENT COMPLETE SYSTEMS WHICH ARE TO BE PROVIDED AND AS MAY BE REQUIRED BY OTHER CONTRACT DOCUMENTS.

2.04 ITEMS NOTED AS "TYPICAL" OR "TYP" MEANS TO APPLY TO OTHER, SIMILAR LOCATIONS.

2.05 ITEMS NOTED AS "SIMILAR" OR "SIM" MEANS THAT A COMPONENT IS SIMILAR IN CHARACTER AND FINISH TO THE REFERENCED DETAIL BUT MAY VARY IN DIMENSION, LOCATION OR ORIENTATION.

3 MATERIALS, SYSTEMS AND COMPONENTS

3.01 ALL MATERIALS, SYSTEMS, FINISHES AND COMPONENTS SHALL BE PROVIDED AS INDICATED IN THE CONTRACT DOCUMENTS. PROPOSED SUBSTITUTIONS OF MATERIALS, SYSTEMS, COMPONENTS, FINISHES AND/OR PRODUCT SHALL BE SUBMITTED BY THE CONTRACTOR TIMELY WITH THE SEQUENCE OF CONSTRUCTION AND WITH PROPER, DETAILED INFORMATION FOR CONSIDERATION BY THE OWNER AND/OR ARCHITECT. PROPOSED SUBSTITUTIONS MAY ONLY BE INCORPORATED INTO THE WORK IF ACCEPTED BY THE OWNER AND/OR ARCHITECT.

3.02 CONTRACTOR SHALL PROVIDE ALL SUPPLEMENTAL MATERIAL REQUIRED TO PROPERLY INSTALL, SUPPORT AND BRACE ALL COMPONENTS OF THE WORK.

3.03 CONTRACTOR SHALL VERIFY AND COORDINATE CONDITIONS AND DIMENSIONS BEFORE FABRICATION OF ANY WORK.

3.04 PROVIDE FIRE-RETARDANT WOOD BLOCKING OR STEEL REINFORCING AS REQUIRED IN PARTITIONS AND IN CEILINGS TO SUPPORT MILLWORK, LIGHT FIXTURES, ACCESSORIES, ARTWORK, HARDWARE, HANDRAILS AND/OR OTHER APPLIED FINISH SYSTEMS.

4 FINISHES

4.01 CONTRACTOR SHALL PROVIDE MEANS TO LEVEL CONCRETE FLOOR SLABS AND/OR REPAIR ACCESS FLOORING TO RECEIVE NEW FINISH FLOORING IN ALL AREAS WHERE DEMOLITION OF EXISTING TILE, PARTITIONS, CARPETING, ETC CAUSES AND/OR EXPOSES UNEVENNESS IN THE FLOOR OR SLAB.

4.02 PATCH CONSTRUCTION BY FILLING, PREPARING, REFINISHING, CLOSING UP AND SIMILAR OPERATIONS FOLLOWING PERFORMANCE OF OTHER WORK. PATCH WITH DURABLE SEAMS THAT ARE CONCEALED AND NOT VISIBLE. TEST AND INSPECT PATCHED AREAS AFTER COMPLETION TO VERIFY/DEMONSTRATE INTEGRITY OF INSTALLATION.

4.03 RESTORE FINISHES OF PATCHED AREAS AND EXTEND FINISH RESTORATION INTO ADJOINING CONSTRUCTION IN A MANNER THAT WILL CONCEAL VISIBLE EVIDENCE OF PATCHING AND REFINISHING.

4.04 WHERE PATCHING OCCURS IN A PAINTED SURFACE, APPLY PRIMER AND INTERMEDIATE PAINT COATS OVER THE PATCH AND SUPPLY FINAL PAINT COAT OVER THE ENTIRE UNBROKEN SURFACE CONTACTING THE PATCH. PROVIDE ADDITIONAL COATS UNTIL PATCH BLENDS WITH ADJACENT SURFACE.

4.05 MATERIALS USED FOR INTERIOR WALLS, CEILINGS AND TRIM SHALL BE CLASS A FIRE RATED UNLESS OTHERWISE NOTED.

4.06 INSTALL FINISH MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDED SPECIFICATIONS, ENVIRONMENTAL CONDITIONS, SURFACE PREPARATIONS, ADHESIVES, COMPATIBILITY WITH ADJACENT MATERIALS, BACKINGS, ETC

4.07 ELECTRICAL SWITCH AND COVER PLATES, SURFACE HARDWARE, GRILLES, ETC SHALL BE INSTALLED AFTER PAINTING AND/OR APPLICATION OF WALL/FLOOR COVERINGS.

UNITED PARCEL SERVICE INC.


A

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal



UPS SAV TENANT IMPROVEMENT

GENERAL NOTES, SYMBOLS, & ABBREVIATIONS

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1


02/20/2026
ISSUED FOR CONSTRUCTION

A G-003


3/19/2026 4:45:29 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®

LAVATORIES & MIRRORS




A
LAVATORY CLEARANCES




B
CLEAR FLOOR SPACE AT LAVATORIES


URINALS



FRONT ELEVATION **PLAN**

SIGNAGE






NOTE:
SIGNS SHALL BE INSTALLED ON THE WALL ADJACENT TO THE LATCH SIDE OF THE DOOR. MOUNTING HEIGHT SHALL BE 60" AFF TO THE CENTERLINE OF SIGN.
REFER TO SPECIFICATION FOR SIGNAGE REQUIREMENTS.


A
DISPLAY CONDITIONS INTERNATIONAL SYMBOL OF ACCESSIBILITY

B
INTERNATIONAL TDD SYMBOL


C
INTERNATIONAL SYMBOL OF ACCESS FOR HEARING LOSS

SPACE ALLOWANCE & REACH RANGES







A
HIGH FORWARD REACH LIMIT




NOTE:
X SHALL BE < 25", **Z** SHALL BE > **X**
WHEN **X** < 20", **Y** SHALL BE 48" MAX,
WHEN **X** IS 20" - 25",
Y SHALL BE 44" MAX




B
MAXIMUM FORWARD REACH OVER OBSTRUCTION




C
HIGH & LOW SIDE REACH LIMITS




D
MAXIMUM SIDE REACH OVER OBSTRUCTION




E
CLEAR FLOOR SPACE PARALLEL APPROACH




F
DIAMETER SPACE



G
MINIMUM CLEAR WIDTH FOR SINGLE WHEELCHAIR




H
MINIMUM CLEAR WIDTH FOR TWO WHEELCHAIRS




J
T-SHAPE SPACE FOR 180 DEGREE TURNS


DOOR CLEARANCES



FRONT APPROACH




HINGE APPROACH




LATCH APPROACH

DRINKING FOUNTAINS




A
SPOUT HEIGHT AND KNEE CLEARANCE


NOTE: EQUIPMENT PERMITTEDIN SHADED AREA



B
CLEAR FLOOR SPACE





C
FREE-STANDING FOUNTAIN OR COOLER




D
BUILT-IN FOUNTAIN OR COOLER


PROTRUDING OBJECTS






A
WALKING PARALLEL TO A WALL






NOTE A: THIS OVERHANG CAN BE GREATER THAN 12" BECAUSE NO ONE CAN APPROACH THE OBJECT FROM THIS DIRECTION

B
OBJECTS MOUNTED ON POST OR PYLONS



C
EXAMPLE OF PROTECTION AROUND WALL-MOUNTED OBJECTS



D
FREE-STANDING OVERHANG OBJECTS

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. [redacted]
REGISTERED ARCHITECT

ADA DIAGRAMS & MOUNTING HEIGHTS

UPS SAV TENANT IMPROVEMENT


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1


02/20/2026
ISSUED FOR CONSTRUCTION


A G-004

© 2025 STRATUS®


TOILET STALLS









A
TOILET STALLS NEW CONSTRUCTION






B
STANDARD STALL





C
ALTERNATE STALLS

NOTES:
A. 56" MINIMUM IF WATER CLOSET IS WALL-MOUNTED. 59" MINIMUM IF FLOOR MOUNTED.
B. 42" MINIMUM IF LATCH APPROACH. OTHER APPROACHES ARE 48" MINIMUM.
C. 66" MINIMUM IF WATER CLOSET IS WALL-MOUNTED. 69" MINIMUM IF FLOOR MOUNTED.


WATER CLOSETS









A
CLEAR FLOOR SPACE AT WATER CLOSETS (NOT IN A STALL)





B
GRAB BARS AT WATER CLOSETS

MOUNTING HEIGHTS




WALL MOUNTED ADJUSTABLE HEIGHT COMPUTER



FIRE ALARM PULL (NFPA 72 17.14.4)



FIRE ALARM SPEAKER & STROBE




TYPICAL DEVICE ALIGNMENT




CARD READER (ADA COMPLIANT: 308.2.1 / 308.3.1)




DOOR ACTUATOR (ADA COMPLIANT: 308.2.1 / 308.3.1)




COAT HOOK (ADA COMPLIANT: 213.3.7 / 603.4)



FIRE EXTINGUISHER CABINET



RECESSED SPECIMEN PASS THROUGH




PAPER TOWEL DISPENSER (ADA COMPLIANT 308.2.2)




HAND SANITIZER / SOAP DISPENSER (ADA COMPLIANT 308.2.2)




TOILET PAPER DISPENSER




SANITARY NAPKIN DISPENSER




MIRROR




SEAT COVER DISPENSER



MOP SINK



LOCKER



ADA BENCH (42" LONG MIN)

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035234
REGISTERED ARCHITECT

ADA DIAGRAMS & MOUNTING HEIGHTS

UPS SAV TENANT IMPROVEMENT


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION


G-005

3/19/2026 4:45:31 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA- TI.rvt

© 2025 STRATUS®




A.1 — NON-RATED:
5/8" GYP. BD. ON 6" METAL STUD FRAMING TO 13' AFF WITH THERMAL INSULATION
TOTAL WIDTH: 7-1/4"




B.1 — NON-RATED:
5/8" GYP. BD. ON 3-5/8" METAL STUD FRAMING TO 13' AFF
WITH SOUND ATTENUATION
TOTAL WIDTH: 4-1/4"

B.2 — NON-RATED:
5/8" GYP. BD. ON 3-5/8" METAL STUD FRAMING TO 13' AFF
TOTAL WIDTH: 4-1/4"



C.1 — NON-RATED:
5/8" GYP. BD. ON 3-5/8" METAL STUD FRAMING TO 13' AFF
WITH THERMAL INSULATION
TOTAL WIDTH: 4-1/4"



D.1 — NON-RATED:
5/8" GYP. BD. ON 3-5/8" METAL STUD FRAMING TO 13' AFF
WITH SOUND ATTENUATION
TOTAL WIDTH: 4-7/8"

D.2 — NON-RATED:
5/8" GYP. BD. ON 3-5/8" METAL STUD FRAMING TO 13' AFF
TOTAL WIDTH: 4-7/8"

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035254
REGISTERED ARCHITECT

UPS SAV TENANT IMPROVEMENT

WALL TYPES


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

A G-006

3/19/2026 4:45:31 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®



1 LIFE SAFETY PLAN - OVERALL
G-101 1/8" = 1'-0"

OCCUPANCY CLASSIFICATION

AREA #	ROOM NAME	AREA	FUNCTION OF SPACE	OCCUPANT LOAD FACTOR	OCCUPANT LOAD	REQUIRED EXITS	PROVIDED EXITS	ACCESSORY OR INCIDENTAL
01	GSE AREA	2163 SF	2024 NFPA - INDUSTRIAL - GENERAL & HIGH HAZARD	100 SF (GROSS)	21.63			
02	WAREHOUSE	9529 SF	2024 NFPA - INDUSTRIAL - GENERAL & HIGH HAZARD	100 SF (GROSS)	95.29			
03	BUSINESS AREA 01	1060 SF	2024 NFPA - BUSINESS - GENERAL	150 SF (GROSS)	7.07			
04	STORAGE AREA 01	43 SF	2024 NFPA - STORAGE - OTHER THAN STORAGE OR MERCANTILE	500 SF (GROSS)	0.09			
05	BUSINESS AREA 02	297 SF	2024 NFPA - BUSINESS - GENERAL	150 SF (GROSS)	1.98			
06	STORAGE AREA 02	1506 SF	2024 NFPA - STORAGE - OTHER THAN STORAGE OR MERCANTILE	500 SF (GROSS)	3.01			
07	BUSINESS AREA 03	292 SF	2024 NFPA - BUSINESS - GENERAL	150 SF (GROSS)	1.95			
TOTAL:					131.01			

TRAVEL DISTANCES

EGRESS PATH	DOOR #	LENGTH
A	100	73' - 1"
B	EX02	69' - 8"
B	EX04	66' - 6"


COMMON PATH OF TRAVEL

EGRESS PATH	LENGTH
A	73' - 1"

PLUMBING CALCULATIONS

AREA #	ROOM NAME	PLUMBING CLASSIFICATION NO	CLASSIFICATION	DESCRIPTION	OCCUPANT LOAD	SEX CALCULATIONS RATIO % OF MEN	RATIO % OF WOMEN	RATIO EQUAL SEX	TOTAL MEN	TOTAL WOMEN	MINIMUM NUMBER OF REQUIRED PLUMBING FIXTURES WATER CLOSETS MEN	WATER CLOSETS WOMEN	LAVATORIES MEN	LAVATORIES WOMEN	BATHTUBS & SHOWERS	DRINKING FOUNTAINS	OTHER
01	GSE AREA	4	FACTORY AND INDUSTRIAL	STRUCTURES IN WHICH OCCUPANTS ARE ENGAGED IN WORK FABRICATING, ASSEMBLY, OR PROCESSING OF PRODUCTS OR MATERIALS	21.63			Yes	10.82	10.82	0.11	0.11	0.11	0.11		0.05	1 SERVICE SINK
02	WAREHOUSE	4	FACTORY AND INDUSTRIAL	STRUCTURES IN WHICH OCCUPANTS ARE ENGAGED IN WORK FABRICATING, ASSEMBLY, OR PROCESSING OF PRODUCTS OR MATERIALS	95.29			Yes	47.65	47.65	0.48	0.48	0.48	0.48		0.24	1 SERVICE SINK
03	BUSINESS AREA 01	2	BUSINESS	BUILDINGS FOR THE TRANSACTION OF BUSINESS, PROFESSIONAL SERVICES, OTHER SERVICES INVOLVING MERCHANDISE, OFFICE BUILDINGS, BANKS, LIGHT INDUSTRIAL, AMBULATORY CARE AND SIMILAR USES	7.07			Yes	3.53	3.53	0.14	0.14	0.09	0.09		0.07	1 SERVICE SINK
04	STORAGE AREA 01	8	STORAGE	STRUCTURES FOR THE STORAGE OF GOODS, WAREHOUSES, STOREHOUSES AND FREIGHT DEPOTS, LOW AND MODERATE HAZARD	0.09			Yes	0.04	0.04	0.00	0.00	0.00	0.00		0.00	1 SERVICE SINK
05	BUSINESS AREA 02	2	BUSINESS	BUILDINGS FOR THE TRANSACTION OF BUSINESS, PROFESSIONAL SERVICES, OTHER SERVICES INVOLVING MERCHANDISE, OFFICE BUILDINGS, BANKS, LIGHT INDUSTRIAL, AMBULATORY CARE AND SIMILAR USES	1.98			Yes	0.99	0.99	0.04	0.04	0.02	0.02		0.02	1 SERVICE SINK
06	STORAGE AREA 02	8	STORAGE	STRUCTURES FOR THE STORAGE OF GOODS, WAREHOUSES, STOREHOUSES AND FREIGHT DEPOTS, LOW AND MODERATE HAZARD	3.01			Yes	1.51	1.51	0.02	0.02	0.02	0.02		0.00	1 SERVICE SINK
07	BUSINESS AREA 03	2	BUSINESS	BUILDINGS FOR THE TRANSACTION OF BUSINESS, PROFESSIONAL SERVICES, OTHER SERVICES INVOLVING MERCHANDISE, OFFICE BUILDINGS, BANKS, LIGHT INDUSTRIAL, AMBULATORY CARE AND SIMILAR USES	1.95			Yes	0.97	0.97	0.04	0.04	0.02	0.02		0.02	1 SERVICE SINK
TOTAL REQUIRED:					131.01				65.51	65.51	0.82	0.82	0.74	0.74	0.00	0.41	

LIFE SAFETY LEGEND



UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035234
REGISTERED ARCHITECT

NOTE:
REV: A
DATE: 03/18/2026
ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION


G-101

OVERALL LIFE SAFETY PLAN

UPS SAV TENANT IMPROVEMENT

3/19/2026 4:45:36 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®



1 / AD-101 LEVEL 1 - DEMOLITION
3/32" = 1'-0"

0 5'-4" 10'-8" 21'-4"
SCALE: 3/32" = 1'-0"

DEMOLITION GENERAL NOTES:

A. REMOVE EXISTING CONSTRUCTION AS REQUIRED FOR EXTENTS AS INDICATED.

B. THE CONTRACTOR SHALL PROTECT AREAS AND CONSTRUCTION INDICATED TO REMAIN FROM DAMAGE DURING DEMOLITION AND NEW CONSTRUCTION.

C. THE CONTRACTOR SHALL PATCH, REPAIR AND FINISH AS REQUIRED ANY AREAS, SURFACES OR MATERIALS DAMAGED DURING DEMOLITION THAT ARE INTENDED TO REMAIN.

D. THE CONTRACTOR SHALL FIELD VERIFY EXISTING PROJECT CONDITIONS AND DIMENSIONS PRIOR TO BEGINNING WORK AND SHALL INFORM ARCHITECT IMMEDIATELY IN WRITING OF ANY DISCREPANCIES OR CONDITIONS NOT SHOWN IN DRAWINGS OR IN CONFLICT WITH INTENT OF THE WORK PRIOR TO PROCEEDING WITH THAT PORTION OF THE WORK. ONLY ITEMS FOUND BELOW SLABS, NOT ACCESSIBLE TO REVIEW OR DESCRIBED IN DRAWINGS AND IN CONFLICT WITH NEW WORK SHALL BE CONSIDERED FOR ADDITIONAL COMPENSATION.

E. ALL SITE ACCESS, SITE USE, WORK AND ACTIVITIES SHALL BE COORDINATED AND SCHEDULED WITH THE OWNER TO AVOID INTERRUPTION OF FACILITY WORK FLOW AND ACCESS.

F. DEBRIS RESULTING FROM DEMOLITION SHALL BE REMOVED ON A DAILY BASIS TO A WASTE AREA PROVIDED BY THE CONTRACTOR. ALL MATERIAL SHALL BE DISPOSED OF PROPERLY.

G. DUMPSTER AND STAGING/MATERIAL AREAS OR LOCATIONS SHALL BE PROVIDED BY THE CONTRACTOR AT LOCATIONS COORDINATEDWITH THE OWNER TO AVOID INTERRUPTION OF ACTIVITIES OR ACCESS.

H. ALL WORK SHALL BE DONE IN COMPLIANCE WITH CURRENT APPLICABLE CODES FOR THE CODE AUTHORITY HAVING JURISDICTION.

DEMOLITION KEY NOTES:

#	NOTE
03	TRENCH FLOOR AS REQUIRED - SEE DETAIL 4/A-600. REFERENCE PLUMBING DRAWINGS FOR MORE INFORMATION.

PROJECT NORTH

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035234
REGISTERED ARCHITECT

EXISTING CONDITIONS & DEMOLITION FLOOR PLAN - FIRST FLOOR

UPS SAV TENANT IMPROVEMENT


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

AD-101

3/19/2026 4:45:39 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA- T1.rvt

© 2025 STRATUS®



1 OVERALL FIRST FLOOR PLAN
A-101 3/32" = 1'-0"

GENERAL NOTES:

A. PARTITION TYPES ARE DESCRIBED ON SHEET G-005.

B. ALL GYPSUM BOARD TO BE USED ON THE NEW CONSTRUCTION IS TO BE 5/8" THICK. PROVIDE CORNER REINFORCEMENT AT EXPOSED OUTSIDE CORNERS.

C. DIMENSIONS ARE FROM FACE OF BASE BUILDING & EXISTING PARTITIONS TO FACE OF NEW STUDS UNLESS NOTED OTHERWISE.

D. ALL ANGLES SHALL BE 90 DEGREES, UNLESS OTHERWISE NOTED.

E. DOOR JAMBS ARE TO BE 6" FROM ADJACENT WALL UNLESS NOTED OTHERWISE.

F. WHEN DIFFERENT PARTITION TYPES ARE LOCATED ADJACENT TO ONE ANOTHER, THE FINISHED FACES OF THE PARTITIONS SHALL BE ALIGNED AND FLUSH UNLESS NOTED OTHERWISE.

G. PROVIDE BRACING ABOVE CEILING HEIGHT PARTITIONS WHEN LONG UNBRACED WALL LENGTHS OCCUR AND AT ALL DOOR AND GLAZED OPENING JAMBS IN ACCORDANCE WITH MANUFACTURERS' SPECIFICATIONS.

H. PROVIDE FIRE RETARDANT WOOD BLOCKING INSIDE PARTITIONS FOR SECURING WALL-HUNG CABINETS, SHELVING AND OTHER MILLWORK ATTACHED TO THE PARTITIONS.

J. ALL FINISHED DRYWALL WORK TO BE LEVEL 4 FINISH. LEVEL 5 FINISH LOCATIONS DENOTED ON SIGNAGE/ARTWORK FLOOR PLAN, SHEET A151.

K. ALL EXISTING DOORS TO REMAIN ARE DESIGNATED AS 'E'.

L. PROVIDE WOOD BLOCKING WHERE THERE ARE MONITORS AND MARKER BOARDS. CONTRACTOR MUST VERIFY MONITOR AND MARKER BOARD LOCATIONS WITH OWNER TO ENSURE WOOD BLOCKING IS INSTALLED IN THE CORRECT LOCATIONS.

M PLACE MIN. R-38 BATT INSULATION AT CEILING LEVEL ABOVE ALL CONDITIONED SPACES.

KEY NOTES:

#	NOTE
01	CHAINLINK FENCE TO UNDERSIDE OF STRUCTURE ABOVE.
02	DIAGONAL HATCH INDICATES EXTENTS OF THICKENED SLAB-ON-GRADE.
04	COMBO EYE WASH & SHOWER - REF PLUMBING DRAWINGS FOR MORE INFORMATION
05	UTILITY SINK - REF PLUMBING DRAWINGS FOR MORE INFORMATION

0 5'-4" 10'-8" 21'-4"
SCALE: 3/32" = 1'-0"

PROJECT NORTH

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035254
REGISTERED ARCHITECT

OVERALL FIRST FLOOR PLAN

UPS SAV TENANT IMPROVEMENT


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

A-101

3/19/2026 4:45:38 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - T1.rvt

© 2025 STRATUS®



1 BUILDING SECTION - THROUGH OFFICE
A-301
1/4" = 1'-0"

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 033234
REGISTERED ARCHITECT

UPS SAV TENANT IMPROVEMENT

WALL SECTION


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

A-301

3/19/2026 4:45:40 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®



1 ENLARGED OFFICE FIRST FLOOR PLAN
A-401 1/4" = 1'-0"

SCALE: 1/4" = 1'-0"

GENERAL NOTES:

A. PARTITION TYPES ARE DESCRIBED ON SHEET G-005.

B. ALL GYPSUM BOARD TO BE USED ON THE NEW CONSTRUCTION IS TO BE 5/8" THICK. PROVIDE CORNER REINFORCEMENT AT EXPOSED OUTSIDE CORNERS.

C. DIMENSIONS ARE FROM FACE OF BASE BUILDING & EXISTING PARTITIONS TO FACE OF NEW STUDS UNLESS NOTED OTHERWISE.

D. ALL ANGLES SHALL BE 90 DEGREES, UNLESS OTHERWISE NOTED.

E. DOOR JAMBS ARE TO BE 6" FROM ADJACENT WALL UNLESS NOTED OTHERWISE.

F. WHEN DIFFERENT PARTITION TYPES ARE LOCATED ADJACENT TO ONE ANOTHER, THE FINISHED FACES OF THE PARTITIONS SHALL BE ALIGNED AND FLUSH UNLESS NOTED OTHERWISE.

G. PROVIDE BRACING ABOVE CEILING HEIGHT PARTITIONS WHEN LONG UNBRACED WALL LENGTHS OCCUR AND AT ALL DOOR AND GLAZED OPENING JAMBS IN ACCORDANCE WITH MANUFACTURERS' SPECIFICATIONS.

H. PROVIDE FIRE RETARDANT WOOD BLOCKING INSIDE PARTITIONS FOR SECURING WALL-HUNG CABINETS, SHELVING AND OTHER MILLWORK ATTACHED TO THE PARTITIONS.

J. ALL FINISHED DRYWALL WORK TO BE LEVEL 4 FINISH. LEVEL 5 FINISH LOCATIONS DENOTED ON SIGNAGE/ARTWORK FLOOR PLAN, SHEET A151.

K. ALL EXISTING DOORS TO REMAIN ARE DESIGNATED AS 'E'.

L. PROVIDE WOOD BLOCKING WHERE THERE ARE MONITORS AND MARKER BOARDS. CONTRACTOR MUST VERIFY MONITOR AND MARKER BOARD LOCATIONS WITH OWNER TO ENSURE WOOD BLOCKING IS INSTALLED IN THE CORRECT LOCATIONS.

M PLACE MIN. R-38 BATT INSULATION AT CEILING LEVEL ABOVE ALL CONDITIONED SPACES.

KEY NOTES:

#	NOTE
01	CHAINLINK FENCE TO UNDERSIDE OF STRUCTURE ABOVE.
02	DIAGONAL HATCH INDICATES EXTENTS OF THICKENED SLAB-ON-GRADE.
04	COMBO EYE WASH & SHOWER - REF PLUMBING DRAWINGS FOR MORE INFORMATION
05	UTILITY SINK - REF PLUMBING DRAWINGS FOR MORE INFORMATION

PROJECT NORTH

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 031234
REGISTERED ARCHITECT

UPS SAV TENANT IMPROVEMENT

ENLARGED OFFICE FIRST FLOOR PLAN


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

A-401

3/19/2026 4:45:42 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®



1 ENLARGED OFFICE REFLECTED CEILING PLAN
A-402 1/4" = 1'-0"

CEILING GENERAL NOTES:

A. THIS REFLECTED CEILING PLAN IS PROVIDED TO DOCUMENT CEILING DESIGN INTENT. SEE ALSO MECHANICAL AND ELECTRICAL DOCUMENTATION FOR COMPLETE INFORMATION, INCLUDING SWITCH LOCATIONS, CIRCUITING, AND WIRING LAYOUT. ALL MEP-FP DEVICE LOCATIONS NOT SHOWN ON DRAWINGS OR IN CONFLICT WITH MEP-FP DRAWINGS ARE TO BE COORDINATED WITH THE ARCHITECT PRIOR TO INSTALLATION. IN THE EVENT OF DISCREPANCIES BETWEEN ARCHITECTS' REFLECTED CEILING PLAN AND ENGINEER'S PLANS, IMMEDIATELY NOTIFY THE ARCHITECT IN WRITING BEFORE ORDERING MATERIALS OR PROCEEDING WITH THE WORK.

B. FOLLOWING COMPLETION OF THE ACOUSTICAL CEILING INSTALLATION, ALL JOINTS AND GRID SHALL BE STRAIGHT, TRUE TO LINE, WITH EXPSED SURFACES FLUSH AND LEVEL. DAMAGED, DIRTY OR DISCOLORED TILES ARE TO BE CLEANED OR REPLACED, AND LEFT FREE OF DEFECTS. AFTER 30 DAYS FROM SUBSTANTIAL COMPLETION, THE CONTRACTOR SHALL INSPECT THE WORK AND ADJUST THE TILE AS REQUIRED.

C. WITHIN A ROOM OR AREA, THE CONTRACTOR SHALL ESTABLISH A SINGLE FLOOR ELEVATION THAT IS TO BE USED AS THE ORIGIN FOR ALL CEILING HEIGHTS ABOVE FINISHED FLOOR.

D. VERIFY FIELD CONDITIONS AND LOCATIONS OF ALL MEP-FP AND STRUCTURAL ELEMENTS. CONTRACTOR TO COORDINATOR TO COORDINATE THE WORK OF ALL TRADES NECESSARY TO MAINTAIN THE FINISH CEILING HEIGHTS INDICATED. INSTALL DUCTWORK TIGHT TO UNDERSIDE OF STRUCTURE IN SMALL SPACES TO AVOID VIBRATION. INSTALLATION OR ALTERNATION OF DUCTWORK, PIPING, OR OTHER EQUIPMENT THAT WILL REQUIRE FASCIAS, SOFFITS AND OTHER TRANSITIONS IN CEILING HEIGHT SHALL BE REVIEWED WITH THE ARCHITECT PRIOR TO PROCEEDING. CONTRACTOR TO PROVIDE COMPLETE COORDINATION DRAWINGS FOR THE ARCHITECT AND ENGINEER'S REVIEW PRIOR TO BEGINNING WORK.

E. PROVIDE SMOKE DETECTORS THROUGHOUT TENANT AREAS IN ACCORDANCE WITH LOCAL CODES AND MANUFACTURER'S RECOMMENDATIONS. SEE ELECTRICAL DRAWINGS.

F. ALL CEILING MOUNTED DEVICES SHALL BE WHITE.

G. PROVIDE BLOCKING ABOVE CEILING REQUIRED FOR ALL CEILING MOUNTED EQUIPMENT. PROVIDE ADDITIONAL SUPPORT FOR LIGHT FIXTURE AS RECOMMENDED BY FIXTURE MANUFACTURER.

H. LOCATE ANY ABOVE CEILING CONTROLS THAT NEED ACCESSING ABOVE ACOUSTICAL TILE CEILING AREAS. DO NOT PLACE ANY CONTROL DEVICES ABOVE GYPSUM BOARD CEILINGS UNLESS APPROVED BY ARCHITECT. ABOVE CELING AL EQUIPMENT AND CONTROLS SHALL HAVE ADEQUATE ACCESS BY PANELS PER EQUIPMENT MANUFACTURER RECOMMENDATIONS OR REQUIREMENTS.

I. WHEN MULTIPLE SWITCHES OCCUR IN CLOSE PROXIMITY, GANG UNDER SINGLE SWITCH PLATE

J. INSTALL NEW THERMOSTATS CLOSE TO DOOR OPENINGS. DO NOT INSTALL IN CENTER OF WALL. ARCHITECTS AND CLIENT TO APPROVE ALL LOCATIONS

K. ALL LIGHTS TO BE CONTROLLED BY MOTION SENSOR. PROVIDE OVERRIDE SWITCH AT ALL CONFERENCE ROOMS.

M PLACE MIN. R-38 BATT INSULATION AT CEILING LEVEL ABOVE ALL CONDITIONED SPACES.

KEY NOTES:

#	NOTE
01	CHAINLINK FENCE TO UNDERSIDE OF STRUCTURE ABOVE.
02	DIAGONAL HATCH INDICATES EXTENTS OF THICKENED SLAB-ON-GRADE.
04	COMBO EYE WASH & SHOWER - REF PLUMBING DRAWINGS FOR MORE INFORMATION
05	UTILITY SINK - REF PLUMBING DRAWINGS FOR MORE INFORMATION



0 2'-0" 4'-0" 8'-0"
SCALE: 1/4" = 1'-0"

PROJECT NORTH

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035234
REGISTERED ARCHITECT

ENLARGED OFFICE REFLECTED CEILING PLAN

UPS SAV TENANT IMPROVEMENT


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION


A-402

3/19/2026 4:45:43 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt


© 2025 STRATUS®



1 ENLARGED RESTROOM PLAN
A-403 1/2" = 1'-0"



2 INTERIOR ELEVATION - MOTHER'S ROOM
A-403 1/2" = 1'-0"



3 ENLARGED PLAN - PLUMBING WALL
A-403 1/2" = 1'-0"

RESTROOM FIXTURE SCHEDULE

#	DESCRIPTION	FURNISH OWNER	FURNISH GC	INSTALL OWNER	INSTALL GC	REMARKS
P1	WALL HUNG LAVATORY		•		•	REFERENCE PLUMBING DRAWINGS
P2	WALL HUNG URINAL		•		•	REFERENCE PLUMBING DRAWINGS
P3	WALL HUNG WATER CLOSET		•		•	REFERENCE PLUMBING DRAWINGS
P3A	WALL HUNG WATER CLOSET - ADA		•		•	REFERENCE PLUMBING DRAWINGS
P4	48" GRAB BAR		•		•	
P5	36" GRAB BAR		•		•	
P6	18" GRAB BAR		•		•	
P7	PAPER TOWEL DISPENSER	•			•	
P8	MIRROR		•		•	
P9	SOAP DISPENSER	•			•	
P10	TOILET SEAT COVER DISPENSER	•			•	
P11	TOILET PAPER DISPENSER	•			•	
P12	ADA SHOWER STALL		•		•	PRE-FABRICATED 3-SIDED FBIERGLASS SHOWER ENCLOSURE WITH INTEGRAL PAN AND DRAIN ASSEMBLY - BASIS OF DESIGN: FREEDOM SHOWERS MODEL APF3838BF1PRRF
P13	LOCKER		•		•	
P14	ADA BENCH		•		•	
P15	MOP SINK		•		•	
P16	SANITARY NAPKIN DISPOSAL	•			•	
P17	UNDERMOUNT KITCHEN SINK		•		•	REFERENCE PLUMBING DRAWINGS
P18	UNDERCOUNTER REFRIGERATOR	•			•	
P19	MOTHER'S SIDE TABLE	•		•		CORPORATE ENVIRONMENTS MUUTO AROUND SIDE TABLE, TOP AND LEG FINISH SELECTION BY OWNER.
P20	MOTHER'S CHAIR	•		•		CORPORATE ENVIRONMENTS CAROLINA SEEK CHAIR, FABRIC AND COLOR SELECTION BY OWNER
P21	HI-LO DRINKING FOUNTAIN		•		•	

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035234
REGISTERED ARCHITECT

NOTE:
REV: A
DATE: 03/18/2026
ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION


ENLARGED RESTROOM PLANS AND ELEVATIONS

UPS SAV TENANT IMPROVEMENT

A-403

3/19/2026 4:45:45 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®



1 ENLARGED RESTROOM REFLECTED CEILING PLAN
A-404 1/2" = 1'-0"

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035234
REGISTERED ARCHITECT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

ENLARGED RESTROOM REFLECTED CEILING PLAN

UPS SAV TENANT IMPROVEMENT

A-404


3/19/2026 4:45:47 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®


DOOR SCHEDULE


GENERAL INFO		NOMINAL DIMENSIONS			DOOR			FRAME			DETAIL			HW SET	COMMENTS
MARK	DESCRIPTION	WIDTH	HEIGHT	THICKNESS	TYPE	MATERIAL	FINISH	TYPE	MATERIAL	FINISH	HEAD	JAMB	SILL		
001	GSE AREA	3' - 0"	7' - 0"	0' - 2"	-	CHAINLINK	-	-	-	-	-	-	-	-	
100	MOTHER'S ROOM	3' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-6	
101	UNISEX	3' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-6	
102	WOMENS RESTROOM	3' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-6	
103	JANITOR'S	3' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-7	PROVIDE 180 DEGREE HINGE
104	MENS RESTROOM	3' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-6	
105	MENS SHOWER	3' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-6	
106	WOMENS SHOWER	3' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-6	
108A	ACMX NON-CLIMATE CONTROL PARTS STORAGE	6' - 0"	7' - 0"	0' - 2"	A CC	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-5	
108B	ACMX NON-CLIMATE CONTROL PARTS STORAGE	3' - 0"	7' - 0"	0' - 2"	C	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-5	
109	ACMX CLIMATE CONTROL PARTS STORAGE	3' - 0"	7' - 0"	0' - 2"	C	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-5	
110B	MANAGEMENT OFFICE	3' - 0"	7' - 0"	0' - 2"	C	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-5	
111	TSG SERVER	4' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-7	
112	FLIGHT	3' - 0"	7' - 0"	0' - 2"	B	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-5	
113	TRAINING ROOM	3' - 0"	7' - 0"	0' - 2"	A C	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-5	
114	SECURITY EMPLOYEE ENTRANCE	3' - 0"	7' - 0"	0' - 2"	C	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-5	
115	CORRIDOR	3' - 0"	7' - 0"	0' - 2"	C	HM	PT-3	1	HM	PT-3	1/A-600	2/A-600	3/A-600	HS-5	
EX01	EXISTING PERSONNEL DOOR	3' - 0"	7' - 0"	0' - 2"	EX	EX	EX	EX	EX	EX	EX	EX	EX	EX	
EX02	EXISTING PERSONNEL DOOR	3' - 0"	7' - 0"	0' - 2"	EX	EX	EX	EX	EX	EX	EX	EX	EX	EX	
EX03	EXISTING PERSONNEL DOOR	3' - 0"	7' - 0"	0' - 2"	EX	EX	EX	EX	EX	EX	EX	EX	EX	EX	
EX04	EXISTING PERSONNEL DOOR	3' - 0"	8' - 0"	0' - 2"	EX	EX	EX	EX	EX	EX	EX	EX	EX	EX	

DOOR TYPES




DOOR FRAME TYPES






4 SLAB PATCHING DETAIL (A-600) 1" = 1'-0"




5 ROOF FLASHING DETAIL (A-600) 1 1/2" = 1'-0"




1 INTERIOR DOOR HEAD (A-600) 3" = 1'-0"


2 INTERIOR DOOR JAMB (A-600) 3" = 1'-0"



3 SILL/FLOOR TRANSITIONS (A-600) 6" = 1'-0"



6 TRAINING ROOM COUNTER (A-600) 1 1/2" = 1'-0"



7 BASE CABINET-SINK (A-600) 1 1/2" = 1'-0"

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035254
REGISTERED ARCHITECT

UPS SAV TENANT IMPROVEMENT

DOOR SCHEDULES & DETAILS

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

A-600

3/19/2026 4:45:48 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®



1 ENLARGED OFFICE FIRST FLOOR FINISH PLAN
A-701 1/4" = 1'-0"

A

FINISH SCHEDULE

NOTE: SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION

SYMBOL	TYPE	MANUFACTURER INFO	REMARKS
FRP	FIBERGLASS REINFORCED PLASTIC PANELING		
PT-1	PAINT; SHERWIN WILLIAMS		
RB-1	RUBBER WALL BASE; ROPPE	BLACK BROWN #193	
SC-1	SEALED POLISHED CONCRETE		

UNITED PARCEL SERVICE INC.

A

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. [redacted]
REGISTERED ARCHITECT

ENLARGED OFFICE FIRST FLOOR FINISH PLAN

UPS SAV TENANT IMPROVEMENT


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

A-701

3/19/2026 4:45:51 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®



1 ENLARGED RESTROOM FINISH PLAN
A-702
1/2" = 1'-0"

A

FINISH SCHEDULE

NOTE: SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION

SYMBOL	TYPE	MANUFACTURER INFO	REMARKS
FRP	FIBERGLASS REINFORCED PLASTIC PANELING		
PT-1	PAINT; SHERWIN WILLIAMS		
RB-1	RUBBER WALL BASE; ROPPE	BLACK BROWN #193	
SC-1	SEALED POLISHED CONCRETE		

UNITED PARCEL SERVICE INC.

A

STRATUS®
3715 NORTHSIDE PARKWAY, NW
B [redacted] 00

DES: JD CHK: JG DRW: JD

2025-1073

Seal

STATE OF GEORGIA
JASON MICHAEL GARZA
CERTIFICATE NO. 035234
REGISTERED ARCHITECT

ENLARGED RESTROOM FINISH PLAN

UPS SAV TENANT IMPROVEMENT

REV: A
DATE: 03/18/2026
NOTE: ADDENDUM 1

02/20/2026
ISSUED FOR CONSTRUCTION

A-702

3/19/2026 4:45:53 PM Autodesk Docs://UPS SAV Interior Renovations/UPS - SAVANNAH, GA - TI.rvt

© 2025 STRATUS®

GENERAL PLUMBING NOTES:

ADMINISTRATIVE:

1. THE FOLLOWING ABBREVIATIONS SHALL APPLY TO NOTES AND PLANS:
   PC - PLUMBING CONTRACTOR,
   EC - ELECTRICAL CONTRACTOR,
   MC - MECHANICAL CONTRACTOR,
   GC - GENERAL CONTRACTOR,
   FASC - FIRE ALARM SYSTEM CONTRACTOR.
   SPC- CURRENT STATE PLUMBING CODE (INTERNATIONAL PLUMBING CODE WITH GEORGIA AMENDMENTS)
2. "PROVIDE" MEANS TO FURNISH AND INSTALL. THE PLUMBING CONTRACTOR SHALL ALSO INSTALL MATERIALS FURNISHED BY OTHERS AND THE GENERAL CONTRACTOR.
3. THE PC SHALL BE RESPONSIBLE FOR A COMPLETE AND OPERATIONAL SYSTEM AS DESCRIBED BY THESE PLANS AND SPECIFICATIONS.
4. ALL MATERIALS AND EQUIPMENT SHALL BE DELIVERED TO THE SITE AND UNLOADED AT AN APPROVED LOCATION. PC SHALL PROTECT ALL MATERIALS AND EQUIPMENT FROM BREAKAGE, THEFT, AND THE ELEMENTS. ALL MATERIALS AND EQUIPMENT SHALL REMAIN THE PROPERTY OF THE PC UNTIL THE PROJECT HAS BEEN COMPLETED AND TURNED OVER TO THE OWNER.
5. ALL MATERIALS USED SHALL BE NEW AND FREE OF DEFECTS. ANY MATERIALS FOUND TO BE DEFECTIVE SHALL BE REPLACED AT NO EXPENSE TO THE OWNER. ALL MATERIALS AND EQUIPMENT SHALL BEAR APPROVAL FROM UL OR AN APPROVED THIRD-PARTY AGENCY. WHERE A MANUFACTURER AND MODEL NUMBER IS GIVEN, IT IS TO ESTABLISH A STANDARD OF QUALITY AND NOT TO LIMIT PRODUCTS TO A PARTICULAR MANUFACTURER. PRODUCTS DETERMINED TO BE EQUAL BY THE ENGINEER WILL BE ACCEPTED.
6. THE PLUMBING SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH THE SPC AND ANY APPLICABLE LOCAL CODES. WHERE A CONFLICT EXISTS BETWEEN THE ABOVE REQUIREMENTS, THE CONTRACTOR SHALL OBTAIN CLARIFICATION FROM THE ENGINEER OR IN THE EVENT ANY PART OF THESE PLANS CONFLICTS WITH THE ABOVE REQUIREMENTS.
7. THE PC SHALL OBTAIN AND PAY FOR ALL PERMITS, FEES, AND INSPECTIONS NECESSARY FOR THE COMPLETION OF THE WORK UNDER THIS CONTRACT.
8. DO NOT SCALE THESE DRAWINGS-REFER TO ARCHITECTURAL SHEETS FOR DIMENSIONS.
9. THESE PLANS ARE DIAGRAMMATIC. THE PC SHALL ADJUST THE LOCATIONS OF EQUIPMENT, FIXTURES, PIPING, ETC, TO ACCOMMODATE PLANNED AND ENCOUNTERED INTERFERENCES. THE DRAWINGS DO NOT SHOW ALL BENDS, OFFSETS, AND FITTINGS THAT MAY BE REQUIRED FOR A COMPLETE AND OPERATIONAL SYSTEM. THE PC SHALL MAKE ALLOWANCES FOR SUCH DEVIATIONS AND CONTINGENCIES IN BID TO IMPLEMENT THEM WITHOUT ADDITIONAL COST TO THE OWNER.
10. THE PC SHALL VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH EXISTING CONDITIONS. CONTRACTOR SHALL CONTACT THE ENGINEER TO RESOLVE ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS AND THESE PLANS. TO AVOID POTENTIAL CONFLICTS, COORDINATE WITH OTHER TRADES PRIOR TO THE START OF CONSTRUCTION.
11. ALL UNDERGROUND UTILITIES SHALL BE LOCATED PRIOR TO ANY DIGGING.
12. TRENCHING, COMPACTION, AND BACKFILL SHALL BE BY PC AND SHALL BE IN ACCORDANCE WITH SECTION 306 OF THE SPC. UNDERGROUND LINES SHALL BE LOCATED SUCH THAT THEY DO NOT ENDANGER FOOTINGS OR FOUNDATION WALLS.
13. THE PC SHALL PROVIDE FIRESTOPPING AT ALL PENETRATIONS OF RATED FLOOR/CEILING ASSEMBLIES AND RATED WALL ASSEMBLIES TO PRESERVE OR RESTORE THE FIRE RESISTANCE RATING. SEAL ALL PENETRATIONS USING A UL LISTED SYSTEM FOUND IN THE UL DIRECTORY SPECIFIC TO THE UL LISTING OF THE ASSEMBLY BEING PENETRATED. SEE ARCHITECTURAL PLANS FOR UL RATED ASSEMBLIES SPECIFIC TO THE PROJECT.
14. SYSTEM TESTING SHALL BE PERFORMED BY PLUMBING CONTRACTOR IN ACCORDANCE WITH SPC, SECTIONS 312.2, 312.3, AND 312.5.
15. PC SHALL DISINFECT THE ENTIRE DOMESTIC WATER PIPING SYSTEM IN ACCORDANCE WITH THE AMERICAN WATER WORKS ASSOCIATION'S SPECIFICATIONS AND LOCAL HEALTH DEPARTMENT REGULATIONS.
16. AT THE COMPLETION OF WORK AND PRIOR TO ACCEPTANCE BY OWNER, THE PC SHALL CLEAN ALL EXPOSED FIXTURES, MATERIALS, AND EQUIPMENT UNDER THIS CONTRACT.
17. PC SHALL COORDINATE WITH THE GENERAL CONTRACTOR TO ENSURE ALL APPLICABLE CONSTRUCTION WASTE IS RECYCLED DURING THE CONSTRUCTION PHASE OF THE PROJECT.
18. ALL PLUMBING SCOPE IS WITHIN FIVE (5) FEET OF EXTERIOR OF BUILDING OR AS SHOWN ON PLANS.

METHODS:

1. EXTEND DOMESTIC WATER PIPE AS INDICATED ON THE PLANS AND INSTALL DOMESTIC WATER DISTRIBUTION PIPING TO ALL FIXTURES AND EQUIPMENT REQUIRING THE SAME. WATER SERVICE PIPE AND THE BUILDING SEWER SHALL BE SEPARATED BY 5 FEET OF UNDISTURBED OR COMPACTED EARTH IN ACCORDANCE WITH 603.2 SPC. PROVIDE ALL FITTINGS, VALVES, AND OTHER ACCESSORIES AS NECESSARY FOR A COMPLETE INSTALLATION. ALL DOMESTIC WATER PIPING SHALL BE CONCEALED IN FINISHED AREAS. ANY OPEN ENDS SHALL BE PROTECTED UNTIL FINAL CONNECTIONS ARE MADE.
2. ABOVE GRADE DOMESTIC WATER PIPING SHALL BE SLOPED AT A MINIMUM OF 1/32 INCH PER FOOT AND ARRANGED TO DRAIN AT LOW POINTS. INSTALL PIPING TO ALLOW FOR EXPANSION AND CONTRACTION WITHOUT STRESSING PIPE, JOINTS, OR CONNECTED EQUIPMENT. ROUTE PIPING IN AN ORDERLY MANNER-PARALLEL OR PERPENDICULAR TO WALLS WHEN POSSIBLE-AND MAINTAIN GRADIENT. EACH SUPPLY BRANCH LINE SERVING MORE THAN ONE FIXTURE SHALL HAVE A SHUTOFF VALVE INSTALLED TO ISOLATE ALL FIXTURES AND PIECES OF EQUIPMENT SUPPLIED BY THE BRANCH LINE. THE SHUTOFF VALVE SHALL BE LABELED AND LOCATED AS CLOSE TO THE CONNECTION TO THE SUPPLY MAIN AND RISER AS POSSIBLE. PROVIDE A FULL-OPEN VALVE ON THE BASE OF EVERY WATER RISER PIPE AND ON THE TOP OF EVERY WATER DOWN-FEED PIPE. PROVIDE VALVE HANDLE EXTENSIONS AS NECESSARY FOR INSULATION.
3. IT SHALL BE THE RESPONSIBILITY OF THE PC TO SUSPEND AND SUPPORT ALL PIPING SYSTEMS FOLLOWING RECOGNIZED ENGINEERING PRACTICES AND USING STANDARD, COMMERCIALLY ACCEPTED PIPE HANGERS AND SUSPENSION EQUIPMENT. ALL FIXTURES, DEVICES, AND EQUIPMENT SHALL BE SECURELY MOUNTED TO THE BUILDING STRUCTURE AND SHALL NOT RELY ON CEILING OR WALL SURFACES FOR SUPPORT. THE SUPPORT ATTACHMENT SHALL SUPPORT THE WEIGHT OF THE FIXTURE OR EQUIPMENT PLUS THE WEIGHT OF THE SUPPORT ATTACHMENT ITSELF. SUPPORT FROM THE TOP CHORD OF THE ROOF JOISTS, GIRDERS, AND BEAMS. THE BOTTOM CHORD IS NOT TO BE USED FOR EQUIPMENT AND PIPING SUPPORT. HANGERS SHALL NOT BE ATTACHED TO CORRUGATED STEEL DECKING. USE STEEL HANGERS FOR STEEL AND PLASTIC PIPE AND COPPER OR COPPER-PLATED HANGERS FOR COPPER PIPE. PROVIDE PROTECTION FOR COPPER PIPING IN CONTACT WITH DISSIMILAR METALS. WHERE COPPER PIPING IS SUPPORTED ON HANGERS WITH OTHER PIPING, PROVIDE A PERMANENT ELECTROLYTIC ISOLATION MATERIAL TO PREVENT CONTACT WITH OTHER METALS. IN GENERAL, HANGERS SHALL BE CLEVIS TYPE, STANDARD WEIGHT. FOR PIPING, HANGER SPACING SHALL BE IN ACCORDANCE WITH TABLE 308.5 OF THE SPC. HANGERS AND ACCESSORIES SHALL BE GRINNEL, MASON, OR B-LINE.
4. SLEEVE ALL PIPES PASSING THROUGH PARTITIONS, WALLS, AND FLOORS. SLEEVES IN FLOORS AND INTERIOR WALLS OF POURED IN PLACE CONCRETE, BRICK, TILE, OR MASONRY SHALL BE SCHEDULE 40 STEEL PIPE, MACHINE CUT. SLEEVES IN GYPSUM BOARD WALLS SHALL BE 22 GAUGE, ROLLED GALVANIZED SHEET METAL. TACK WELD ON THE LONGITUDINAL SEAM. PROVIDE SLEEVES WHERE PIPES PASS THROUGH FLOORS AND WALLS ABOVE AND BELOW CEILINGS. PROVIDE SPLIT PIPE SLEEVES IN NEW WALLS BUILT UP AROUND EXISTING PIPES. TACK WELD SPLIT SLEEVES TOGETHER. SLEEVES IN WALLS SHALL BE INSTALLED FLUSH WITH THE WALL. SLEEVES IN FLOORS SHALL EXTEND 3/4 INCH ABOVE THE FLOOR-EXCEPT THEY SHALL BE FLUSH FOR 2 HOUR RATED FLOORS-AND SHALL BE FLUSH WITH THE STRUCTURE BELOW. EACH SLEEVE SHALL HAVE AN INSIDE DIAMETER 1 INCH LARGER THAN THE OUTSIDE DIAMETER OF THE COVERING OF EACH COVERED PIPE TO ALLOW CONTINUOUS INSULATION-BUT NOT LESS THAN TWO PIPE SIZES LARGER THAN EACH UNCOVERED. ANNULAR SPACES BETWEEN SLEEVES AND PIPES SHALL BE FILLED OR CAULKED IN AN APPROVED MANNER.
5. THE TOP OF WATER PIPES INSTALLED BELOW GRADE OUTSIDE THE BUILDING SHALL BE BELOW THE FROST LINE OR A MINIMUM OF 12 INCHES BELOW FINISHED GRADE WHICHEVER IS GREATER. WATER PIPING INSTALLED IN A WALL EXPOSED TO THE EXTERIOR SHALL BE LOCATED ON THE HEATED SIDE OF THE WALL INSULATION. WATER PIPING INSTALLED IN AN UNCONDITIONED UTILITY ROOM OR UNCONDITIONED ATTIC SHALL BE INSULATED TO A MINIMUM OF R6.5 DETERMINED IN ACCORDANCE WITH ASTM C 177.
6. HOT WATER PROVIDED TO PUBLIC HAND-WASHING FACILITIES/LAVATORIES SHALL BE TEMPERED WATER DELIVERED THROUGH AN APPROVED WATER-TEMPERATURE LIMITING DEVICE THAT CONFORMS TO ASSE 1070 OR CSA B125.3.
7. INSULATE ALL EXPOSED WASTE AND SUPPLY PIPING UNDER LAVATORIES, SINKS, AND ELECTRIC WATER COOLERS WITH THE HANDI-LAV GUARD INSULATION KIT BY TRUEBRO OR EQUAL.
8. POTABLE WATER OUTLETS SHALL BE PROTECTED FROM BACKFLOW IN ACCORDANCE WITH 608.16 SPC. PRESSURE TYPE VACUUM BREAKERS SHALL CONFORM TO ASSE 1020 AND SPILPROOF VACUUM BREAKERS SHALL COMPLY WITH ASSE 1056. HOSE-CONNECTION VACUUM BREAKERS SHALL CONFORM TO ASSE 1011, ASSE 1019, ASSE 1035, OR ASSE 1052. CONNECTIONS TO BEVERAGE DISPENSERS, COFFEE MACHINES, AND NON-CARBONATED BEVERAGE DISPENSERS SHALL BE PROTECTED BY A BACKFLOW PREVENTER IN ACCORDANCE WITH ASSE 1022.
9. THE PC SHALL INSTALL WATER HAMMER ARRESTORS ON BRANCH LINES WITH QUICK CLOSING VALVES PER MANUFACTURER'S INSTALLATION INSTRUCTIONS. WATER HAMMER ARRESTORS SHALL CONFORM TO ASSE 1010.
10. THE PC SHALL PROVIDE CHECK VALVES AT ALL FIXTURES WITH THREADED OUTLETS AS REQUIRED BY CODE. TRAP PRIMERS SHALL BE PROVIDED AS SHOWN ON THE PLANS OR AS REQUIRED.
11. ADJUST STOPS AND VALVES FOR INTENDED FLOW RATE TO FIXTURES WITHOUT SPLASHING, NOISE, OR OVERFLOW.
12. BEFORE COMMENCING WORK, CHECK INVERT ELEVATIONS REQUIRED FOR SEWER CONNECTIONS, CONFIRM INVERTS, AND VERIFY THESE CAN BE PROPERLY CONNECTED TO WITH SLOPE FOR DRAINAGE AND COVER TO AVOID FREEZING. ONCE INVERTS AND FALL HAVE BEEN ESTABLISHED, EXTEND SANITARY SEWER AS SHOWN AND INSTALL ALL DRAINS, STACKS, VENTS, FLOOR DRAINS, AND CLEANOUTS NECESSARY FOR A COMPLETE INSTALLATION.
13. ALL SANITARY SEWER PIPING IS BELOW GRADE OR WITHIN WALLS UNLESS OTHERWISE NOTED. ALL SANITARY VENT PIPING IS ABOVE THE CEILING OR WITHIN WALLS UNLESS OTHERWISE NOTED. SOIL AND WASTE PIPING SHALL BE INSTALLED TO PROVIDE PROTECTION AGAINST FREEZING PER 305.4 SPC. WASTE AND SOIL LINES LEAVING THE BUILDING MUST HAVE A MINIMUM COVER OF 3 INCHES.
14. SOIL AND WASTE LINES 2-1/2 INCHES AND SMALLER SHALL BE SLOPED AT 1/4 INCH PER FOOT MINIMUM. SOIL AND WASTE LINES 3 INCHES TO 6 INCHES IN DIAMETER SHALL BE SLOPED AT 1/8 INCH PER FOOT MINIMUM.
15. FOR WATER CLOSET WASTE CONNECTIONS, A 4 INCH BY 3 INCH CLOSET BEND SHALL BE ACCEPTABLE. WHERE A 3 INCH BEND IS UTILIZED ON WATER CLOSETS, A 4 INCH BY 3 INCH FLANGE SHALL BE INSTALLED TO RECEIVE THE FIXTURE HORN.
16. FOR PLASTIC PIPE SIZES GREATER THAN 6 INCHES, AND OTHER PIPE SIZES GREATER THAN 4 INCHES, RESTRAINTS SHALL BE PROVIDED FOR DRAINPIPES AT ALL CHANGES IN DIRECTION AND AT ALL CHANGES IN DIAMETER GREATER THAN TWO PIPE SIZES. BRACES, BLOCKS, RODDING, BACKFILL AND OTHER SUITABLE METHODS AS SPECIFIED BY THE COUPLING MANUFACTURER SHALL BE UTILIZED.
17. BASES OF STACKS SHALL BE SUPPORTED BY THE BUILDING STRUCTURE, VIRGIN OR COMPACTED EARTH, OR OTHER SUITABLE MATERIAL TO SUPPORT THE WEIGHT OF THE PIPING.
18. HORIZONTAL DRAINPIPES SHALL HAVE CLEANOUTS IN ACCORDANCE WITH 708.1 SPC. EXTEND CLEANOUTS TO FINISHED FLOOR OR WALL SURFACE. LUBRICATE THREADED CLEANOUT PLUGS WITH A MIXTURE OF GRAPHITE AND LINSEED OIL. ENSURE CLEARANCE AT ALL CLEANOUTS FOR RODDING OF DRAINAGE SYSTEM. INSTALL FLOOR CLEANOUTS AT AN ELEVATION TO ACCOMMODATE FINISHED FLOOR. EVERY CLEANOUT SHALL BE INSTALLED TO ALLOW CLEANING IN THE DIRECTION OF FLOW OF THE DRAINAGE PIPE OR AT RIGHT ANGLES THERETO. CLEANOUTS ON 6 INCH AND SMALLER PIPES SHALL BE PROVIDED WITH A CLEARANCE OF NOT LESS THAN 18 INCHES FOR RODDING.
19. DRAINAGE PIPING FOR FUTURE FIXTURES SHALL TERMINATE WITH AN APPROVED CAP OR PLUG.
20. AIR ADMITTANCE VALVES SHALL BE INSTALLED AFTER THE DWV TESTING REQUIRED BY SECTIONS 312.2 AND 312.3 OF THE SPC. PROVIDE ACCESS TO ALL AIR ADMITTANCE VALVES PER CODE. INSTALLATION OF ALL AIR ADMITTANCE VALVES SHALL CONFORM TO SECTION 918 OF THE SPC. AIR ADMITTANCE VALVES SHALL CONFORM TO ASSE 1050 OR 1051.
21. INDIRECT WASTE PIPING THAT EXCEEDS 2 FEET IN DEVELOPED LENGTH MEASURED HORIZONTALLY, OR 4 FEET IN TOTAL DEVELOPED LENGTH, SHALL BE TRAPPED. THE AIR GAP BETWEEN THE INDIRECT WASTE PIPE AND THE FLOOD LEVEL RIM OF THE WASTE RECEPTOR SHALL BE A MINIMUM OF TWICE THE EFFECTIVE OPENING OF THE INDIRECT WASTE PIPE.
22. THE PC SHALL PROVIDE UNIONS FOR DISASSEMBLY AND SERVICE OF ALL FIXTURES AND OTHER RELEVANT PLUMBING EQUIPMENT. UNIONS SHALL BE GROUND-JOINT WITH BRASS SEAT. PROVIDE INSULATING UNIONS AT EACH JUNCTION OF DISSIMILAR MATERIALS.
23. THE PC SHALL ACCURATELY ROUGH-IN ALL FIXTURES ACCORDING TO MANUFACTURER'S INSTALLATION DIMENSIONS AND INSTRUCTIONS. OFFSET ADAPTERS AND FLEXIBLE CONNECTORS ARE NOT ACCEPTABLE. FLUSH HANDLES SHALL BE MOUNTED ON THE WIDE SIDE OF TOILET AREAS FOR ADA COMPLIANCE. INSTALL EACH FIXTURE WITH TRAP EASILY REMOVABLE FOR SERVICING AND CLEANING. SEAL FIXTURES TO WALL AND FLOOR SURFACES WITH SEALANT. SOLIDLY ATTACH WATER CLOSETS TO FLOOR WITH LAG SCREWS. SEAL ALL SELF-RIMMING LAVATORIES AND SINKS (VITREOUS CHINA AND STAINLESS STEEL) WITH A COMMERCIAL GRADE PLUMBER'S PUTTY OR ACRYLIC LATEX CAULK APPLIED TO THE UNDERSIDE OF THE FIXTURE RIM IN A GENEROUS AMOUNT SO THAT WHEN FIXTURE IS SET, SEALANT SHALL OOZE OUT.
24. ALL VENT THRU THE ROOF (VTR) PENETRATIONS SHALL BE COORDINATED WITH THE GENERAL CONTRACTOR. PC SHALL PROVIDE FLASHING MATERIAL REQUIRED FOR VTRS. JOINTS AT THE ROOF AND AROUND VENT PIPES SHALL BE MADE WATERTIGHT BY THE USE OF LEAD, COPPER, GALVANIZED STEEL, ALUMINUM, OR OTHER APPROVED FLASHINGS OR FLASHING MATERIAL. MAINTAIN MINIMUM 10 FEET FROM ALL OUTSIDE AIR INTAKES.
25. INSTALL FULL OPEN VALVES PER SPC 606.1 ON THE MAIN WATER LINE INTO THE BUILDING. INSTALL SHUTOFF VALVES PER SPC 606.2.

MATERIALS:

1. BALL VALVES SHALL HAVE BRASS BODY, FULL PORT, CHROME PLATED BALL, WITH TEFLON SEATS, 150 PSI WSP, AND COMPLY WITH MSS SP-110. GATE VALVES SHALL HAVE BRONZE BODY, CLASS 150, AND COMPLY WITH MSS SP-80, TYPE 2 STANDARD. VALVE BODY SHALL BE ASTM B 62, BRONZE WITH INTEGRAL SEAT AND UNION RING BONNET. ENDS SHALL BE THREADED OR SOLDER WITH COPPER-SILICON BRONZE STEM AND SOLID-WEDGE BRONZE DISC. INSTALL VALVES IN LOCATIONS THAT PERMIT EASY ACCESS WITHOUT DAMAGE TO BUILDING OR FINISHED MATERIALS; PROVIDE ACCESS DOORS IF REQUIRED. VALVES SHALL BE BY NIBCO, WATTS, OR STOCKHAM.
2. COLD WATER LINES SHALL BE INSULATED WITH 1/2 INCH THICK FIBROUS GLASS INSULATION WITH A FLAME DENSITY RATING LESS THAN 25 AND A SMOKE DENSITY RATING LESS THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84. HOT WATER LINES UP TO 2 INCHES DIAMETER SHALL HAVE 1 INCH THICK INSULATION CONFORMING TO THE SAME STANDARD. PIPING LARGER THAN 2 INCHES SHALL RECEIVE 1-1/2 INCH THICK INSULATION. CLOSED CELL RUBBER INSULATION MEETING THE SMOKE AND FLAME RATINGS ABOVE MAY BE SUBSTITUTED FOR FIBROUS GLASS TYPE IF SO DESIRED. INSULATION INSTALLED ON PIPING OPERATING BELOW AMBIENT TEMPERATURES MUST HAVE A CONTINUOUS VAPOR RETARDER. ALL JOINTS, SEAMS AND FITTINGS MUST BE SEALED. ON SYSTEMS OPERATING ABOVE AMBIENT, THE BUTT JOINTS SHOULD NOT BE SEALED. ON COLD SURFACES WHERE A VAPOR SEAL MUST BE MAINTAINED, INSULATION SHALL BE APPLIED WITH A CONTINUOUS, UNBROKEN MOISTURE AND VAPOR RETARDER. ALL HANGERS, SUPPORTS, ANCHORS, OR OTHER PROJECTIONS SECURED TO COLD SURFACES SHALL BE INSULATED AND VAPOR SEALED TO PREVENT CONDENSATION. ALL PIPE INSULATION SHALL BE CONTINUOUS THROUGH WALLS, CEILING OR FLOOR OPENINGS, OR SLEEVES EXCEPT WHERE FIRESTOP OR FIRESAFING MATERIALS ARE REQUIRED. INSULATION SHALL HAVE A FACTORY APPLIED ALL-SERVICE JACKET WITH SELF-SEALING LAP. WHITE-KRAFT PAPER BONDED TO ALUMINUM FOIL AND REINFORCED WITH GLASS FIBERS; CONFORMING TO ASTM C 1136 TYPE 1; VAPOR RETARDER; WITH A SELF-SEALING ADHESIVE. VERIFY THAT PIPING HAS BEEN TESTED, SURFACES ARE CLEAN AND DRY, AND ALL FOREIGN MATERIALS ARE REMOVED BEFORE APPLYING INSULATION MATERIALS. INSULATION SHALL BE BY KNAUF, ARMACELL, JOHNS-MANVILLE, OR OWENS-CORNING.
3. ALL INSULATION CONTAINING FIBROUS MATERIALS EXPOSED TO AIRFLOW SHALL BE RATED FOR THAT EXPOSURE OR SHALL BE ENCAPSULATED. INSULATING PROPERTIES FOR ALL MATERIALS SHALL MEET OR EXCEED INDUSTRY STANDARDS. POLYSTYRENE PRODUCTS SHALL MEET ASTM C578 91. ALL INSULATION SHALL BE LOW-EMITTING WITH NOT GREATER THAN 0.05 PPM FORMALDEHYDE EMISSIONS. THE MAXIMUM FLAME SPREAD AND SMOKE DEVELOPED INDEX FOR INSULATION SHALL MEET THE REQUIREMENTS OF THE LOCAL CODES AND ORDINANCES ADOPTED BY THE JURISDICTION IN WHICH THE BUILDING IS LOCATED.
4. FAUCETS AND FIXTURE FITTINGS SHALL CONFORM TO ASME A112.18.1. FAUCETS AND FIXTURE FITTINGS THAT SUPPLY DRINKING WATER FOR HUMAN CONSUMPTION SHALL CONFORM TO THE REQUIREMENTS OF NSF 61, SECTION 9. FIXTURE FITTINGS, FAUCETS, AND DIVERTERS SHALL BE INSTALLED AND ADJUSTED SO THAT THE FLOW OF HOT WATER FROM THE FITTINGS CORRESPONDS TO THE LEFT-HAND SIDE OF THE FIXTURE FITTING.
5. BACKFLOW PREVENTION SHALL BE IN ACCORDANCE WITH SECTION 608.14 OF THE SPC AND THE LOCAL AUTHORITY HAVING JURISDICTION. REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTERS SHALL CONFORM TO ASSE 1013 OR AWWA C511. THE RELIEF OPENING SHALL DISCHARGE BY AIR GAP. AIR GAPS SHALL COMPLY WITH ASME A112.1.1 AND AIR GAP FITTINGS WITH ASME A112.1.3. DOUBLE CHECK VALVE ASSEMBLIES SHALL CONFORM TO ASSE 1015 OR AWWA C510. ACCESS TO BACKFLOW PREVENTERS SHALL BE PROVIDED AS SPECIFIED BY THE INSTALLATION INSTRUCTIONS OF THE APPROVED MANUFACTURER.
6. FOR BELOW GRADE SANITARY WASTE PIPING, PC SHALL USE SERVICE WEIGHT CAST IRON PIPE WITH COMPRESSION JOINTS (ASTM A 74). USE MINIMUM 2" SIZE UNDERGROUND. SOLID WALL SCHEDULE 40 PVC (ASTM D 2665) WITH SCHEDULE 40 SOCKET TYPE PIPE FITTINGS (ASTM D 3311) MAY ALSO BE USED. DO NOT USE PVC PIPE FOR APPLICATIONS WHERE THE WASTEWATER TEMPERATURE EQUALS OR EXCEEDS 140°F OR IF THE BUILDING HEIGHT EXCEEDS 75 FEET.
7. FOR ABOVE GRADE SANITARY WASTE AND VENT PIPING, USE SERVICE WEIGHT CAST IRON NO-HUB TYPE WITH COUPLINGS (CISPI 301). SOLID WALL SCHEDULE 40 PVC (ASTM D 2665) WITH SCHEDULE 40 SOCKET TYPE FITTINGS (ASTM D 3311) MAY BE USED IF PERMITTED BY LOCAL CODE, EXCEPT IN BUILDINGS EXCEEDING 75 FEET IN HEIGHT. DO NOT INSTALL PVC IN RETURN AIR PLENUMS. ALL VENT AND BRANCH VENT PIPES SHALL BE SO GRADED AND CONNECTED AS TO DRAIN BACK TO THE DRAINAGE PIPE BY GRAVITY. BRANCH VENTS EXCEEDING 40 FEET IN DEVELOPED LENGTH SHALL BE INCREASED BY ONE NOMINAL SIZE FOR THE ENTIRE DEVELOPED LENGTH OF THE PIPE.
8. ALL OVERHEAD DOMESTIC WATER PIPING SHALL BE TYPE L COPPER WITH 95/5 LEAD FREE SOLDER, AND ALL BELOW GRADE WATER PIPING SHALL BE TYPE K COPPER WITH NO JOINTS. ALL PIPING SHALL HAVE MANUFACTURER'S NAME AND THE APPLICABLE STANDARD TO WHICH IT WAS MANUFACTURED CLEARLY MARKED ON EACH LENGTH. PIPING SHALL COMPLY WITH ASTM B-88. USE BRAZED JOINTS ON ALL COPPER PIPING 1-1/2 INCH AND LARGER. ALL PIPE AND PIPE FITTINGS, INCLUDING VALVES AND FAUCETS, USED IN THE WATER DISTRIBUTION SYSTEM SHALL HAVE A MAXIMUM LEAD CONTENT OF 0.25-PERCENT AND SHALL CONFORM TO NSF 61. HOT WATER DISTRIBUTION PIPE AND TUBING SHALL HAVE A MINIMUM PRESSURE RATING OF 100 PSI AT 180°F. COLD WATER DISTRIBUTION PIPE AND TUBING SHALL HAVE A MINIMUM PRESSURE RATING OF 160 PSI AT 73.4°F. DO NOT INSTALL PEX OR CPVC PIPING IN RETURN AIR PLENUMS.
   8.1 PC MAY USE PEX (ASTM F 877) WITH APPROVED FITTINGS (ASTM F 1807) WITH OWNER'S APPROVAL. CPVC PIPING (ASTM D 2846 OR ASTM F 441) WITH APPROVED FITTINGS (ASTM D 2846, ASTM F 438, OR ASTM F 439) MAY ALSO BE USED WHERE NOT LOCATED IN PLENUMS. ALL PLASTIC PIPE, FITTINGS, AND COMPONENTS SHALL BE THIRD-PARTY CERTIFIED AS CONFORMING TO NSF 14.
9. PC SHALL PROVIDE ALL WATER HEATERS (WATTAGE/INPUT AND CAPACITY AS NOTED IN SCHEDULE). ALL WATER HEATERS SHALL BE THIRD PARTY CERTIFIED; PROVIDE PANS FOR WATER HEATERS IN ACCORDANCE WITH 504.7 OF THE SPC. ELECTRICAL CONNECTIONS SHALL BE BY ELECTRICAL CONTRACTOR, PC SHALL COORDINATE WITH EC ON ELECTRICAL CHARACTERISTICS OF THE EQUIPMENT PROVIDED.
10. ALL PUMPS SHALL BE RATED FOR TRANSPORT OF POTABLE WATER. PUMPS IN AN INDIVIDUAL WATER SUPPLY SYSTEM SHALL BE CONSTRUCTED AND INSTALLED SO AS TO PREVENT CONTAMINATION FROM ENTERING THE WATER SUPPLY SYSTEM.

ABBREVIATIONS AND DEFINITIONS

ABBREVIATION	DEFINITION
CWS	COLD WATER SUPPLY
HWS	HOT WATER SUPPLY
GL	GREASE LADEN
VTR	VENT TO ROOF
FPHB	FREEZE PROOF HOSE BIBB
IHB	INTERIOR HOSE BIBB
PC	PLUMBING CONTRACTOR
BFP	BACK FLOW PREVENTOR
AFF	ABOVE FINISHED FLOOR
RI	ROUGH IN
CRI	CONCEALED ROUGH IN
ID	INTERIOR DRAIN-STORM
DS	DOWNSPUT-STORM
SS	SANITARY SEWER
FD	FLOOR DRAIN
RD	ROOF DRAIN
FU	FIXTURE UNIT
PT	PLASTER TRAP
PU	PROCTO UNIT
OS&Y	OUTSIDE STEAM AND YOKE
WH	WATER HEATER
OSD	OPEN-SITE DRAIN
VS	VENT STACK (SANITARY)
SV	STACK VENT (SANITARY)
FCO	FLOOR CLEAN OUT
WCO	WALL CLEAN OUT
PCO	PLUG CLEAN OUT

LINETYPE LEGEND

HOT WATER RECIRCULATING	
COLD WATER SUPPLY	
HOT WATER SUPPLY	
SANITARY SEWER LINE	
VENT LINE	

PLUMBING DRAWING INDEX

SHEET NUMBER	SHEET TITLE
P-001	PLUMBING NOTES
P-002	PLUMBING SCHEDULES & DETAILS
P-101	PLUMBING BUILDING 1 WASTE/VENT PLAN
P-102	PLUMBING BUILDING 1 DOMESTIC SUPPLY PLAN
P-103	PLUMBING ENLARGED PLANS
P-201	PLUMBING RISERS
FP-101	FIRE PROTECTION SUGGESTED HEAD LAYOUT

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
GEORGIA CERTIFICATE OF AUTHORITY — KILIAN ENGINEERING, INC. No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #ZC6110338
DES: JCL CHK: CSL/REW DRW: JCL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. LAWTER

PRINCIPAL IN CHARGE
[redacted]

REV:	DATE:	NOTE:
A	02/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

PLUMBING NOTES

UPS SAV TENANT INPROVEMENT

P-001

© 2025 STRATUS®

PLUMBING FIXTURE SCHEDULE

SYMBOL	FIXTURE	MANUFACTURER	FITTING	HW	CW	WASTE
P1	FLUSH VALVE WATER CLOSET	[redacted] AMERICAN STANDARD BRANDS	FLOOR MOUNTED, VITREOUS CHINA, 1.28 GPF LOW CONSUMPTION SIPHON JET FLUSHING TOILET COMPLYING WITH ASME 112. 19. 2. TOILET SHALL BE ELONGATED FONT BOWL. PROVIDE BERMIS 1955CTFR OPEN FRONT SEAT LESS COVER. PROVIDE SLOAN ROYAL 111 ESS-S HARD WIRED SENSOR FLUSHOMETER OR EQUAL BY AMERICAN STANDARD BRANDS.	-	1"	3"
P1H	ADA FLUSH VALVE WATER CLOSET	[redacted] AMERICAN STANDARD BRANDS	FLOOR MOUNTED, VITREOUS CHINA, 1.28 GPF LOW CONSUMPTION SIPHON JET FLUSHING TOILET COMPLYING WITH ASME 112. 19. 2. TOILET SHALL BE ELONGATED FONT BOWL. PROVIDE BERMIS 1955CTFR OPEN FRONT SEAT LESS COVER. PROVIDE SLOAN ROYAL 111 ESS-S HARD WIRED SENSOR SENSOR FLUSHOMETER OR EQUAL BY AMERICAN STANDARD BRANDS. TOP OF SEAT SHALL BE 17-19 INCHES AFF FOR ADA.	-	1"	3"
P2A	WALL MOUNT LAVATORY	[redacted] SLOAN VALVE CO.	VITREOUS CHINA LAVATORY WITH BACKSPLASH COMPLYING WITH ASME 112. 19. 2. TOP OF RIM SHALL BE 34 INCHES AFF FOR ADA. PROVIDE WITH LAV-GUARD PROTECTORS FOR SUPPLY AND DRAIN LINES. PROVIDE JR SMITH 0700 (CONCEALED ARMS) WITH 19" ARMS 0800 (WALL SUPPORT PLATE). USE SLOAN ETF-600-PLG-TEE-CP-0.5GPM-MLM-IR-FCT HARD WIRED TOUCHLESS FAUCET OR APPROVED EQUAL BY KOHLER VALVE CO.	1/2"	1/2"	2"
P2B	COUNTER MOUNT LAVATORY	KOHLER K-2337-4 OR EQUAL BY SLOAN VALVE CO.	VITREOUS CHINA SELF-RIMMING LAVATORY COMPLYING WITH ASME 112. 19. 2. MOUNT SO RIM IS 34 INCHES AFF AND 2 INCHES FROM FRONT EDGE FOR ADA. PROVIDE WITH LAV-GUARD PROTECTORS SUPPLY AND DRAIN LINES. USE SLOAN ETF-600-PLG-TEE-CP-0.5GPM-MLM-IR-FCT HARD WIRED TOUCHLESS FAUCET OR APPROVED EQUAL BY KOHLER VALVE CO.	1/2"	1/2"	2"
P3	URINAL	KOHLER K-4991-ET OR EQUAL BY AMERICAN STANDARD BRANDS	VITREOUS CHINA, WALL-MOUNTED, ADA COMPLIANT, LOW CONSUMPTION WASHOUT URINAL COMPLYING WITH ASME 112. 19. 2.- 0.5 GPF. PROVIDE SLOAN ROYAL 186 ESS-0.125-DBP-TMO-H HARD WIRED SENSOR FLUSHOMETER OR EQUAL BY AMERICAN STANDARD BRANDS. TOP OF RIM SHALL BE 17 INCHES AFF FOR ADA.	-	3/4"	2"
P4	SQUARE SHOWER	DREAMLINE DL-6194 OR APPROVED EQUAL	PROVIDE WITH MIXING VALVE, PRESSURE BALANCED, LEVER HANDLE, PREPLUMBED TREE TO SUPPLY ELBOW, SOAP DISH, PROVIDE SHOWER HEAD, SHOWER SPRAY HOSE. DELTA T13H133 SHOWER SYSTEM, CHROME PLATED PRESSURE BALANCE CARTRIDGE,HANDLE TEMPERATURE CONTROL, RATED FOR MINIMUM FLOW RATE OF 1.2 GPM @ 45 PSI.	1/2"	1/2"	2"
P5A	MOP SINK	FIAT MSB3624 OR EQUAL BY AMERICAN STANDARD BRANDS, ELJER, KOHLER, OR STERN WILLIAMS	OUTSIDE DIMENSIONS OF 36 X24 X10. INCLUDE A COMBINATION DOME STRAINER AND LINT BASKET OF STAINLESS STEEL. PROVIDE 830-AA CHROME PLATED SERVICE FAUCET WITH VACUUM BREAKER, INTEGRAL STOPS, ADJUSTABLE WALL BRACE, PAIL HOOK AND 3/4 INCH HOSE THREAD ON SPOUT.	1/2"	1/2"	3"
P5B	SERVICE SINK	KOHLER K-6718 OR EQUAL BY CRANE-FIAT, AMERICAN STANDARD BRANDS, ELJER, OR STERN WILLIAMS	WALL MOUNTED, ENAMELED CAST IRON, BLANK BACK. INCLUDE SERVICE SINK STRAINER. PROVIDE 830-AA CHROME PLATED SERVICE FAUCET WITH VACUUM BREAKER, INTEGRAL STOPS, ADJUSTABLE WALL BRACE, PAIL HOOK AND 3/4 INCH HOSE THREAD ON SPOUT.	1/2"	1/2"	3"
P6	EXPANSION TANK	AMTROL ST-5 OR EQUAL BY WATTS OR BELL & GOSSETT	INSTALL ON COLD WATER LINE BETWEEN WATER HEATER AND RPZ	-	3/4"	-
P7	HOT WATER RE-CIRCULATION PUMP	TACO COMFORT SOLUTIONS MODEL 006-IQBC7-IFC	9 GPM AT 8.5 FT. HEAD WITH LINE CORD, TIMER AND AQUASTAT AND CHECK VALVE.3/4" SWEAT CONNECTION, BRONZE CASING.	3/4"	-	-
P8	WALL CLEANOUT	ZURN, WATTS, OR JR SMITH	CAST IRON CLEANOUT FERRULE WITH THREADED BRASS COUNTERSUNK CLEANOUT PLUG, STAINLESS STEEL ACCESS COVER, AND VANDAL PROOF STAINLESS STEEL SCREW	-	-	4"
P9	FLOOR DRAIN	WATTS FD-200-A OR EQUAL BY ZURN OR JR SMITH	ON GRADE EPOXY COATED CAST IRON FLOOR DRAIN WITH ANCHOR FLANGE, WEEP HOLES, ADJUSTABLE ROUND NICKEL BRONZE STRAINER, AND NO HUB OUTLET.	-	-	3"
P10	BARRIER-TYPE TRAP PRIMER	SURE SEAL SS3009V OR EQUAL	WATERLESS INLINE 3" DRAIN TRAP SEAL. HDPE HOUSING WITH PROPRIETARY HEAVY DUTY SILICONE DIAPHRAGM AND SOFT EPDM RUBBER SEALING GASKET. FLOOR RATING ASSE 1072 AF GW.	-	-	3"
P11	THERMOSTATIC MIXING VALVE	WATTS LFMMV OR EQUAL BY LAWLER OR LEONARD VALVE	ASSE STANDARD 1069 OR 1070 APPROVED WITH 1/2 INCH FEMALE NPT INLET AND OUTLET CONNECTIONS, BRASS BODY, AND INTEGRAL MOUNTING HOLES. TAMPER RESISTANT THERMOPLASTIC ENCLOSURE. SINGLE REPLACEABLE CARTRIDGE DESIGN.	1/2"	1/2"	-
P12	WATER HAMMER ARRESTOR	ZURN Z1700 SERIES OR EQUAL BY WATTS OR SIOUX CHIEF	INSTALL ON BRANCH LINES PER MFG'S INSTRUCTIONS. PROVIDE ACCESS PANEL WHERE NECESSARY WHERE LOCATED ABOVE HARD CEILINGS OR WITHIN WALLS.	-	VARIES	-
P13A	AIR ADMITTANCE VALVE	STUDOR REDIVENT OR APPROVED EQUAL	ANSI/ASSE 1051 LISTED. NSF STANDARD 14. PROVIDE PVC OR ABS CONNECTOR AS NECESSARY.CONNECT VALVE TO PIPING PER MANUFACTURER. INSTALL IN THE VERTICAL, UPRIGHT POSITION AFTER ROUGH-IN AND PRESSURE TESTING OF THE SYSTEM.PROVIDE WALL BOX IF NOT ABOVE CEILING OR OTHERWISE CONCEALED.	-	-	VARIES
P13B	AIR ADMITTANCE VALVE	[redacted] RECESSED BOX OR APPROVED EQUAL	ANSI/ASSE 1051 LISTED. NSF STANDARD 14. PROVIDE PVC OR ABS CONNECTOR AS NECESSARY.CONNECT VALVE TO PIPING PER MANUFACTURER. INSTALL IN THE VERTICAL, UPRIGHT POSITION AFTER ROUGH-IN AND PRESSURE TESTING OF THE SYSTEM. PROVIDE STUDOR WALL BOX .	-	-	VARIES
P14	EYEWASH/ EMERGENCY EYE & SHOWER STATION	HAWS 8300-8309 OR APPROVED EQUAL	MODEL 8300-8309 COMBINATION SHOWER AND EYE/FACE WASH SHALL INCLUDE A STAINLESS STEEL 11" ROUND BOWL, AN AXION® MSR EYE/FACE WASH HEAD SHALL FEATURE INVERTED DIRECTIONAL LAMINAR FLOW WHICH ACHIEVES ZERO VERTICAL VELOCITY™ SUPPLIED BY AN INTEGRAL 3.7 GPM FLOW CONTROL. UNIT SHALL ALSO INCLUDE THE AXION MSR HYDRODYNAMIC DESIGNED ABS PLASTIC SHOWERHEAD WITH 20 GPM FLOW CONTROL, CHROME-PLATED BRASS STAY-OPEN BALL VALVE EQUIPPED WITH STAINLESS STEEL BALL AND STEM, AND CHROME-PLATED BRASS IN-LINE 50 X 50 MESH WATER STRAINER. UNIT SHALL ALSO INCLUDE SCHEDULE 40 HOT-DIPPED GALVANIZED STEEL PIPE AND TTINGS, POWDERCOATED CAST-IRON 9" DIAMETER FLOOR FLANGE, SELF-ADHESIVE HIGH VISIBILITY SAFETY GREEN AND BRIGHT YELLOW STRIPES, UNIVERSAL SIGN, AND 1-1/4" NPT SUPPLY.	-	1 1/4"	1-1/4"
P15	DRINKING FOUNTAIN	ELKAY EZH20 LZSTL8WSSP	ADA COMPLIANT FOR ADULT AND CHILD, 8.0 GPH OF 50°F WATER @ 90°F AMBIENT, PROVIDE ACCESSORY APRON FOR ADA COMPLIANCE AS NECESSARY - WITH BOTTLE REFILLING STATION.	-	3/8"	2"
P16	HUB DRAIN	PROVIDED BY PC	PVC 4"x3" REDUCING HUB WITH A DEEP SEAL P-TRAP PROVIDED WITH WIRE MESH STRAINER FABRICATED BY PLUMBING CONTRACTOR AND INSTALLED 1/2" LIP ABOVE FINISHED FLOOR SEE DETAIL.	-	-	3"
P17	DUAL CHECK VALVE W/ ATMOSPHERIC PORT	WATTS SD-3 OR APPROVED EQUAL BY WILKINS OR CONBRACO	BODY AND ADAPTERS SHALL BE 316 STAINLESS STEEL CONSTRUCTION AND ALL RUBBER COMPONENTS SHALL COMPLY WITH FDA FOOD ADDITIVE REGULATIONS. ALL MATERIALS IN CONTACT WITH THE POTABLE WATER SHALL COMPLY WITH THE REQUIREMENTS OF THE SAFE DRINKING WATER ACT, PUBLIC LAW 93-523, NATIONAL INTERIM PRIMARY DRINKING WATER REGULATIONS. STRAINER MANUFACTURED FROM NSF APPROVED ACETAL PLASTIC.	-	1/2"	-

NOTE: PC TO VERIFY ALL FIXTURE SCHEDULES WITH UPS / ARCHITECT PRIOR TO PURCHASE AND INSTALLATION.

DRAINAGE SUMMARY

FIXTURE TYPE	QTY	IND. F.U.	TOTAL F.U.
SANITARY SEWER			
WATER CLOSET (FLUSH VALVE)	5	4.00	20.00
URINAL (3/4" FLUSH VALVE)	1	4.00	4.00
LAVATORY/HAND SINK	7	1.00	7.00
MOP SINK/SERVICE SINK	3	2.00	6.00
SHOWER	2	2.00	4.00
DRINKING FOUNTAIN	1	0.5	0.50
EMERGENCY EYEWASH/SHOWER COMBO	3	0.00	0.00
EMERGENCY FLOOR DRAIN	6	0.00	0.00
INDIRECT FLOOR RECEPTOR	1	5.00	5.00
SUBTOTAL SANITARY SEWER			46.50
SANITARY SEWER SIZE			EX. 4"


WATER SUPPLY SUMMARY

FIXTURE TYPE	QTY	WATER SUPPLY FIXTURE UNITS				
		CW	HW	CW & HW	HW TOTAL	TOTAL
WATER CLOSET (FLUSH VALVE)	5	5.00	0.00	10.00	0.00	50.00
URINAL (¾" FLUSH VALVE)	1	5.00	0.00	5.00	0.00	5.00
LAVATORY/HAND SINK	7	1.50	1.50	2.00	10.50	14.00
MOP SINK/SERVICE SINK	3	2.25	2.25	3.00	6.75	9.00
SHOWER	2	1.00	1.00	1.40	2.00	2.80
DRINKING FOUNTAIN	1	0.25	0.00	0.25	0.00	0.25
EMERGENCY EYEWASH/SHOWER COMBO	1	0.00	0.00	0.00	0.00	0.00
ICE MACHINE	1	0.50	0.00	0.50	0.00	0.50
TOTAL FIXTURE UNITS					19.3	81.6
TOTAL DEMAND IN GPM					35.00	82.00
MAIN SIZE (VEL. 6-8 FPM)		FLUSH VALVE				EX. 2"


ELECTRIC WATER HEATER SCHEDULE

MARK	MFG	MODEL	TANK VOL	INPUT	RECOVERY	SET POINT	POWER		CONNECTIONS		OPTIONS
			GAL	KW EA. ELEMENT	GPH @ 60°F ΔT	°F	VOLTAGE	PHASE	COLD	HOT	
WH1	A.O. SMITH	DEL-50	50	6.0/6.0	68	110	480	3	3/4	3/4	1-6


1. TWO 3.0 KW ELEMENTS WIRED FOR SIMULTANEOUS OPERATION
2. PROVIDE GALVANIZED STEEL SAFETY PAN (AS REQUIRED)
3. UL 174 LISTED
4. PROVIDE ASME LISTED TEMPERATURE AND PRESSURE RELIEF VALVE
5. MEET OR EXCEED ENERGY FACTOR REQUIREMENTS OF ASHRAE 90.1-2007
6. OR EQUAL BY RHEEM, BRADFORD WHITE, OR STATE




1 WALL CLEANOUT DETAIL
Scale: NONE




2 FLOOR DRAIN DETAIL
Scale: NONE



3 HUB DRAIN DETAIL
Scale: NONE



4 THERMOSTATIC MIXING VALVE DETAIL
Scale: NONE



5 WATER HEATER W/ RECIRC DETAIL
Scale: NONE

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY KILIAN ENGINEERING, INC. No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: JCL CHK: CSL/REW DRW: JCL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. LAWTER

PRINCIPAL IN CHARGE
[redacted]

PLUMBING SCHEDULES & DETAILS

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	02/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION


P-002

© 2025 STRATUS®

= NEW TO EXISTING CONNECTION BEYOND POINT.

LINETYPE LEGEND

HOT WATER RECIRCULATING	
COLD WATER SUPPLY	
HOT WATER SUPPLY	
SANITARY SEWER LINE	
VENT LINE	



1 PLUMBING BUILDING 1 WASTE/VENT PLAN

Scale: 1/8" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778

GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #ZZ6110338

DES: JCL CHK: CSL/REW DRW: JCL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WHITTER

PRINCIPAL IN CHARGE
[redacted]

PLUMBING BUILDING 1 WASTE/VENT PLAN

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

P-101

© 2025 STRATUS®

DOMESTIC SUPPLY PLAN HEX NOTES

1. CAP EXISTING PIPING COLD WATER SERVICE TO HOSE BIBB AS TO NOT BEING ABOVE OF THE TSG SERVICE ROOM. GC SHALL REPAIR SURFACES TO MATCH EXISTING CONDITIONS.

DOMESTIC SUPPLY PLAN GENERAL NOTES


ALL REQUIRED VALVES NOT SHOWN.

- INSTALL FULL OPEN VALVES PER CURRENT GA. PLUMBING CODE 606.1 AND 606.3
- INSTALL SHUT OFF VALVES PER CURRENT GA. PLUMBING CODE 606.2 AND 606.3

= NEW TO EXISTING CONNECTION POINT

LINETYPE LEGEND

HOT WATER RECIRCULATING	
COLD WATER SUPPLY	
HOT WATER SUPPLY	
SANITARY SEWER LINE	
VENT LINE	



1 PLUMBING BUILDING 1 DOMESTIC SUPPLY PLAN

Scale: 1/8" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY KILIAN ENGINEERING, INC. No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #ZZ6110338
DES: JCL CHK: CSL/REW DRW: JCL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. LIGHTER

PRINCIPAL IN CHARGE
[redacted]

PLUMBING BUILDING 1 DOMESTIC SUPPLY PLAN

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

P-102

© 2025 STRATUS®

SANITARY PLAN HEX NOTES

1. ROUTE WATER HEATER DRAIN PAN PIPING DOWN EXTERIOR WALL TO EXTERIOR INDIRECTLY AND TERMINATE WITH AIR GAP OVER SPLASH BLOCK.
2. OFFSET VENT THROUGH ROOF AS REQUIRED TO BE AWAY FROM ANY FRESH AIR INTAKE.
3. ROUTE EQUIPMENT DRAIN INDIRECTLY TO HUB DRAIN AND TERMINATE WITH AIR GAP.

SEE SANITARY RISER SHEET P-201 FOR BRANCH SIZING.

= NEW TO EXISTING CONNECTION BEYOND POINT.

LINETYPE LEGEND

HOT WATER RECIRCULATING	
COLD WATER SUPPLY	
HOT WATER SUPPLY	
SANITARY SEWER LINE	
VENT LINE	


DOMESTIC SUPPLY PLAN GENERAL NOTES

ALL REQUIRED VALVES NOT SHOWN.
- INSTALL FULL OPEN VALVES PER CURRENT PLUMBING CODE 606.1.2, 606.1.5, AND 606.1.8
- INSTALL SHUT OFF VALVES PER CURRENT PLUMBING CODE 606.2 AND 606.2.1

DOMESTIC SUPPLY PLAN HEX NOTES


1. PROVIDE GATE AND CHECK VALVE ON SERVICE SINK/MOP SINK SUPPLY LINES.

SEE DOMESTIC SUPPLY RISER SHEET P-201 FOR BRANCH SIZING.



1 BUILDING 1 ENLARGED WASTE/VENT PLAN

Scale: 1/4" = 1'-0"



2 BUILDING 1 ENLARGED DOMESTIC SUPPLY PLAN

Scale: 1/4" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #ZZ6110338

DES: JCL | CHK: CSL/REW | DRW: JCL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WHITE

PRINCIPAL IN CHARGE

[redacted]

PLUMBING ENLARGED PLANS

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A


02/20/2026
ISSUED FOR CONSTRUCTION

P-103

© 2025 STRATUS®


SANITARY RISER HEX NOTES

1. OFFSET VENT THROUGH ROOF AS REQUIRED TO BE AWAY FROM ANY FRESH AIR INTAKE.
2. ROUTE EQUIPMENT DRAIN INDIRECTLY TO HUB DRAIN AND TERMINATE WITH AIR GAP.




1 BUILDING 1 WASTE/VENT RISER

Scale:NONE



2 BUILDING 1 WASTE/VENT RISER

Scale:NONE



3 BUILDING 1 WASTE/VENT RISER

Scale:NONE


DOMESTIC SUPPLY PLAN GENERAL NOTES

ALL REQUIRED VALVES NOT SHOWN.

- INSTALL FULL OPEN VALVES PER CURRENT PLUMBING CODE 606.1.2, 606.1.5, AND 606.1.8
- INSTALL SHUT OFF VALVES PER CURRENT PLUMBING CODE 606.2 AND 606.2.1

DOMESTIC SUPPLY RISER HEX NOTES


1. PROVIDE GATE AND CHECK VALVE ON MOP SINK/SERVICE SINK SUPPLY LINES



4 BUILDING 1 DOMESTIC RISER PLAN


Scale: NONE

WATER SUPPLY FIXTURE BRANCH SIZING			
SYMBOL	FIXTURE	HW	CW
P1	FLUSH VALVE WATER CLOSET	-	1"
P1H	ADA FLUSH VALVE WATER CLOSET	-	1"
P2A	WALL MOUNT LAVATORY	1/2"	1/2"
P2B	COUNTER MOUNT LAVATORY	1/2"	1/2"
P3	URINAL	-	3/4"
P4	SQUARE SHOWER	1/2"	1/2"
P5A	MOP SINK	1/2"	1/2"
P5B	SERVICE SINK	1/2"	1/2"
P14	EYEWASH/ EMERGENCY EYE & SHOWER STATION	-	1 1/4"
P15	DRINKING FOUNTAIN	-	1/2"
-	ICE MACHINE	-	1/2"



5 BUILDING 1 DOMESTIC RISER PLAN

Scale: NONE



6 BUILDING 1 DOMESTIC RISER PLAN

Scale: NONE

KILIAN
A Stratus Team Company
www.kilianengineering.com | (P) 252.438.8778
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
FIRM REG. #ZZ6110338
DES: JCL CHK: CSL/REW DRW: JCL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WATER

PRINCIPAL IN CHARGE

PLUMBING RISERS

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

P-201

© 2025 STRATUS®

GENERAL MECHANICAL NOTES:

ADMINISTRATIVE:

1. THE FOLLOWING ABBREVIATIONS SHALL APPLY TO NOTES AND PLANS:
   PC - PLUMBING CONTRACTOR,
   EC - ELECTRICAL CONTRACTOR,
   MC - MECHANICAL CONTRACTOR,
   GC - GENERAL CONTRACTOR,
   FASC - FIRE ALARM SYSTEM CONTRACTOR,
   AHJ - AUTHORITY HAVING JURISDICTION.
   SMC - CURRENT STATE MECHANICAL CODE (INTERNATIONAL MECHANICAL CODE WITH GEORGIA AMENDMENTS)
   SBC - CURRENT STATE BUILDING CODE (INTERNATIONAL BUILDING CODE WITH GEORGIA AMENDMENTS)
   SECC- CURRENT STATE ENERGY CONSERVATION CODE (INTERNATIONAL ENERGY CONSERVATION CODE WITH GEORGIA AMENDMENTS)
   NFPA - NATIONAL FIRE PROTECTION ASSOCIATION
2. "PROVIDE" MEANS TO FURNISH AND INSTALL. MC SHALL ALSO INSTALL MATERIALS FURNISHED BY OTHERS AND GENERAL CONTRACTOR AS SHOWN ON THE PLANS OR NECESSARY FOR A COMPLETE INSTALLATION.
3. THE MC SHALL BE RESPONSIBLE FOR A COMPLETE AND OPERATING SYSTEM AS DESCRIBED BY THESE PLANS AND SPECIFICATIONS.
4. ALL MATERIALS AND EQUIPMENT SHALL BE DELIVERED TO THE SITE AND UNLOADED BY THE CONTRACTOR AT AN APPROVED LOCATION. THE MC SHALL PROTECT ALL MATERIALS AND EQUIPMENT FROM BREAKAGE, THEFT, AND THE ELEMENTS. ALL MATERIALS AND EQUIPMENT SHALL REMAIN THE PROPERTY OF THE MC UNTIL THE PROJECT HAS BEEN COMPLETED AND TURNED OVER TO THE OWNER.
5. THE MC SHALL INSTALL ALL MATERIALS AND EQUIPMENT IN ACCORDANCE WITH THE SMC AND SBC AND ANY APPLICABLE LOCAL CODES. WHERE A CONFLICT EXISTS BETWEEN THE ABOVE REQUIREMENTS, THE MC SHALL OBTAIN CLARIFICATION FROM THE ENGINEER OR IN THE EVENT ANY PART OF THESE PLANS CONFLICTS WITH THE ABOVE REQUIREMENTS.
6. THE MC SHALL OBTAIN AND PAY FOR ALL PERMITS, FEES, AND INSPECTIONS NECESSARY FOR THE COMPLETION OF THE WORK UNDER THIS CONTRACT.
7. DO NOT SCALE THESE DRAWINGS-REFER TO ARCHITECTURAL SHEETS FOR DIMENSIONS.
8. THE MC SHALL VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH EXISTING CONDITIONS. THE MC SHALL CONTACT THE ENGINEER TO RESOLVE ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS AND THESE PLANS. THE MC SHALL COORDINATE WITH OTHER TRADES PRIOR TO THE START OF CONSTRUCTION.
9. ALL MECHANICAL MATERIALS SHALL BE NEW AND FREE OF DEFECT AND LISTED AND LABELED BY UL OR AN APPROVED THIRD-PARTY AGENCY. ANY MATERIALS FOUND TO BE DEFECTIVE SHALL BE REPLACED BY THE MC WITHOUT ADDITIONAL COST TO THE OWNER. WHERE A MANUFACTURER AND MODEL NUMBER IS GIVEN, THE CITED EXAMPLE IS INTENDED TO ESTABLISH A STANDARD OF QUALITY AND NOT TO LIMIT PRODUCTS TO A PARTICULAR MANUFACTURER. SUCH EXAMPLES ARE USED TO CONVEY A GENERAL STYLE, TYPE, CHARACTER, AND QUALITY OF THE PRODUCT DESIRED; PRODUCTS DETERMINED TO BE EQUAL BY THE ENGINEER WILL BE ACCEPTED.
10. THESE PLANS ARE DIAGRAMMATIC. THE MC SHALL ADJUST THE LOCATIONS OF EQUIPMENT, DUCTS, REGISTERS, GRILLES, ETC, TO ACCOMMODATE PLANNED AND ENCOUNTERED INTERFERENCES. THE DRAWINGS DO NOT SHOW ALL BENDS, OFFSETS, AND FITTINGS THAT MAY BE REQUIRED FOR A COMPLETE AND OPERATIONAL SYSTEM. THE MC SHALL MAKE ALLOWANCES FOR SUCH DEVIATIONS AND CONTINGENCIES IN BID TO IMPLEMENT THEM WITHOUT ADDITIONAL COST TO THE OWNER.
11. EC SHALL BE RESPONSIBLE FOR ALL POWER CONNECTIONS TO THE MECHANICAL EQUIPMENT. MC SHALL BE RESPONSIBLE FOR ALL CONTROL WIRING.
12. IT IS THE MC'S RESPONSIBILITY TO VERIFY THAT ITEMS FURNISHED FOR THIS CONTRACT WILL FIT IN THE SPACE AVAILABLE. THE MC SHALL MAKE FIELD MEASUREMENTS AS NECESSARY TO DETERMINE SPACE REQUIREMENTS. IF THE MC MUST ALTER EQUIPMENT DUE TO SPACE CONSIDERATIONS, THE MC SHALL PROVIDE SIZES AND SHAPES THAT FIT THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS.
13. MC SHALL COORDINATE WITH THE EC REGARDING THE ELECTRICAL REQUIREMENTS OF ALL EQUIPMENT BEING PROVIDED.
14. MAINTAIN CLEARANCES FOR ALL EQUIPMENT ACCORDING TO MANUFACTURER'S RECOMMENDATIONS FOR SERVICEABILITY. ALL ROOFTOP EQUIPMENT MUST BE A MINIMUM OF 10 FEET FROM ROOF EDGE.
15. MC SHALL FURNISH A BOUND SET OF OPERATING AND MAINTENANCE INSTRUCTIONS FOR ALL EQUIPMENT TO THE OWNER UPON COMPLETION OF THE PROJECT. MC SHALL PROVIDE ALL DOCUMENTATION TO THE OWNER AS NECESSARY TO SUBMIT FOR FACTORY WARRANTIES.
16. CONTRACTOR SHALL PROTECT ALL HVAC EQUIPMENT FROM CONSTRUCTION AND SHEET ROCK DUST DURING CONSTRUCTION. ALL FILTERS SHALL BE REPLACED WITH NEW AT THE COMPLETION OF THE PROJECT.
17. ALL EQUIPMENT INSTALLED ON ROOF MUST BE WITHIN THE ROOF SCREEN.
18. IF A ROOF PENETRATION IS REQUIRED AND THE ROOF IS UNDER WARRANTY, USE THE AUTHORIZED ROOFER. PROVIDE DOCUMENTATION.
19. ALL PIPING, WIRING, CONDUIT, INSULATION, EQUIPMENT, SUPPORTS, ETC. SHALL BE SUITABLE FOR INSTALLATION IN A RETURN PLENUM AS NECESSARY. COORDINATE WITH OTHER TRADES ON LOCATIONS OF ALL PLENUMS.
20. MC SHALL COORDINATE WITH THE GENERAL CONTRACTOR TO ENSURE ALL APPLICABLE CONSTRUCTION WASTE IS RECYCLED DURING THE CONSTRUCTION PHASE OF THE PROJECT.
21. THE MC SHALL VERIFY THE FUNCTIONALITY AND OPERATION OF ALL EXISTING MECHANICAL EQUIPMENT IN THE AREA OF WORK. REPLACE FILTERS, LEAK TEST AND RECHARGE REFRIGERANT LINES, REPLACE OR LUBRICATE BEARINGS, CHECK LINKAGES AND ACTUATORS, AND PERFORM OTHER MAINTENANCE SERVICE AS NECESSARY TO GET THE EQUIPMENT IN PROPER ORDER.

METHODS:

1. INSULATE DUCTWORK WITH FIBERGLASS DUCT WRAP: INSTALLED R-VALUE SHALL BE A MINIMUM R-6. COVERINGS AND LININGS, INCLUDING ADHESIVES WHEN USED, SHALL HAVE A FLAME SPREAD INDEX NOT MORE THAN 25 AND A SMOKE-DEVELOPED INDEX NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM E 84. ALL NEW DUCTWORK SHALL RECEIVE INSULATION ON THE OUTSIDE. INSTALL DUCT WRAP INSULATION WITH FACING OUTSIDE SO THAT TAPE FLAP OVERLAPS INSULATION AND FACING OF ADJACENT PIECE OF DUCT WRAP. INSULATION SHALL BE TIGHTLY BUTTED. FOR RECTANGULAR DUCTS, INSTALL SO INSULATION IS NOT EXCESSIVELY COMPRESSED AT DUCT CORNERS. STAPLE SEAMS APPROXIMATELY 6 INCHES ON CENTER WITH OUTWARD CLINCHING STAPLES. SEAL SEAMS WITH PRESSURE SENSITIVE TAPE MATCHING THE FACING. FOR RECTANGULAR DUCTS 24 INCHES IN WIDTH OR GREATER, SECURE DUCT WRAP TO THE BOTTOM OF THE DUCT WITH MECHANICAL FASTENERS SPACED 18 INCHES ON CENTER TO PREVENT SAGGING OF INSULATION. ADJACENT SECTIONS OF DUCT WRAP SHALL BE TIGHTLY BUTTED WITH THE 2 INCH TAPE FLAP OVERLAPPING. ALL TEARS, PUNCTURES, ETC. OF THE DUCT WRAP INSULATION SHALL BE SEALED WITH TAPE OR MASTIC TO PROVIDE A VAPOR TIGHT SYSTEM. INSULATION SHALL BE BY KNAUF INSULATION, OWENS CORNING CORP, OR CERTAINTEED CORPORATION.
2. VERIFY THAT DUCTS HAVE BEEN TESTED BEFORE APPLYING INSULATION MATERIALS. VERIFY THAT DUCT SURFACES ARE CLEAN, DRY AND FREE OF FOREIGN MATERIAL PRIOR TO INSULATING. DUCT COVERINGS SHALL NOT PENETRATE A WALL OR FLOOR REQUIRED TO HAVE A FIRE-RESISTANCE RATING OR REQUIRED TO BE FIRE BLOCKED.
3. WHERE DUCTS ARE CONNECTED TO EXTERIOR WALL LOUVERS AND DUCT OUTLET IS SMALLER THAN LOUVER FRAME, PROVIDE BLANK-OUT PANELS SEALING LOUVER AREA AROUND DUCT. USE SAME MATERIAL AS DUCT, PAINTED BLACK ON EXTERIOR SIDE. SEAL TO LOUVER FRAME AND DUCT.
4. PROVIDE DUCT ACCESS DOORS FOR INSPECTION AND CLEANING BEFORE AND AFTER FILTERS, COILS, FANS, AUTOMATIC DAMPERS, AT FIRE DAMPERS, COMBINATION FIRE AND SMOKE DAMPERS.
5. CONSTRUCT T'S, BENDS, AND ELBOWS WITH RADII OF NOT LESS THAN 1-1/2 TIMES THE WIDTH OF THE DUCT ON CENTERLINE. WHERE NOT POSSIBLE AND WHERE RECTANGULAR ELBOWS MUST BE USED, PROVIDE TURNING VANES.
6. INCREASE DUCT SIZES GRADUALLY, NOT EXCEEDING 15 DEGREES DIVERGENCE; MAXIMUM OF 30 DEGREES DIVERGENCE UPSTREAM OF EQUIPMENT AND 45 DEGREES CONVERGENCE DOWNSTREAM.
7. IT SHALL BE THE RESPONSIBILITY OF THE MC TO SUSPEND AND SUPPORT ALL EQUIPMENT, DUCTWORK, DIFFUSERS, AND OTHER MATERIALS FOLLOWING RECOGNIZED ENGINEERING PRACTICES AND USING STANDARD, COMMERCIALLY ACCEPTED HANGERS AND SUSPENSION EQUIPMENT. ALL HVAC EQUIPMENT SHALL BE SECURELY MOUNTED TO THE BUILDING STRUCTURE AND SHALL NOT RELY ON CEILING OR WALL SURFACES FOR SUPPORT. THE SUPPORT ATTACHMENT SHALL SUPPORT THE WEIGHT OF THE EQUIPMENT PLUS THE WEIGHT OF THE SUPPORT ATTACHMENT ITSELF. SUPPORT FROM THE TOP CHORD OF THE ROOF JOISTS, GIRDERS, AND BEAMS. THE BOTTOM CHORD IS NOT TO BE USED FOR EQUIPMENT OR PIPING SUPPORT. HANGERS SHALL NOT BE ATTACHED TO CORRUGATED STEEL DECKING.
8. DUCTS SHALL BE SUPPORTED IN ACCORDANCE WITH SMACNA AT INTERVALS NOT EXCEEDING 10 FEET. DUCTS 36 INCHES OR LARGER SHALL HAVE TRAPEZE TYPE HANGERS SUSPENDED WITH THREADED ROD. SUPPORT DUCTS FROM BAR JOISTS, GIRDERS, OR BEAMS.
9. CHECK LOCATIONS OF AIR OUTLETS AND INLETS AND MAKE NECESSARY ADJUSTMENTS IN POSITION TO CONFORM WITH ARCHITECTURAL FEATURES, SYMMETRY, AND LIGHTING ARRANGEMENT. COORDINATE WITH SPRINKLER CONTRACTOR IF APPLICABLE.
10. PROVIDE BALANCING DAMPERS AT POINTS ON SUPPLY WHERE BRANCHES ARE TAKEN FROM LARGER DUCTS AS REQUIRED FOR AIR BALANCING. INSTALL MINIMUM 2 DUCT WIDTHS FROM DUCT TAKE-OFF. PROVIDE BALANCING DAMPERS ON DUCT TAKE-OFFS TO DIFFUSERS AND REGISTERS, REGARDLESS OF WHETHER DAMPERS ARE SPECIFIED AS PART OF THE DIFFUSER OR REGISTER ASSEMBLY. ADJUST AIR HANDLING AND DISTRIBUTION SYSTEMS TO PROVIDE DESIGN SUPPLY, RETURN, AND EXHAUST AIR QUANTITIES AT SITE ALTITUDE.
11. MC SHALL INSTALL PROGRAMMABLE THERMOSTATS AS SHOWN ON THE PLANS. THERMOSTAT SHALL BE MOUNTED AT 48 INCHES AFF. THERMOSTATS SHALL MEET THE REQUIREMENTS FOR THERMOSTATIC CONTROLS IN SECTION C403 OF THE SECC.
12. FRESH AIR INTAKES SHALL BE INSTALLED ON ALL UNITS AS SHOWN ON DRAWINGS. MAINTAIN 10 FEET OF DISTANCE BETWEEN FRESH AIR INTAKES AND ALL EXHAUST TERMINATIONS AND PLUMBING VENT THRU ROOFS.
13. MC SHALL INSTALL ALL EXHAUST FANS AND VENT TO THE BUILDING'S EXTERIOR. EC SHALL SWITCH FANS WITH LIGHTS OR ON SEPARATE SWITCH AS SHOWN.
14. P-TRAPS MUST BE INSTALLED ON ALL UNITS. MC SHALL INSTALL AUXILIARY DRAIN PANS UNDER OVERHEAD AIR HANDLERS AND AN AUTOMATIC CUT-OFF FLOAT SWITCH FOR EACH. P-TRAPS AND CONDENSATE LINES SHALL BE 1 INCH. P-TRAPS AND CONDENSATE LINES MAY BE PVC WHERE NOT LOCATED IN PLENUMS; OTHERWISE, THEY SHALL BE TYPE M COPPER.
15. INSTALL BACKDRAFT DAMPERS ON FRESH AIR AND EXHAUST DUCTS WHERE THEY PENETRATE THE THERMAL ENVELOPE PER SECC C402.5.5
16. DUCTS CONNECTING TO A FURNACE SHALL HAVE A CLEARANCE TO COMBUSTIBLES IN ACCORDANCE WITH THE FURNACE MANUFACTURER'S INSTALLATION INSTRUCTIONS.
17. FOR STRUCTURES IN FLOOD HAZARD AREAS, DUCTS SHALL BE LOCATED ABOVE THE DESIGN FLOOD ELEVATION. DUCT SHALL NOT BE INSTALLED IN OR WITHIN 4 INCHES OF THE EARTH.
18. MC SHALL INSTALL FIRE DAMPERS AT EACH PENETRATION OF A RATED WALL AS INDICATED ON THE DRAWINGS OR AS REQUIRED BY THE AUTHORITY HAVING JURISDICTION. FIRE DAMPERS SHALL BE UL LABELED (UL 555), CURTAIN TYPE, WITH INTEGRAL FACTORY SLEEVE AND BLADES LOCATED OUTSIDE THE AIR STREAM. INSTALLATION OF ALL FIRE DAMPERS SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS AND SECTION 607 OF THE SMC. PROVIDE ACCESS PANELS FOR TESTING AND SERVICE AS NECESSARY. MC SHALL PROVIDE RADIATION DAMPERS AND THERMAL BLANKETS FOR ALL PENETRATIONS OF RATED CEILING ASSEMBLIES. RADIATION DAMPERS SHALL BE UL LABELED (UL 555C) AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFIC INSTALLATION INSTRUCTIONS. FIRE DAMPERS, COMBINATION FIRE/SMOKE DAMPERS, AND CEILING RADIATION DAMPERS SHALL BE BY RUSKIN, NAILOR, OR LLOYD INDUSTRIES.
19. MC SHALL INSTALL A SMOKE DETECTOR-UL LISTED FOR DUCT INSTALLATION (UL 268A) IN EACH UNIT'S RETURN UPSTREAM OF ANY FILTERS, OUTSIDE AIR CONNECTIONS, OR DECONTAMINATION EQUIPMENT. DUCT SMOKE DETECTORS SHALL BE INSTALLED IN ACCORDANCE WITH NFPA 72. DUCT SMOKE DETECTOR SUPERVISION SHALL COMPLY WITH 606.4.1 OF THE SMC. IF THE BUILDING IS (TO BE) EQUIPPED WITH A FIRE ALARM SYSTEM, THE FIRE ALARM SYSTEM CONTRACTOR SHALL FURNISH AND WIRE ALL DUCT SMOKE DETECTORS. IF THE BUILDING IS NOT PROVIDED WITH A FIRE ALARM SYSTEM, THE MC SHALL FURNISH AND WIRE THE DUCT SMOKE DETECTORS AND A/V DEVICE. IT SHALL BE THE RESPONSIBILITY OF THE MC TO INSTALL ALL SMOKE DUCT DETECTORS PER NFPA AND MFG'S INSTALLATION INSTRUCTIONS REGARDLESS OF WHO FURNISHES THE DEVICES.
20. UNITS PROVIDED WITH ECONOMIZERS SHALL ALSO BE PROVIDED WITH POWERED EXHAUST AND COMPARATIVE ENTHALPY CONTROLS.

MATERIALS:

1. THE MC SHALL PROVIDE ALL HEATING AND COOLING EQUIPMENT AS SCHEDULED ON THE DRAWINGS. ALTERNATES SHALL BE FROM MANUFACTURERS LISTED IN SCHEDULES. THE MC SHALL PROVIDE FACTORY AND FIELD INSTALLED ACCESSORIES AS SCHEDULED OR AS NECESSARY FOR A COMPLETE AND OPERATIONAL HVAC SYSTEM.
2. THE MC SHALL PROVIDE ALL EXHAUST AND SUPPLY FANS AS SCHEDULED OR BY EQUALS LISTED.
3. DUCTWORK IS SHOWN WITH FREE AREA DIMENSIONS. ALL DUCTWORK SHALL BE FABRICATED AND INSTALLED IN ACCORDANCE WITH SMACNA LOW PRESSURE DUCT STANDARD, 2 INCH S.P.
4. EXTERNAL DUCT INSULATION AND FACTORY-INSULATED FLEXIBLE DUCT SHALL BE LEGIBLY PRINTED OR IDENTIFIED AT INTERVALS NOT GREATER THAN 36 INCHES WITH THE NAME OF THE MANUFACTURER, THE THERMAL RESISTANCE R-VALUE AT THE SPECIFIED INSTALLED THICKNESS AND THE FLAME SPREAD AND SMOKE-DEVELOPED INDEXES OF THE COMPOSITE MATERIALS. ALL DUCT INSULATION PRODUCT R-VALUES SHALL BE BASED ON INSULATION ONLY, EXCLUDING AIR FILMS, VAPOR RETARDERS OR OTHER DUCT COMPONENTS, AND SHALL BE BASED ON TESTED C-VALUES AT 75°F MEAN TEMPERATURE AT THE INSTALLED THICKNESS, IN ACCORDANCE WITH RECOGNIZED INDUSTRY PROCEDURES. THE INSTALLED THICKNESS OF DUCT INSULATION USED TO DETERMINE ITS R-VALUES SHALL BE DETERMINED AS FOLLOWS:
   4.1. FOR DUCT BOARD, DUCT LINER AND FACTORY-MADE RIGID DUCTS NOT NORMALLY SUBJECTED TO COMPRESSION, THE NOMINAL INSULATION THICKNESS SHALL BE USED.
   4.2. FOR DUCT WRAP, THE INSTALLED THICKNESS SHALL BE ASSUMED TO BE 75 PERCENT (25-PERCENT COMPRESSION) OF NOMINAL THICKNESS.
   4.3. FOR FACTORY-MADE FLEXIBLE AIR DUCTS, THE INSTALLED THICKNESS SHALL BE DETERMINED BY DIVIDING THE DIFFERENCE BETWEEN THE ACTUAL OUTSIDE DIAMETER AND NOMINAL INSIDE DIAMETER BY TWO.
5. ALL INSULATION CONTAINING FIBROUS MATERIALS EXPOSED TO AIRFLOW SHALL BE RATED FOR THAT EXPOSURE OR SHALL BE ENCAPSULATED. INSULATING PROPERTIES FOR ALL MATERIALS SHALL MEET OR EXCEED INDUSTRY STANDARDS. POLYSTYRENE PRODUCTS SHALL MEET ASTM C578. ALL INSULATION SHALL HAVE FORMALDEHYDE EMISSIONS NOT GREATER THAN 0.05 PPM. THE MAXIMUM FLAME SPREAD AND SMOKE DEVELOPED INDEX FOR INSULATION SHALL MEET THE REQUIREMENTS OF THE LOCAL CODES AND ORDINANCES ADOPTED BY THE JURISDICTION IN WHICH THE BUILDING IS LOCATED.
6. MASTIC USED TO SEAL DUCTWORK SHALL BE LISTED AND LABELED IN ACCORDANCE WITH UL 181A OR UL 181B MAINTAIN AMBIENT TEMPERATURES AND CONDITIONS REQUIRED BY MANUFACTURER OF ADHESIVES, MASTICS, AND INSULATION CEMENTS. DO NOT INSTALL DUCT SEALANT WHEN TEMPERATURES ARE LESS THAT THOSE RECOMMENDED BY THE SEALANT MANUFACTURER.
7. ALL ADHESIVES AND SEALANTS SHALL HAVE VOC CONTENT BELOW 20 GRAMS PER LITER AND WHICH MEET THE REQUIREMENTS OF THE MANUFACTURER OF THE PRODUCTS BEING ADHERED OR INVOLVED. ADHESIVES AND SEALANTS SHALL CONTAIN NO HEAVY METALS OR FORMALDEHYDE.
8. FACTORY-MADE AIR DUCTS AND CONNECTORS SHALL COMPLY WITH UL 181.
9. FLEXIBLE DUCT SHALL BE UL LISTED CLASS 0 OR CLASS 1, INSULATED, AND COMPLY WITH UL 181. FLEXIBLE DUCT SHALL BE FACTORY FORMED, COMPOSED OF SPIRAL WOUND CORROSION RESISTANT WIRE BONDED TO AN INNER FABRIC LINER. DUCT SHALL BE FACTORY INSULATED WITH A FOIL VAPOR BARRIER JACKET. CONNECT TO RIGID DUCT WITH SPIN-IN FITTING AND DAMPER. FLEXIBLE DUCTS AND AIR CONNECTORS SHALL NOT PASS THROUGH ANY FIRE RESISTANCE RATED ASSEMBLY.
10. THE MC SHALL PROVIDE ALL DIFFUSERS GRILLES, LOUVERS, AND OTHER AIR DISTRIBUTION OUTLETS AND INLETS. LOUVERS, GRILLES, AND DIFFUSERS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. FOR LAY-IN CEILINGS, INSTALL SUPPORT FROM THE STRUCTURE FOR EACH DIFFUSER OR DAMPER, AIR DISTRIBUTION OUTLETS AND INLETS SHALL BE AS SCHEDULE OR ALTERNATES LISTED.
11. AIR FILTERS SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 605 OF THE SMC
12. THE MC SHALL PROVIDE ALL REFRIGERATION PIPING. ALL PIPE AND FITTINGS SHALL BE TYPE ACR HARD COPPER TUBING WITH SWEAT FITTINGS. REFRIGERATION LINES SHALL BE RUN NEATLY. WHERE A GROUP OF LINES ARE RUN, TRAPEZE HANGERS MAY BE USED. DO NOT USE CHAIN OR WIRE HANGERS. WRAP TUBING WITH RUBBER TAPE AT EACH CLAMP OR HANGER. FOR COVERED PIPES, HANGERS SHALL FIT AROUND THE OUTSIDE OF THE COVERING WITH 12 GAUGE GALVANIZED STEEL SHIELDS OF A LENGTH EQUAL TO THE OUTSIDE DIAMETER OF THE INSULATION AND COVERING 3/4 OF THE CIRCUMFERENCE OF THE INSULATION. SAGS SHALL NOT BE PERMISSIBLE. HORIZONTAL LINES SHALL PITCH DOWN NOT LESS THAN 1 INCH IN 40 FEET. INSULATE WITH 1 INCH CLOSED CELL ARMAFLEX TYPE INSULATION WITH A FLAME DENSITY RATING LESS THAN 25 AND A SMOKE DENSITY RATING LESS THAN 50. ALL JOINTS AND SPLICES IN INSULATION SHALL BE TAPED AND AIRTIGHT. SOLDER REFRIGERATION LINES USING 15 PERCENT SILVER SOLDER AND EVACUATE LINES TO 300 MICRONS. PROVIDE MOISTURE INDICATING SIGHT GLASS AND FILTER DRYER IN LIQUID LINE. PROVIDE OIL TRAPS AND DOUBLE RISERS IN REFRIGERANT SUCTION AND HOT GAS LINES WHERE REQUIRED TO PREVENT OIL SLUGGING AT THE COMPRESSOR AND INSURE PROPER LUBRICATION. MC SHALL BE RESPONSIBLE FOR SEALING LINE SET PENETRATIONS OF ANY RATED ASSEMBLIES IN ACCORDANCE WITH A SYSTEM LISTED IN THE UL DIRECTORY FOR THE SPECIFIC ASSEMBLY BEING PENETRATED. SEE ARCHITECTURAL PLANS FOR A LIST OF ALL UL FIRE RATED ASSEMBLIES.
13. DUCT LINER MAY BE SUBSTITUTED FOR EXTERIOR DUCT WRAP. DUCT LINER INSULATION MATERIALS SHALL MEET THE REQUIREMENTS OF ASTM C 1071, AND ASTM G 21. EXTERIOR DUCT R-VALUE AND INTERIOR R-VALUE SHALL BE IN ACCORDANCE WITH THE SECC. NOMINAL DUCT SIZES SHALL BE ADJUSTED AS NECESSARY SO THAT FREE AREA DIMENSIONS ARE PRESERVED AS SHOWN ON THE PLANS. FABRICATION AND INSTALLATION SHALL CONFORM TO THE MANUFACTURER'S INSTALLATION RECOMMENDATIONS AND TO THE REQUIREMENTS OF THE LATEST EDITION OF THE NORTH AMERICAN INSULATION MANUFACTURERS ASSOCIATION FIBROUS GLASS DUCT LINER STANDARDS AND/OR SMACNA HVAC DUCT CONSTRUCTION STANDARDS. DUCT LINER SHALL HAVE A BLACK PIGMENTED MAT ON THE AIRSTREAM SIDE TO RESIST DAMAGE DURING INSTALLATION AND SERVICE. EDGES SHALL BE FACTORY COATED WITH BLACK PIGMENTED COATING TO COMPLY WITH SMACNA DCS REQUIREMENTS. ALL PORTIONS OF DUCT DESIGNATED TO RECEIVE DUCT LINER SHALL BE COMPLETELY COVERED WITH DUCT LINER. TRANSVERSE JOINTS SHALL BE NEATLY BUTTED AND THERE SHALL BE NO INTERRUPTIONS OR GAPS. THE BLACK PIGMENTED OR MAT FACED SURFACES SHALL FACE THE AIRSTREAM. DUCT LINER SHALL BE ADHERED TO THE SHEET METAL WITH 90 PERCENT COVERAGE OF ADHESIVE COMPLYING WITH REQUIREMENTS OF ASTM C 916. ALL EXPOSED LEADING EDGES AND TRANSVERSE JOINTS SHALL BE FACTORY COATED OR COATED WITH ADHESIVE DURING FABRICATION. DUCT LINER SHALL BE ADDITIONALLY SECURED WITH MECHANICAL FASTENERS, EITHER WELD-SECURED OR IMPACT DRIVEN, WHICH SHALL COMPRESS THE DUCT LINER SUFFICIENTLY TO HOLD IT FIRMLY IN PLACE. ADHESIVE BONDED PINS ARE NOT PERMITTED DUE TO LONG-TERM ADHESIVE AGING CHARACTERISTICS. LININGS SHALL BE INTERRUPTED AT THE AREA OF OPERATION OF A FIRE DAMPER AND AT A MINIMUM OF 6 INCHES UPSTREAM AND 6 INCHES DOWNSTREAM OF ELECTRIC RESISTANCE AND FUEL-BURNING HEATERS IN A DUCT SYSTEM. METAL NOSINGS OR SLEEVES SHALL BE INSTALLED OVER EXPOSED DUCT LINER THAT FACE OPPOSITE THE DIRECTION OF AIRFLOW. UPON COMPLETION OF INSTALLATION OF DUCT LINER AND BEFORE OPERATION IS TO COMMENCE, VISUALLY INSPECT SYSTEM AND VERIFY THAT THE DUCT LINER IS PROPERLY INSTALLED. OPEN ALL SYSTEM DAMPERS AND TURN ON FANS TO BLOW ALL SCRAPS AND OTHER LOOSE PIECES OF MATERIAL OUT OF THE DUCT SYSTEM. ALLOW FOR A MEANS OF REMOVAL OF SUCH MATERIAL.

MECHANICAL DRAWING INDEX

SHEET NUMBER	SHEET TITLE
M-001	MECHANICAL NOTES
M-101	OVERALL MECHANICAL PLAN
M-102	ENLARGED OFFICE MECHANICAL PLAN
M-103	ENLARGED OFFICE EXHAUST PLAN
M-201	MECHANICAL SCHEDULES
M-301	MECHANICAL DETAILS

RECTANGULAR/SQUARE TO ROUND DUCT EQUIVALENT	
RECTANGULAR DUCT	ROUND DUCT
30"X26"	30"Ø
20"X26"	24"Ø
18"X18"	20"Ø
18"X20"	20"Ø
20"X16"	18"Ø
16"X16"	16"Ø
10"X16"	14"Ø
10"X20"	16"Ø
16"X14"	16"Ø
16"X12"	14"Ø

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY — KILIAN ENGINEERING, INC. — No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #ZC6110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WHITTER

PRINCIPAL IN CHARGE [redacted]

UPS SAV TENANT INPROVEMENT

MECHANICAL NOTES

REV:	DATE:	NOTE:
A	02/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

M-001


© 2025 STRATUS®

MECHANICAL PLAN HEX NOTES

1. EXISTING LOUVER AND EF TO BE RELOCATED FROM OFFICE LOCATION TO NEW LOCATION SHOWN. MC TO COORDINATE RELOCATED ELECTRICAL WITH EC. MC TO PATCH HOLE LEFT IN WALL WITH SIMILAR MATERIAL AND PAINT WITH SIMILAR COLOR AS EXISTING.
2. EXISTING GUH-1 TO REMAIN IN SPACE MC TO COORDINATE EXACT LOCATION WITH UPS ON SITE.

MECHANICAL PLAN GENERAL NOTES

1. ALL EXISTING LOUVERS, EXHAUST FANS, AND GAS UNIT HEATERS NOT SHOWN ON PLANS EXISTING TO REMAIN. MC TO CLEAN, INSPECT, AND VERIFY EXISTING EQUIPMENT IN GOOD WORKING ORDER AND REPLACE LIKE FOR LIKE IF NOT.



1 OVERALL MECHANICAL PLAN
Scale: 1/8" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338

DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. LAWTER

PRINCIPAL IN CHARGE
[redacted]

OVERALL MECHANICAL PLAN

UPS SAV TENANT INPROVEMENT


REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION


M-101

© 2025 STRATUS®

MECHANICAL PLAN HEX NOTES
1. MC TO COORDINATE WITH GC AND EC LOCATION OF HP BEFORE START OF WORK.



1 ENLARGED OFFICE MECHANICAL PLAN
Scale: 1/4" = 1'-0"



2 ENLARGED GSE MECHANICAL PLAN
Scale: 1/4" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WATTS

PRINCIPAL IN CHARGE
[redacted]

ENLARGED OFFICE MECHANICAL PLAN


UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

M-102

© 2025 STRATUS®



1 ENLARGED OFFICE EXHAUST PLAN

Scale: 1/4" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338

DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WATER

PRINCIPAL IN CHARGE
[redacted]

ENLARGED OFFICE EXHAUST PLAN

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

M-103

© 2025 STRATUS®

SPLIT SYSTEM HEAT PUMP SCHEDULE

MARK	MFG/MODEL #	NOMINAL CAPACITY	REF LINES		MOTORS		EFFICIENCIES			ELECTRICAL			REFRIGERANT		WEIGHT	REMARKS
		TONS	GAS	LIQ	COMPRESSOR NO.	COND. FAN NO.	SEER EER	COP @ 17°	HSPF	V/PH	MCA	MOCP	TYPE	AMOUNT LBS	LBS	
HP-1,2	YORK YH436E2S11	3	3/4	3/8	1	1	14.3/11	4.4	7.5	208/1	20.4	30	R-454B	5.08	165	1,3,5,6,8-10

SPLIT SYSTEM AIR HANDLER SCHEDULE

MARK	MFG/MODEL #	NOMINAL CAPACITY	AIR FLOW		FAN MOTORS		HEATING CAPACITY			COOLING CAPACITY				ELECTRICAL			WEIGHT	REMARKS
								AUX ELEC HEAT										
		TON	SUPPLY CFM	MIN. OA	SUPPLY NO.	ESP IN WG	OUTPUT MBH	KW	STAGE	EAT WB/DB °F	TOTAL MBH	SENSIBLE MBH	LATENT MBH	V/PH	MCA	MOCP	LBS	
AHU-1	YORK JHE36C5CD2SS1	3	1200	300	1	.5	36.7	5.8	1	67/80	34.6	26	8.6	208/1	40.9	45	111	2,4-10
AHU-2	YORK JHE36C5CD2SS1	3	1000	300	1	.5	36.7	5.8	1	67/80	33	21.9	11.1	208/1	40.9	45	111	2,4-10

1. PROVIDE CONCRETE PAD FOR UNIT TO SIT ON
2. PROVIDE HEAT STRIP OUTDOOR TEMPERATURE LOCKOUT TO PREVENT SUPPLEMENTAL HEAT OPERATION IN RESPONSE TO THE THERMOSTAT BEING CHANGED TO A WARMER SETTING. SET NO LOWER THAN 35° F AND NO HIGHER THAN 40° F. FOR USE WITH HEAT PUMP OR AC WITH STRIP HEAT.
3. PROVIDE HAIL GUARDS FOR COIL
4. REPLACE ALL FILTERS AT PROJECT'S COMPLETION
5. PROVIDE 7-DAY PROGRAMMABLE THERMOSTAT WITH NIGHT-TIME SET BACK
6. CONSULT MANUFACTURER ON LINE SET LENGTHS EXCEEDING 60 FT (FOR SPLIT SYSTEM'S ONLY)
7. HEATER RATED AT 208V
8. OR EQUAL BY DAIKIN, CARRIER, LENNOX, OR TRANE
9. ANY EQUIPMENT SUBSTITUTIONS MUST EQUAL OR EXCEED EFFICIENCIES LISTED (RATING PER ARI)
10. MAINTAIN MANUFACTURER'S RECOMMENDED CLEARANCES.

DUCTLESS MINI-SPLIT SYSTEM SCHEDULE

OUTSIDE MARK	OUTSIDE UNIT MFG/MODEL #	INSIDE MARK	INSIDE UNIT MFG/MODEL #	NOMINAL CAPACITY	SUPPLY AIR	TOTAL COOLING	SENSIBLE COOLING	LATENT COOLING	SEER	EER	REFRIGERANT		ELECTRICAL				REMARKS
					CFM	MBH	MBH	MBH			TYPE	AMMOUNT(LBS)	V/PH	MCA	MOCP	RFS	
MS-1	MITSUBISHI PUY-AK36NL	MS1-A	PKA-AK36NL	3	920	33.4	20.4	13	20.3	12	R454B	9.88	208/1	34	56	35	1-6
MS-2	MITSUBISHI PUY-AK36NL	MS2-A	PKA-AK36NL	3	920	33.4	20.4	13	20.3	12	R454B	9.88	208/1	34	56	35	1-6

1. OR APPROVED EQUAL BY MITSUBISHI
2. PER STATE MECHANICAL CODE 402.1 & 402.2. THE SPACE MEETS NATURAL VENTILATION REQUIREMENTS OF OPERABLE SPACE EQUALING GREATER THAN 4% OF SQUARE FOOTAGE
3. INDOOR UNITS POWERED BY OUTDOOR UNITS
4. PROVIDE EACH INDOOR UNIT WITH OWN CONTROLLER. PROVIDE WITH WIRED CONTROLLERS MOUNTED AT 48" AFF BELOW RESPECTIVE INDOOR UNIT
5. PROVIDE CONDENSATE PUMPS AS NEEDED FOR INDOOR UNITS. INSTALL BLUE DIAMOND FASCIA KIT T18-016 COMPATIBLE WITH MICRO BLUE X85-003 CONDENSATE PUMP
6. ENSURE EACH UNIT HAS SURGE PROTECTION

ERV SCHEDULE

MARK	MFG	MODEL #	CFM	V/PH	MCA	MOCP	NOTES
ERV-1	RENEWAIRE	HE10-JINH-S15EE	600	208/3	4	15	1

1. OR EQUAL, PROVIDE WITH ALL NECESSARY ACCESSORIES FOR COMPLETE INSTALLATION

REGISTER & GRILLE SCHEDULE

MARK	MFG	MODEL #	SIZE	MOUNTING	DESCRIPTION	NOTES
A	TITUS	OMNI	24X24	LAY-IN	STEEL, 4-WAY DIFFUSER, BRIGHT WHITE	1,2
B	TITUS	OMNI	12X12	SURFACE	STEEL, 4-WAY DIFFUSER, BRIGHT WHITE	1
R	TITUS	PAR-NT	24X24	LAY-IN	STEEL, LAY IN RETURN GRILLE	1,2
EX	TITUS	PAR	12X12	SURFACE	STEEL, SURFACE MOUNT RETURN GRILLE	1

1. OR EQUAL BY AIRGUIDE MFG, ANEMOSTAT PRODUCTS, CARNES CO., OR KRUEGER MFG
2. PROVIDE WITH FOIL LINED, MOLDED INSULATION BLANKET.

AIR COMPRESSOR SCHEDULE

MARK	MFG	MODEL #	CAPACITY @ 90 PSI CFM	MAX PRESSURE PSIG	NOMINAL POWER (HP)	VOLTAGE	TANK SIZE/ CONFIGURATION
AC-1	INGERSOLL-RAND	2475N7.5	24.3	175	7.5	230/1/60	80 GALLON VERTICAL

LOUVER SCHEDULE

MARK	MFG	MODEL #	SIZE	MOUNTING	DESCRIPTION	NOTES
L1	GREENHECK	EHV-901D	50X50	WALL	EXISTING EXHAUST LOUVER PAIRED WITH EF-1	1,2

1. EXISTING LOUVER TO REMAIN.
2. MC TO CLEAN, INSPECT, AND VERIFY LOUVER, SCREEN, AND DAMPER ARE IN GOOD WORKING ORDER

GAS UNIT HEATER SCHEDULE

MARK	MFG/MODEL #	INPUT	HEAT OUTPUT	AIR FLOW	VOLT/PH	FLA	MOCP	NOTES
		MBH	MBH	CFM		AMPS	AMPS	
GUH-1	STERLING XF-100	100	83	1600	120/1	2	20	1

1. HEATER EXISTING TO REMAIN, EC TO CLEAN, INSPECT, AND VERIFY IN GOOD WORKING ORDER.

EXHAUST FAN SCHEDULE

MARK	MFG/MODEL #	TYPE	ESP (in WG)	CFM	VOLT/PH	FLA	SONES	NOTES
EF-1	GREENHECK AER-E42C-605-VG	SIDE WALL	0.40	5010	480/3	4.25	2	1-5
EF-2	CARMON CMB-20	INLINE	1	1050	208/1	8.625	2	1-3

1. PROVIDE WITH PITCHED ROOF CURB & CAP FOR FLAT OR SLOPED ROOF, OR HOODED WALL WITH BACK DRAFT DAMPER CAP AS APPLICABLE
2. PROVIDE WITH SQUARE TO ROUND DUCT ADAPTER AS NECESSARY
3. OR EQUAL BY LOREN COOK OR PENNBARRY OR TWIN CITY
4. EXISTING EXHAUST FAN. MC TO CLEAN, INSPECT, AND VERIFY IN GOOD WORKING ORDER
5. MC TO VERIFY EXISTING FAN IS INSTALLED WITH BUG SCREEN & BACK DRAFT DAMPER

HVAC REFRIGERANT CALCULATION PER ASHRAE 15

UNIT TAG	REFRIGERANT TYPE	AMOUNT	SPACE/ZONE VOLUME	MAX ALLOWED PER TABLE 4.2	TOTAL AMOUNT ALLOWED	COMPLIANT
		LBS	FT^3	$LBS/1000FT^3$	LBS	
AHU-1	R454B	5.08	12015	3.1	37.2465	YES
AHU-2	R454B	5.08	11925	3.1	36.9675	YES

MS-1 & 2 - REFRIGERANT CHARGE IN SYSTEM IS 9.92LM < 22LB. SYSTEM IS NOT LOCATED IN A PUBLIC CORRIDOR OR LOBBY. THEREFORE SYSTEM CHARGE IN COMPLIANCE IF INSTALLED IN ACCORDANCE WITH LISTING & OEM INSTRUCTIONS PER FIGURE 7-1 FROM ASHRAE 15

MECHANICAL SYSTEM, SERVICE SYSTEMS, AND EQUIPMENT

METHOD OF COMPLIANCE:	PRESCRIPTIVE
THERMAL ZONE:	ZONE 2A
EXTERIOR DESIGN CONDITIONS:	
HEATING DESIGN DRY BULB	27.8°F
COOLING DESIGN DRY BULB	95.4°F
COOLING DESIGN WET BULB	77.6°F
INTERIOR DESIGN CONDITIONS:	
HEATING DESIGN DRY BULB	70°F
COOLING DESIGN DRY BULB	75°F
COOLING RELATIVE HUMIDITY	50%
HEATING LOAD:	47,177 BTU/H
SENSIBLE COOLING LOAD:	33,090 BTU/H
LATENT COOLING LOAD:	27,390 BTU/H
MECHANICAL SPACING CONDITIONING SYSTEM:	
UNITARY	AIR COOLED DX
DESCRIPTION OF UNIT(S)	2 - 3-TON SPLIT SYSTEM UNITS
BOILER	N/A
TOTAL BOILER OUTPUT	N/A
CHILLER	N/A
TOTAL CHILLER CAPACITY	N/A
EQUIPMENT EFFICIENCIES:	SEE SCHEDULES
EQUIPMENT SCHEDULES WITH MOTORS (MECHANICAL SYSTEMS):	SEE SCHEDULES
DESIGNER STATEMENT:	

TO THE BEST OF MY KNOWLEDGE, THE MECHANICAL DESIGN FOR THIS BUILDING COMPLIES WITH MECHANICAL AND EQUIPMENT REQUIREMENTS OF THE STATE BUILDING CODE AND ENERGY CONSERVATION CODE

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY — KILIAN ENGINEERING, INC. — No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #ZC6110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. LAWTER

PRINCIPAL IN CHARGE
[redacted]

NOTE: ADDENDUM A
DATE: 03/18/2026
REV: A


02/20/2026
ISSUED FOR CONSTRUCTION

UPS SAV TENANT INPROVEMENT

MECHANICAL SCHEDULES


M-201

© 2025 STRATUS®




1 TYPICAL FLEXIBLE DUCT HANGER SUPPORT DETAIL

Scale: None



2 TYPICAL OVERHEAD AIR HANDLER

Scale: None




NOTE:

1. PITCH ALL LINES DOWN IN DIRECTION OF REFRIGERANT FLOW (1/2" IN 10'-0")
2. MAXIMUM FILTER-DRYER PRESSURE DROPS - 2 P.S.I. ON SUCTION, 1 P.S.I. ON LIQUID.
3. PROVIDE ISOLATION VALVES ON ALL CONDENSING UNIT LINES.
4. INSULATE ALL SUCTION LINES.
5. TRAP ALL SUCTION GAS RISERS HAVING A VERTICAL LIFT OF 5'-0" OR MORE.


3 REFRIGERANT LINE DETAIL

Scale: None



4 GROUND MOUNTED HVAC SLAB DETAIL


Scale: None



NOTE: FOR L, 1D MINIMUM, 3D PREFERRED. WHEN LENGTH OF STRAIGHT DUCT UPSTREAM OF DIFFUSER IS LESS THAN 3D, PROVIDE AN EQUALIZING GRID

5 DIFFUSER RUN-OUT FLEX DETAIL

Scale: None



NOTES: ALL SUPPLY DUCTS ARE INSULATED. (SEE SPECS FOR INSULATION TYPE.) SINGLE BLADE DAMPERS SHOWN. PROVIDE MULTIBLADE DAMPERS FOR ALL DUCTS 12" DEEP AND LARGER

6 DUCT SUPPORT AND LAYOUT DETAIL

Scale: None

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC. No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #ZZ6110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WHITE

PRINCIPAL IN CHARGE
[redacted]

MECHANICAL DETAILS

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

M-301

© 2025 STRATUS®

GENERAL ELECTRICAL NOTES:

ADMINISTRATIVE:

1. THE FOLLOWING ABBREVIATIONS SHALL APPLY TO NOTES AND PLANS:
   PC - PLUMBING CONTRACTOR,
   EC - ELECTRICAL CONTRACTOR,
   MC - MECHANICAL CONTRACTOR,
   GC - GENERAL CONTRACTOR,
   FASC - FIRE ALARM SYSTEM CONTRACTOR,
   AHJ - AUTHORITY HAVING JURISDICTION
   NECA- NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION
   NEC- NATIONAL ELECTRICAL CODE
   SBC- CURRENT STATE BUILDING CODE (INTERNATIONAL BUILDING CODE WITH GEORGIA AMENDMENTS)
   SFC- CURRENT STATE BUILDING CODE: FIRE CODE (INTERNATIONAL FIRE CODE)
2. "PROVIDE" MEANS TO FURNISH AND INSTALL. THE EC SHALL ALSO INSTALL MATERIALS AND EQUIPMENT FURNISHED BY OTHERS AND THE GENERAL CONTRACTOR AS REQUIRED.
3. EC SHALL PROVIDE LABOR, MATERIALS, EQUIPMENT, AND SERVICES NECESSARY AND REASONABLY INCIDENTAL TO INSURE A COMPLETE AND OPERATIONAL ELECTRICAL SYSTEM IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS. MINOR ITEMS, ACCESSORIES, AND DEVICES REASONABLY INFERABLE AS NECESSARY FOR THE COMPLETION AND PROPER OPERATION OF ANY ELECTRICAL SYSTEM SHALL BE PROVIDED BY THE EC.
4. WORKMANSHIP SHALL BE IN ACCORDANCE WITH NECA 1 "STANDARD PRACTICE FOR GOOD WORKMANSHIP IN ELECTRICAL CONTRACTING."
5. ALL MATERIALS AND EQUIPMENT SHALL BE DELIVERED TO THE SITE AND UNLOADED BY THE EC AT AN APPROVED LOCATION. THE EC SHALL PROTECT ALL MATERIALS AND EQUIPMENT FROM BREAKAGE, THEFT, AND THE ELEMENTS. ALL MATERIALS AND EQUIPMENT SHALL REMAIN THE PROPERTY OF THE EC UNTIL THE PROJECT HAS BEEN COMPLETED AND TURNED OVER TO THE OWNER.
6. THE EC SHALL OBTAIN AND PAY FOR ALL PERMITS, FEES, AND INSPECTIONS NECESSARY FOR THE COMPLETION OF THE WORK UNDER THIS CONTRACT.
7. DO NOT SCALE THESE DRAWINGS-REFER TO ARCHITECTURAL SHEETS FOR DIMENSIONS.
8. TRADE NAMES AND MANUFACTURERS ARE SPECIFIED TO ESTABLISH A QUALITY STANDARD. SUBSTITUTIONS SHALL BE PERMITTED IF APPROVED BY THE ENGINEER PRIOR TO INSTALLATION. ALL LISTED MODEL NUMBERS SHALL BE VERIFIED WITH THE MANUFACTURER FOR PROPER APPLICATION OF EQUIPMENT.
9. THE EC SHALL VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH EXISTING CONDITIONS. THE EC SHALL CONTACT THE ENGINEER TO RESOLVE ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS AND THESE PLANS. THE EC SHALL COORDINATE WITH OTHER TRADES PRIOR TO THE START OF CONSTRUCTION.
10. GROUNDING AND BONDING SHALL BE PER NEC ARTICLE 250. THE RACEWAY SYSTEM SHALL NOT BE RELIED UPON FOR GROUNDING CONTINUITY. A GREEN EQUIPMENT GROUNDING CONDUCTOR, SIZED PER NEC TABLE 250-122, SHALL BE RUN IN ALL POWER RACEWAYS. FOR NON-ISOLATED GROUND CIRCUITS PROVIDE ONE EQUIPMENT GROUNDING CONDUCTOR PER CONDUIT RUN. FOR ISOLATED GROUND CIRCUITS, PROVIDE ONE NEUTRAL AND ONE ISOLATED GROUND WIRE FOR EACH CIRCUIT. IN ADDITION, PROVIDE ONE EQUIPMENT GROUNDING CONDUCTOR PER CONDUIT RUN. MAIN BONDING JUMPERS AND SYSTEM BONDING JUMPERS SHALL BE INSTALLED IN ACCORDANCE WITH 250.28 OF THE NEC. FOR BUILDINGS OR STRUCTURES SUPPLIED BY FEEDERS OR BRANCH CIRCUITS, GROUNDING AND BONDING SHALL BE IN ACCORDANCE WITH NEC 250.32. SEPARATELY DERIVED AC SYSTEMS SHALL BE GROUNDED IN ACCORDANCE WITH NEC 250.30. RESISTANCE TO GROUND SHALL NOT EXCEED 25 OHMS; ADDITIONAL GROUNDING ELECTRODES SHALL BE INSTALLED PER 250.56 AS NECESSARY.
11. ALL MATERIALS AND EQUIPMENT SHALL COMPLY WITH THE UNDERWRITERS' LABORATORIES, INC. STANDARDS OR HAVE UL APPROVAL, OR BEAR UL RE-EXAMINATION LISTING WHERE SUCH APPROVAL HAS BEEN ESTABLISHED FOR THE TYPE OF DEVICE IN QUESTION.
12. CONDUCTORS, FUSES, CIRCUIT BREAKERS, AND DISCONNECT SWITCHES SHOWN ON THESE PLANS HAVE BEEN SIZED FOR THE SPECIFIED EQUIPMENT. BEFORE ORDERING ELECTRICAL EQUIPMENT, THE EC SHALL COORDINATE WITH OTHER CONTRACTORS ON THE SITE AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES SHOULD CONDUCTOR, CIRCUIT BREAKER, OR FUSE SIZES REQUIRE CHANGE.
13. THE EC SHALL COORDINATE WITH THE GC TO ENSURE THE FOLLOWING MATERIALS ARE RECYCLED DURING THE CONSTRUCTION PHASE OF THE PROJECT: LIGHT FIXTURES, INCLUDING PROPER DISPOSAL OF BALLASTS, FLUORESCENT LIGHT BULBS, AND TRANSFORMERS, WIRING AND ELECTRICAL EQUIPMENT, AND INSULATION. WASTE MATERIALS CONTAINING LEAD, ASBESTOS, PCBS (FLUORESCENT LAMP BALLASTS), OR OTHER HARMFUL SUBSTANCES SHALL BE HANDLED AND DISPOSED OF IN ACCORDANCE WITH FEDERAL AND STATE LAWS AND REQUIREMENTS CONCERNING HAZARDOUS WASTE.
14. ALL WORK SHALL CONFORM TO NEC, SBC, AND ALL APPLICABLE LOCAL CODES.
15. THE EC SHALL ALSO COORDINATE WITH THE GC REGARDING THE BONDING OF THE FOOTING REBAR, SO THAT IT WILL BE IN PLACE AND READY AT TIME OF FOOTING INSPECTION.

METHODS:

1. EC SHALL REVIEW THE MECHANICAL PLANS TO ESTABLISH POINTS OF CONNECTION AND THE EXTENT OF THE ELECTRICAL WORK TO BE PROVIDED IN THE CONTRACT.
2. ALL CIRCUIT BREAKERS FEEDING HVAC EQUIPMENT SHALL BE HACR BREAKERS. ALL BRANCH CIRCUIT CONDUCTORS SHALL BE MINIMUM #12 AWG IN 3/4 IN CONDUIT. EACH MULTI-WIRE BRANCH CIRCUIT SHALL BE PROVIDED WITH A MEANS TO SIMULTANEOUSLY DISCONNECT ALL UNGROUNDED CONDUCTORS AT THE SOURCE PER NEC 210.4(B). GROUP ALL CONDUCTORS OF EACH MULTI-WIRE BRANCH CIRCUIT PER 210.4(D) WITH WIRE TIES OR SIMILAR MEANS. DO NOT EXCEED THREE HOMERUNS PER CONDUIT. DO NOT INSTALL ISOLATED GROUND AND NON-ISOLATED GROUND CIRCUITS IN THE SAME CONDUIT. INSTALL CONDUCTORS OF DIFFERENT VOLTAGES IN SEPARATE CONDUITS.
3. ALL LIGHT FIXTURES SHALL BE SUPPORTED INDEPENDENTLY OF THE SUSPENDED CEILING. COORDINATE LIGHTING LAYOUT WITH CEILING GRID, MECHANICAL EQUIPMENT, DUCTWORK AND SPRINKLER HEADS AS NECESSARY. SEE REFLECTED CEILING PLAN FOR DETAILS. FLUORESCENT FIXTURES UTILIZING DOUBLE-ENDED LAMPS MUST HAVE A DISCONNECTING MEANS COMPLYING WITH NEC 410.130(G).
4. MOUNT LIGHT SWITCHES AT 48 IN AFF. MULTIPLE SWITCHES AT SAME LOCATION SHALL BE UNDER ONE WALL PLATE. VERIFY WALL PLATE COLOR AND MATERIAL WITH THE ARCHITECT/OWNER. INSTALL SWITCHES WITH OFF POSITION DOWN. ALL SWITCHES SHALL BE HEAVY DUTY, IVORY PLASTIC WITH TOGGLE HANDLE, RATED 120-277V AC, AND COMPLYING WITH NEMA WD 6 AND WD 1. SWITCHES SHALL BE BY COOPER WIRING DEVICES, LEVITON MANUFACTURING, PASS & SEYMOUR, OR HUBBELL. PROVIDE BOX DEVICE PARTITION/DIVIDERS FOR MULTI-GANG BOXES FOR COMPLIANCE WITH NEC 404.8(B).
5. EC SHALL PROVIDE FIRE-STOPPING AT ALL ELECTRICAL PENETRATIONS OF RATED FLOORS AND WALLS TO PRESERVE OR RESTORE THE FIRE-RESISTANCE RATING. SEAL PENETRATIONS USING A UL LISTED SYSTEM FOUND IN THE UL DIRECTORY SPECIFIC TO THE UL LISTING OF THE ASSEMBLY BEING PENETRATED. SEE ARCHITECTURAL PLANS FOR UL RATED ASSEMBLIES SPECIFIC TO THIS PROJECT.
6. EC SHALL PROVIDE GFCI RECEPTACLES IN KITCHENS, RESTROOMS, OUTDOORS, AND IN SHOP AREAS AS REQUIRED BY NEC 210.8. REFRIGERATORS AND WATER COOLERS MUST HAVE A DEDICATED GFCI BREAKER. EACH OUTDOOR HVAC UNIT MUST HAVE A GFCI RECEPTACLE WITHIN 25 FEET FOR SERVICING. GFCI RECEPTACLES SHALL CONFORM TO UL 943 CLASS A AND UL 498 STANDARDS. SHOW WINDOW RECEPTACLES SHALL BE PROVIDED IN ACCORDANCE WITH 210.62 OF THE NEC. RECEPTACLES SHALL BE BY COOPER WIRING DEVICES, LEVITON MANUFACTURING, PASS & SEYMOUR, OR HUBBELL. ALL RECEPTACLES SHALL BE 125V RATED, HEAVY DUTY, AND COMPLY WITH NEMA WD 6 AND WD 1.
7. LOCATIONS AND HEIGHTS OF ALL WALL-MOUNTED DEVICES SHALL BE COORDINATED WITH THE ARCHITECT PRIOR TO INSTALLATION.
8. CONCEAL ALL CONDUIT EXCEPT IN MECHANICAL ROOMS OR UNFINISHED AREAS AS NOTED. USE EMT CONDUIT FOR ALL BRANCH CIRCUITS AND FEEDERS INSIDE THE BUILDING. TYPE MC CABLE AND TYPE AC CABLE MAY BE INSTALLED WITHIN WALLS IF ALL NEUTRAL WIRES, ISOLATED GROUND WIRES, AND EQUIPMENT GROUND WIRES AS LISTED ABOVE ARE CONTAINED IN THE CABLE. *** TYPE NM CABLE MAY BE USED FOR INTERIOR BRANCH CIRCUITS IN NORMALLY DRY LOCATIONS SUBJECT TO THE RESTRICTIONS OF NEC 334.10 AND 334.12. TYPE NM CABLE CONDUCTORS SHALL BE DERATED PER NEC 334.80. *** FLEXIBLE CONNECTIONS TO MOTORS AND OTHER EQUIPMENT SHALL BE MADE USING WEATHERPROOF FLEXIBLE CONDUIT. FOR LAY-IN LIGHT FIXTURES, USE MAXIMUM OF SIX (6) FEET OF FLEXIBLE MC CABLE (OR THE FLEXIBLE CONDUIT PROVIDED BY THE FIXTURE MANUFACTURER). SCHEDULE 40 PVC CONDUIT MAY BE USED FOR THE SECONDARY UNDERGROUND SERVICE, UNDERGROUND TELEPHONE SERVICE, AND BRANCH AND FEEDER CIRCUITS UNDER SLAB OR EXTERIOR TO THE BUILDING. EXPOSED EXTERIOR CONDUIT SHALL BE SCHEDULE 80 PVC. ALL UNDERGROUND RACEWAYS SHALL BE IDENTIFIED WITH UNDERGROUND LINE MARKING TAPE 6-8 IN BELOW GRADE DIRECTLY ABOVE THE RACEWAY. PROVIDE PULL WIRE IN EMPTY CONDUITS. UPSIZE CONDUIT FROM MINIMUM SIZE AS NECESSARY FOR LONGER PULLS. UNDERGROUND RACEWAYS THAT STUB INTO THE BOTTOM OF SWITCHBOARDS, OUTDOOR TRANSFORMERS, GENERATORS, ETC., SHALL RISE AT LEAST 2 IN ABOVE THE FINISHED SLAB TO PREVENT WATER FROM DRAINING INTO THE RACEWAYS. RACEWAYS THAT PENETRATE EXTERIOR WALLS OR INTERIOR PARTITIONS SEPARATING SPACES THAT WILL BE AT SIGNIFICANTLY DIFFERENT TEMPERATURES SHALL BE SEALED IN ACCORDANCE WITH ARTICLES 300.5(G), 300.7(A), AND 300.50(F) OF THE NEC. ROUTE CONDUIT IN AND UNDER SLAB FROM POINT-TO-POINT. ROUTE EXPOSED CONDUIT AND CONDUIT INSTALLED ABOVE ACCESSIBLE CEILINGS PARALLEL AND PERPENDICULAR TO WALLS. COMPLETELY AND THOROUGHLY SWAB ALL RACEWAYS BEFORE INSTALLING WIRE. PULL ALL CONDUCTORS INTO EACH RACEWAY AT ONE TIME. USE A SUITABLE WIRE PULLING LUBRICANT FOR BUILDING WIRE #4 AWG AND LARGER.
9. CABLES, RACEWAYS, OR BOXES, INSTALLED IN EXPOSED OR CONCEALED LOCATIONS UNDER METAL-CORRUGATED SHEET ROOF DECKING, SHALL BE INSTALLED AND SUPPORTED SO THERE IS NOT LESS THAN 1-1/2 IN MEASURED FROM THE LOWEST SURFACE OF THE ROOF DECKING TO THE TOP OF THE CABLE, RACEWAY, OR BOX. A CABLE, RACEWAY, OR BOX SHALL NOT BE INSTALLED IN CONCEALED LOCATIONS IN METAL-CORRUGATED, SHEET DECKING-TYPE ROOF. SEE NEC 300.4(E)
10. THE EC SHALL PROVIDE ALL OUTLET, JUNCTION, PULL BOXES, FITTINGS, AND SUPPORTS. ALL OUTLET AND JUNCTION BOXES SHALL BE GALVANIZED STEEL TYPE BY APPLETON, STEEL CITY, OR RACO. EXTERIOR BOXES SHALL BE TYPE FS. VAPORTITE BOXES SHALL BE TYPE GS. WHERE SURFACE MOUNTED BOXES ARE USED, THOSE BOXES AND THEIR FACEPLATES SHALL HAVE ROUNDED CORNERS. BOXES INSTALLED IN FLOORS SHALL BE RATED FOR THE APPLICATION. MOUNT JUNCTION AND OUTLET BOXES FLUSH WITH FINISH SURFACES UNLESS OTHERWISE NOTED.
10. WHERE MOUNTING HEIGHTS ARE GIVEN, THEY SHALL BE MEASURED FROM THE FINISHED FLOOR TO THE CENTER OF THE BOX. ALL BOXES SHALL BE SIZED PER NEC ARTICLE 314. ALL OUTLET AND JUNCTION BOXES SHALL HAVE A COVER PLATE, PROVIDED BY THE EC. OUTLET BOXES IN RATED WALLS SHALL BE INSTALLED IN ACCORDANCE WITH SBC 714.4.2 (MAXIMUM BOX SIZE IS 16 SQUARE IN AND MAXIMUM OF SIX (6) BOXES PER 100 SQUARE FEET). INSTALL OUTLET BOXES IN RATED WALLS SUCH THAT OPENINGS OCCUR IN ONE SIDE ONLY WITHIN ANY GIVEN STUD SPACE. ALL CLEARANCES BETWEEN THE OUTLET BOX AND THE GYPSUM BOARD SHALL BE FILLED WITH JOINT COMPOUND OR OTHER APPROVED FIRE STOP MATERIAL. FLUSH MOUNTED JUNCTION BOXES IN ADJACENT ROOMS SHALL NOT BE MOUNTED BACK-TO-BACK. SURFACE MOUNTED FIXTURES SHALL BE SECURED THROUGH FLUSH MOUNTED 4X4 OCTAGONAL OR SQUARE BOXES.
11. ALL CONDUIT, BOXES, AND ELECTRICAL EQUIPMENT SHALL BE FIRMLY AND SECURELY FASTENED TO OR SUPPORTED FROM THE BUILDING STRUCTURAL MEMBERS OR EMBEDDED IN CONCRETE OR MASONRY. ELECTRICAL SUPPORTS SHALL NOT BE ATTACHED TO DUCTWORK, PIPING, OR THEIR SUPPORTS. HANGERS SHALL BE CATALOG ITEMS COMPATIBLE WITH AND SUITABLE FOR THE INTENDED USE. FOR METAL ROOF DECK INSTALLATIONS, 1 IN EMT CONDUIT MAXIMUM AND 4 IN JUNCTION BOXES MAXIMUM MAY BE SUPPORTED BY DECKING. THE SUSPENDED CEILING SYSTEM SHALL NOT BE USED FOR THE SUPPORT OF ELECTRICAL RACEWAY SYSTEMS OR SUPPORT OF COMMUNICATIONS OR DATA SYSTEMS WIRING. CONTRACTOR SHALL COMPLY WITH 1613 OF THE SBC.
12. ALL TELEPHONE AND COMMUNICATIONS OUTLETS AND RACEWAYS ARE ROUGH-INS ONLY. EACH TELEPHONE AND COMMUNICATIONS OUTLET SHALL BE A 4 IN SQUARE BY 2-1/8 IN DEEP BOX WITH 3/4 IN KNOCK-OUTS AND A 3/4 IN CONDUIT STUBBED FROM THE OUTLET BOX TO ABOVE THE CEILING. PROVIDE A NON-METALLIC INSULATING BUSHING ON ALL CONDUITS STUBBED ABOVE THE CEILING. PROVIDE A BLANK COVER PLATE ON ALL OUTLET BOXES.
13. EC SHALL INSTALL DISCONNECT SWITCHES IN SIGHT OF ALL HARDWIRED EQUIPMENT AND APPLIANCES OR PROVIDE BREAKERS CAPABLE OF BEING LOCKED IN THE OPEN POSITION PER NEC 422.31. FOR MOTOR DRIVEN APPLIANCES, PROVIDE A DISCONNECTING MEANS PER NEC 422.31 AND 430 PART IX. WHERE AN INDIVIDUAL DISCONNECT SWITCH, CIRCUIT BREAKER, STARTER, ETC, IS SHOWN ON THE PLANS ADJACENT TO ITS LOAD AND NOT LOCATED ON A WALL, PROVIDE NECESSARY MATERIALS AND LABOR TO SUPPORT THE DEVICE.
14. EC SHALL FIELD IDENTIFY ALL SWITCH BOARD, PANEL BOARDS, CONTROL PANELS, METER SOCKETS, ETC., TO WARN QUALIFIED PERSONS OF POTENTIAL ELECTRICAL ARC FLASH HAZARDS PER 110.16 OF NEC.
15. EC SHALL PROVIDE NAMEPLATES FOR IDENTIFICATION OF ALL EQUIPMENT, SWITCHES, PANELS, ETC. THE NAMEPLATES SHALL BE LAMINATED PHENOLIC PLASTIC, BLACK FRONT, AND BACK WITH WHITE CORE, WHITE ENGRAVED LETTERS (1/4 IN MINIMUM) ETCHED INTO THE WHITE CORE. EC SHALL PROVIDE A TYPE WRITTEN DIRECTORY CARD THAT ACCURATELY IDENTIFIES CIRCUITS INSIDE EACH PANEL. HANDWRITTEN LABELS ARE NOT ACCEPTABLE.
16. IN ACCORDANCE WITH SECTION 510 OF THE SFC, TESTING WILL BE REQUIRED TO DETERMINE SATISFACTORY FIRST RESPONDER RADIO SIGNAL STRENGTH INSIDE EACH BUILDINGS ON SITE. TESTING WILL NEED TO EITHER BE COMPLETED BY A COUNTY FIRE INSPECTOR (OBTAIN BY REQUESTING A COURTESY INSPECTION) OR A CERTIFIED 3RD PARTY. TESTING SHALL TAKE PLACE AT BOTH 80% PROJECT COMPLETION AND AGAIN AT 100% COMPLETION. IF UNACCEPTABLE SIGNAL DEGRADATION IS PRESENT AT EITHER 80% OR 100% INSPECTION, THEN AN ACCEPTABLE BOOSTER SYSTEM SHALL BE ADDED TO THE BUILDING DESIGN AT THAT TIME.
17. COLOR CODE CONDUCTORS PER NEC. FEEDERS SHALL BE IDENTIFIED IN ACCORDANCE WITH NEC 215.12. USE BLACK, RED, AND BLUE FOR PHASES A, B, AND C RESPECTIVELY ON 208Y/120 VOLT THREE-PHASE Y SYSTEMS AND WHITE FOR THE NEUTRAL. ISOLATED GROUND WIRES SHALL BE GREEN WITH YELLOW BANDS OR STRIPES. USE BROWN, ORANGE, AND YELLOW FOR PHASES A, B, AND C RESPECTIVELY FOR 480Y/277 VOLT THREE-PHASE Y SYSTEMS AND GRAY FOR THE NEUTRAL. ON 4 WIRE DELTA CONNECTED SYSTEMS WHERE THE MIDPOINT OF ONE PHASE WINDING IS GROUNDED, THE PHASE CONDUCTOR HAVING THE HIGHER PHASE TO GROUND VOLTAGE SHALL BE PERMANENTLY IDENTIFIED WITH AN OUTER FINISH THAT IS ORANGE IN COLOR; THIS IDENTIFICATION SHALL BE MADE AT EACH POINT WHERE A CONNECTION IS MADE. COLORS SHALL BE FACTORY APPLIED FOR CONDUCTORS #6 AWG AND SMALLER. ALL EQUIPMENT GROUNDING CONDUCTORS SHALL BE GREEN IN COLOR AND MINIMUM #12 AWG. THE EC SHALL PROVIDE PLENUM RATED CABLE FOR ANY ELECTRICAL, TELEPHONE, COMMUNICATION, OR OTHER CABLE THAT ENTERS CEILING RETURN PLENUMS.
18. ABANDONED CONDUIT AND BOXES SHALL HAVE ALL ELECTRICAL WIRING REMOVED COMPLETELY AND NOT JUST "MADE SAFE." CONDUIT AND BOXES SHALL BE REMOVED WHERE PRACTICAL WITHOUT CREATING ADDITIONAL DEMOLITION/RESTITUTION WORK FOR OTHER TRADES.
19. WHERE CONDUCTORS ARE RUN IN PARALLEL, THE EC SHALL COMPLY WITH NEC 310.10(G).
20. ALL EQUIPMENT LOCATED UNDER KITCHEN HOODS SHALL BE WIRED FROM SHUNT TRIP BREAKERS.
21. ISOLATED-GROUND TYPE RECEPTACLES SHALL BE INSTALLED IN ACCORDANCE WITH NEC 250.146(D). ISOLATED GROUND RECEPTACLES SHALL BE ORANGE IN COLOR.
22. PROVIDE AND INSTALL LISTED TAMPER PROOF RECEPTACLES IN AREAS REQUIRED PER NEC 406.12.
23. TRANSFER EQUIPMENT SHALL BE LISTED FOR THE PARTICULAR USE (I.E., "EMERGENCY" OR "STANDBY") AND SHALL BE APPROVED BY THE AUTHORITY HAVING JURISDICTION.

MATERIALS:

1. THE EC SHALL PROVIDE ALL NECESSARY DISCONNECTS, SWITCHES, RECEPTACLES, TERMINALS, ETC, UNDER THE ELECTRICAL BID AND SHALL INCLUDE ALL NECESSARY CIRCUITS AND CONNECTIONS TO THE EQUIPMENT PROVIDED BY ALL SUPPLIERS, UNLESS NOTED OTHERWISE BY OTHER DISCIPLINES.
2. EC SHALL PROVIDE ALL SERVICE ENTRANCE EQUIPMENT, SUB PANELS, AND OTHER ELECTRICAL DISTRIBUTION EQUIPMENT AS NECESSARY FOR A COMPLETE INSTALLATION. EC SHALL COORDINATE WITH UTILITY REGARDING SERVICE AND METERING DETAILS. *PRIOR TO ORDERING EQUIPMENT, THE EC SHALL OBTAIN THE AVAILABLE FAULT CURRENT OR TRANSFORMER SIZE AND IMPEDANCE FROM THE UTILITY AND CONTACT THE ENGINEER IF THE VALUE EXCEEDS THE EQUIPMENT SPECIFIED.* PANEL BOARDS AND SWITCH BOARDS SHALL BE SQUARE D, CUTLER-HAMMER, SIEMENS, OR GE. BUSES SHALL BE COPPER UNLESS OTHERWISE APPROVED BY THE ENGINEER. RECESSED PANEL BOARDS SHALL BE INSTALLED FLUSH WITH THE WALL FINISH. METER BASES SHALL COMPLY WITH THE UTILITY'S SPECIFICATIONS AND SHALL BE MOUNTED AT A HEIGHT APPROVED BY THE UTILITY. ALL EQUIPMENT IDENTIFIED FOR SERVICE ENTRANCE USE SHALL BE SO LABELED AND UL LISTED FOR SUCH USE. EC SHALL INSTALL ALL ELECTRICAL EQUIPMENT WITH CLEARANCES PER NEC 110.26. EC SHALL PERMANENTLY LABEL EQUIPMENT PER NEC 110.24.
3. ENCLOSED SAFETY SWITCHES SHALL BE HEAVY DUTY TYPE BY SQUARE D, EATON, OR GE. ENCLOSED SWITCHES SHALL HAVE A HANDLE LOCKABLE IN THE OFF POSITION AND SHALL HAVE A HANDLE INTERLOCKED TO PREVENT OPENING THE FRONT COVER WHILE IN THE ON POSITION. ENCLOSED SWITCHES OF THE FUSIBLE TYPE SHALL BE FUSED IN ACCORDANCE WITH NAMEPLATE DATA WITH DUAL ELEMENT TYPE FUSES BY BUSSMAN, LITTELFUSE, OR MERSEN.
4. OCCUPANCY SENSORS SHALL BE BY WATTSTOPPER, LUTRON, LEVITON, SENSOR SWITCH, HUBBELL, OR APPROVED EQUAL.
5. CIRCUIT BREAKERS SHALL BE MOLDED-CASE, THERMAL MAGNETIC TYPE WITH QUICK-MAKE, QUICK-BREAK MECHANISM, COMMON TRIP ON MULTI-POLE BREAKERS, AND UL LISTED FOR BOTH COPPER AND ALUMINUM CONDUCTORS. CIRCUIT BREAKERS IN PANELS SHALL BE SERIES RATED WITH THE MAIN BREAKER, FULLY RATED FOR THE SYSTEM, OR SERIES RATED WITH THE BREAKER FEEDING THE PANEL FROM THE FACTORY.
6. ALL WIRE, CONNECTORS, TERMINALS, AND LUGS SHALL BE PROVIDED BY THE EC. WHERE CONDUCTORS ARE RUN IN PARALLEL, LUGS SHALL BE LISTED FOR PARALLEL CONDUCTORS. PUSH WIRE CONNECTORS ARE NOT ALLOWED FOR BUILDING WIRE. PUSH CONNECTORS ARE ONLY ALLOWED, WHEN APPROVED, AS PART OF MANUFACTURED LISTED PRODUCTS. ALL WIRE SHALL BE INSTALLED IN CONDUIT UNLESS SPECIFICALLY NOTED OTHERWISE.
7. THE INSULATION TYPE FOR INTERIOR WIRING SHALL BE DUAL RATED THHN/THWN OR XHHW; ALL WIRING INSTALLED BELOW GRADE OR IN MOIST OR WET LOCATIONS SHALL HAVE TYPE THWN OR XHHW INSULATION. INSULATION VOLTAGE RATING SHALL BE 600 VOLTS AND A MINIMUM TEMPERATURE RATING OF 75°C. CONDUCTORS SHALL BE SOLID OR STRANDED COPPER FOR #10 AWG AND #12 AWG, AND STRANDED COPPER FOR #8 AWG AND LARGER SIZES. ALL WIRING AND CABLE SHALL BE UL LISTED. ALL TERMINATIONS AND DEVICES SHALL BE RATED FOR USE WITH 75°C CONDUCTORS. FINAL CONNECTIONS TO ALL MOTORS AND EQUIPMENT SUBJECT TO VIBRATION OR MOVEMENT SHALL BE MADE WITH STRANDED COPPER CONDUCTORS. CONDUCTORS SHALL BE BY CERRO WIRE, INC, INDUSTRIAL WIRE & CABLE, INC, ENCORE WIRE CORPORATION, OR SOUTHWIRE COMPANY.
8. JOINTS IN SOLID CONDUCTORS SHALL BE SPLICED USING IDEAL "WIRE NUTS", 3M "SCOTCH LOCK", OR T&B "PIGGY" CONNECTORS IN JUNCTION BOXES, OUTLET BOXES, AND LIGHTING FIXTURES. JOINTS IN STRANDED CONDUCTORS SHALL BE SPLICED BY APPROVED MECHANICAL CONNECTORS AND GUM RUBBER TAPE OR FRICTION TAPE. SOLDERLESS MECHANICAL CONNECTORS FOR SPLICES AND TAPS, PROVIDED WITH UL APPROVED INSULATING COVERS, MAY BE USED INSTEAD OF MECHANICAL CONNECTORS PLUS TAPE. IN ALL CASES, CONDUCTORS SHALL BE CONTINUOUS FROM OUTLET TO OUTLET AND NO SPLICING SHALL BE MADE EXCEPT WITHIN OUTLET OR JUNCTION BOXES, TROUGHS, OR GUTTERS. WHERE CONCENTRIC, ECCENTRIC, OR OVERSIZED KNOCKOUTS ARE ENCOUNTERED, A GROUNDING TYPE INSULATED BUSHING SHALL BE PROVIDED.
9. ALL LUMINAIRES SHALL BE LISTED. LUMINAIRES IN WET OR DAMP LOCATIONS SHALL BE MARKED AS SUITABLE FOR THE RESPECTIVE USE. EMERGENCY LIGHTING SHALL BE INSTALLED AS SHOWN. FINAL LOCATIONS OF ALL EXIT AND EMERGENCY LIGHTS SHALL BE VERIFIED WITH THE BUILDING INSPECTOR PRIOR TO INSTALLATION. ALL FLUORESCENT FIXTURES SHALL HAVE ELECTRONIC BALLASTS MEETING ANSI C82.11 FOR ELECTRONIC BALLAST PERFORMANCE. ALL BALLASTS SHALL BE UL LISTED AND MEET FEDERAL AND STATE EFFICIENCY REQUIREMENTS.
10. ALL CONDUIT, FITTINGS, COUPLINGS, AND SUPPORTS SHALL BE PROVIDED BY THE EC. CONDUIT FITTINGS AND COUPLINGS SHALL BE BY APPLETON, RACO, OR O-Z/GEDNEY. COUPLINGS SHALL BE THREADED, SET-SCREW, OR COMPRESSION TYPE. INDENTER OR CRIMP TYPE ARE NOT PERMITTED. CONDUIT FITTINGS AT ALL ELECTRICAL BOXES INCLUDING PULL, JUNCTION, AND OUTLET BOXES, SHALL HAVE INSULATED THROATS TO PREVENT INSULATION SCORING. DIE CAST FITTINGS ARE NOT PERMITTED
11. EMT SHALL BE MANUFACTURED IN ACCORDANCE WITH AMERICAN NATIONAL STANDARDS INSTITUTE-AMERICAN NATIONAL STANDARD FOR STEEL ELECTRICAL METALLIC TUBING (EMT), ANSI C80.3 AND UL 797. RIGID METAL CONDUIT SHALL BE MANUFACTURED IN ACCORDANCE WITH ANSI-AMERICAN NATIONAL STANDARD FOR ELECTRICAL RIGID STEEL CONDUIT (ERSC), ANSI C80.1 AND UL 6. INTERMEDIATE METAL CONDUIT SHALL BE MANUFACTURED IN ACCORDANCE WITH ANSI-AMERICAN NATIONAL STANDARD FOR INTERMEDIATE METAL CONDUIT ANSI C80.6 AND UL 1242.
12. METAL CONDUIT SHALL BE BY ALLIED TUBING & CONDUIT, BECK MANUFACTURING, INC, OR WHEATLAND TUBE COMPANY. FLEXIBLE METAL CONDUIT, LIQUID-TIGHT FLEXIBLE METAL CONDUIT, AND NONMETALLIC CONDUIT SHALL BE BY AFC CABLE SYSTEMS, INC, ELECTRI-FLEX COMPANY, OR INTERNATIONAL METAL HOSE.

ELECTRICAL DRAWING INDEX

SHEET NUMBER	SHEET TITLE
E-001	ELECTRICAL NOTES
E-101	OVERALL LIGHTING PLAN
E-102	ENLARGED OFFICE LIGHTING PLAN
E-103	OVERALL POWER PLAN
E-104	ENLARGED OFFICE POWER PLAN
E-105	OVERALL LV CAMERA/ACCESS PLAN
E-201	ELECTRICAL SCHEDULES
E-301	ELECTRICAL PANEL SCHEDULES
E-302	ELECTRICAL PANEL SCHEDULES & POWER RISER

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY — KILIAN ENGINEERING, INC. — No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #2Z6110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WATTS

PRINCIPAL IN CHARGE
[redacted]

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION


UPS SAV TENANT INPROVEMENT

ELECTRICAL NOTES

E-001

© 2025 STRATUS®

LIGHTING PLAN HEX NOTES
1. EXISTING LIGHTS AND CONTROLS IN WAREHOUSE EXISTING TO REMAIN.
2. LIGHTS IN ACMX STORAGE AREA TO BE REDESIGNED AND RECONNECTED AS SHOWN ON E-102. LIGHTS TO REMAIN ON EXISTING CIRCUIT.



1 OVERALL LIGHTING PLAN

Scale: 1/8" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]

GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338

DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. LEWTER

PRINCIPAL IN CHARGE
[redacted]

OVERALL LIGHTING PLAN

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A


02/20/2026
ISSUED FOR CONSTRUCTION

E-101

© 2025 STRATUS®

LIGHTING PLAN GENERAL NOTES
1. ALL LIGHTING AND CONTROLS SHOWN IN VIEW ARE NEW 2. EGRESS LIGHT TO BE POWERED BY SAME LIGHTING CIRCUIT SUPPLYING THE ROOM AND WIRED AHEAD OF SWITCH

⬡ LIGHTING PLAN HEX NOTES
1. LIGHTS TO REMAIN ON EXISTING CIRCUIT. EC TO REDO CONTROLS AS SHOW.



1 ENLARGED OFFICE LIGHTING PLAN

Scale: 1/4" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WATER

PRINCIPAL IN CHARGE
[redacted]

ENLARGED OFFICE LIGHTING PLAN

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	02/18/2026	ADDENDUM A


02/20/2026
ISSUED FOR CONSTRUCTION

E-102

© 2025 STRATUS®

POWER PLAN HEX NOTES
1. ALL PANELS AND STEP-DOWN TRANSFORMER EXISTING TO REMAIN.
2. ALL RECEPTS ON OFFICE AREA WALLS TO BE DEMOED BACK TO BREAKER
3. EXISTING POWER FOR OIL/WATER SEPARATOR MONITORING SYSTEM
4. EXISTING PANEL TO BE RELOCATED TO NEW LOCATION SHOWN. EC TO COORDINATE FINAL LOCATION W/ UPS

POWER PLAN GENERAL NOTES
1. EC TO VERIFY ALL EXISTING DOOR JUNCTION BOXES, ACCESS CONTROLS, AND RECEPTS SHALL BE CLEAN, INSPECTED, AND TESTED FOR PROPER OPERATION



1 OVERALL POWER PLAN

Scale: 1/8" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY — KILIAN ENGINEERING, INC. No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WATER

PRINCIPAL IN CHARGE
[redacted]

UPS SAV TENANT INPROVEMENT

OVERALL POWER PLAN

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

E-103


© 2025 STRATUS®

POWER PLAN HEX NOTES


1. 30 AMP, NEMA 1, 480V 3Ø DISCONNECT FOR WH-1, MOUNTED AT UNIT HEIGHT
2. DATA AND RECEPT TO BE MOUNTED 7' AFF FOR TV
3. 60 AMP, NEMA 1, 208V 1Ø DISCONNECT FOR AHU MOUNTED ABOVE CEILING. SERVICE DISCONNECT TO BE MOUNTED AT UNIT HEIGHT
4. 60 AMP, NEMA 3R, 208V 1Ø DISCONNECT, FUSED AT 45 AMPS FOR HP-1 AND 2.
5. MOTOR RATED SWITCH FOR RECIRC PUMP TO BE MOUNTED ABOVE CEILING
6. PHONE BOARD TO BE INSTALLED WITH 2 QUAD RECEPTS, MOUNTED AT 36 AFF, AND 6 SURFACE MOUNT DATA OUTLETS IN 2 GANG BOXES. EC TO PAINT BOARD WITH GRAY FIRE-RATED PAINT, VERIFY W/ GC
7. TELECOM MASTER GROUND BUS BAR TO BE MOUNTED 72" AFF
8. 4" CONDUIT STUB UP W/ SLEEVE
9. DOUBLE STACKED LADDER RACK CONNECTING ALL STUB UP LOCATIONS
10. 60 AMP, NEMA 3R, 208V 3Ø DISCONNECT, FUSED AT 35 AMPS FOR MS-1 AND 2. VERIFY FUSE AND BREAKER SIZE WITH PURCHASED EQUIPMENT
11. RECEPT TO BE MOUNTED AT 42" AFF
12. JBOX FOR INTERIOR WALL MOUNTED MINI SPLIT POWERED FROM EXTERIOR UNIT. MOUNT PER MANUFACTURERS INSTRUCTIONS.
13. JBOX FOR HARDWIRED SINK FAUCET. EC TO MOUNT PER MANUFACTURERS INSTRUCTION
14. JBOX FOR HARDWIRED TOILET SENSOR. EC TO MOUNT PER MANUFACTURERS INSTRUCTION

POWER PLAN GENERAL NOTES

1. ALL ELECTRICAL SHOWN IN VIEWS ARE NEW
2. EC WILL PROVIDE UNISTRUT STAND FOR RECEPTS IN GSE AREA TO MOUNT TO AT 18" AFF.
3. ALL DATA TO BE ROUTED BACK TO NEW SERVER ROOM.



1 ENLARGED OFFICE POWER PLAN
Scale: 1/4" = 1'-0"



2 ENLARGED GSE POWER PLAN
Scale: 1/4" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WHITE

PRINCIPAL IN CHARGE
[redacted]

UPS SAV TENANT INPROVEMENT

ENLARGED OFFICE POWER PLAN

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

E-104


© 2025 STRATUS®

CAMERA AND ACCESS GENERAL NOTES
1. CAMERAS AND CARD READERS TO BE INSTALLED BY OTHERS. EC IS RESPONSIBLE FOR ELECTRICAL WIRING ONLY FOR CAMERA AND CARD READERS.
2. ALL CAMERAS AND ACCESS PANES TO BE WIRED THROUGH SECURITY SYSTEM LOCATED IN THE SERVER ROOM.
3. EC TO RUN AND STUB OUT EMT FOR DATA DROP LOCATIONS. ALL COMMUNICATION CABLES TO BE RUN BY OTHERS.

CAMERA CONNECTION LEGEND		
MARK	TYPE	MODEL
EPTZ	40X PTZ	HANWHA XNP-6400
E360	360 FISHEYE	HANWHA XNF-8010RV
IPTZ	MINI 12X PTZ	HANWHA XNP-6120HW
I360	360 FISHEYE	HANWHA XNF-8010RV
IFIX	FIXED DOME	HANWHA XNV-6080R

CARD ACCESS LEGEND	
MARK	TYPE
CAP	CARD ACCESS PANEL (HEAD END)
CR	CARD ACCESS/BADGE READER

SECURITY POWER/DATA LEGEND	
MARK	TYPE
CAP	POWER DROP (120V HARDWIRED TO PANEL) FOR CARD ACCESS PANEL
MD	POWER DROP (120V OUTLET) FOR WALK-THROUGH METAL DETECTOR
●	DATA DRIP FOR CARD ACCESS PANEL



1 OVERALL LV CAMERA/ACCESS PLAN

Scale: 1/8" = 1'-0"

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY
KILIAN ENGINEERING, INC.
No. PEF007969

UNITED PARCEL SERVICE INC.

STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WEBB

PRINCIPAL IN CHARGE
[redacted]

OVERALL LV CAMERA/ACCESS PLAN

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

E-105

© 2025 STRATUS®

LIGHTING DEVICE LEGEND		
SYMBOL	DESCRIPTION	REMARKS
$	SINGLE POLE WALL SWITCH	HEAVY DUTY, AC ONLY, COMMERCIAL GRADE GENERAL USE SNAP SWITCH COMPLYING WITH NEMA WD 6 AND WD 1. IVORY PLASTIC BODY WITH TOGGLE HANDLE. 120-277V, 20A. MEET FEDERAL SPECIFICATION W-S-896.
$D	DIMMER SWITCH	COMMERCIAL GRADE, 120V, 1500W
$M	WALL MOUNTED OCCUPANCY SENSOR	WATTSTOPPER DSW-301 LINE VOLTAGE OCCUPANCY SENSOR. ULTRA SONIC AND INFRARED.
$LV	LOW VOLTAGE SWITCH	WATTSTOPPER LVSW-101 LOW VOLTAGE MOMENTARY CONTROL SWITCH.
$3	3 WAY SWITCH	3-WAY TYPE SWITCH WITH SAME CHARACTERISTICS AS SINGLE POLE SWITCH ABOVE.
(DT)	CEILING OCCUPANCY SENSOR	WATTSTOPPER, UT-300-3 LOW VOLTAGE OCCUPANCY SENSOR. 360° ULTRA SONIC AND INFRARED.
(P)	POWER PACK	WATTSTOPPER, BZ-150 LOW VOLTAGE POWER PACK FOR CEILING PACK SENSORS.
(J)	JUNCTION BOX	GALVANIZED METAL BOX CONSTRUCTED IN ACCORDANCE WITH 314.40 OF THE NEC.
⊠	EXHAUST FAN	VENT FAN, 120V, CFM AS NOTED MC TO PROVIDE AND VENT, EC TO WIRE.

POWER DEVICE LEGEND		
SYMBOL	DESCRIPTION	REMARKS
▶	DATA AND TELEPHONE JACK	PHONE/DATA OUTLET. EC TO INSTALL 3/4"C WITH PULL-STRING FROM OUTLET BOX TO ABOVE CEILING FOR FUTURE USE. JACKS AND COMMUNICATION CABLING BY OTHERS.
	DUPLEX RECEPTACLE	NEMA 5-20R, HEAVY DUTY, COMMERCIAL GRADE, 125V, 20A COMPLYING WITH NEMA WD 6 AND WD 1. GFCI OR AFCI IF NOTED. 'WP' DENOTES WEATHERPROOF COVER. 'CH' DENOTES COUNTER HEIGHT. LISTED TAMPERPROOF IF NOTED. MEET FEDERAL SPECIFICATION W-C-596.
	QUAD RECEPTACLE	QUAD RECEPTACLE OF SAME CHARACTERISTICS AS DUPLEX TYPE ABOVE.
	DEDICATED RECEPTACLE	NEMA 5-20R, HEAVY DUTY, COMMERCIAL GRADE, 125V, 20A COMPLYING WITH NEMA WD 6 AND WD 1 UNLESS OTHERWISE NOTED ON PLANS. VERIFY PLUG TYPE PRIOR TO PURCHASE & INSTALLATION. GFCI OR AFCI IF NOTED. 'WP' DENOTES WEATHERPROOF COVER. 'CH' DENOTES COUNTER HEIGHT. LISTED TAMPERPROOF IF NOTED. MEET FEDERAL SPECIFICATION W-C-596. MAY BE EITHER SIMPLEX, DUPLEX, OR QUAD.
	240V RECEPTACLE	240V RECEPTACLE WITH SAME CHARACTERISTICS AS DUPLEX TYPE ABOVE. VERIFY NEMA PLUG CONFIGURATION.
	480V RECEPTACLE	480V RECEPTACLE WITH SAME CHARACTERISTICS AS DUPLEX TYPE ABOVE. VERIFY NEMA PLUG CONFIGURATION.
	DUPLEX FLOOR RECEPTACLE	DUPLEX RECEPTACLE OF SAME CHARACTERISTICS AS ABOVE WITH BRASS COVER. MOUNT IN FLOOR. ALL FLOOR BOXES MUST BE LISTED FOR FLOOR APPLICATION.
	QUAD FLOOR RECEPTACLE	QUAD RECEPTACLE OF SAME CHARACTERISTICS AS ABOVE WITH BRASS COVER. MOUNT IN FLOOR. ALL FLOOR BOXES MUST BE LISTED FOR FLOOR APPLICATION.
	DEDICATED FLOOR RECEPTACLE	MOUNT IN FLOOR NEMA 5-20R, HEAVY DUTY, COMMERCIAL GRADE, 125V, 20A COMPLYING WITH NEMA WD 6 AND WD 1 UNLESS OTHERWISE NOTED ON PLANS. VERIFY PLUG TYPE PRIOR TO PURCHASE & INSTALLATION. GFCI OR AFCI IF NOTED. 'WP' DENOTES WEATHERPROOF COVER. 'CH' DENOTES COUNTER HEIGHT. LISTED TAMPERPROOF IF NOTED. MEET FEDERAL SPECIFICATION W-C-596. MAY BE EITHER SIMPLEX, DUPLEX, OR QUAD.
	240V RECEPTACLE	MOUNT IN FLOOR 240V RECEPTACLE WITH SAME CHARACTERISTICS AS DUPLEX TYPE ABOVE. VERIFY NEMA PLUG CONFIGURATION.
	480V RECEPTACLE	MOUNT IN FLOOR 480V RECEPTACLE WITH SAME CHARACTERISTICS AS DUPLEX TYPE ABOVE. VERIFY NEMA PLUG CONFIGURATION.
	FUSIBLE DISCONNECT SWITCH	HEAVY DUTY TYPE. TYPE 1 ENCLOSURE IN INTERIOR APPLICATIONS, TYPE 3R ENCLOSURE IN EXTERIOR APPLICATIONS, FUSE ACCORDING TO NAMEPLATE DATA.
	DISCONNECT SWITCH	HEAVY DUTY TYPE. TYPE 1 ENCLOSURE IN INTERIOR APPLICATIONS, TYPE 3R ENCLOSURE IN EXTERIOR APPLICATIONS.
(J)	JUNCTION BOX	GALVANIZED METAL BOX CONSTRUCTED IN ACCORDANCE WITH 314.40 OF THE NEC.

BREAKER FEEDER SCHEDULE			
AMPS	WIRE SIZE	GROUND SIZE	CONDUIT SIZE
15A	#12	#12	1/2"
20A	#12	#12	1/2"
25A	#10	#10	3/4"
30A	#10	#10	3/4"
35A	#8	#10	1"
40A	#8	#10	1"
50A	#8	#10	1"
60A	#6	#10	1 1/4"
70A	#4	#8	1 1/4"
80A	#4	#8	1 1/4"
90A	#3	#8	1 1/2"
100A	#3	#8	1 1/2"
110A	#2	#6	2"
125A	#1	#6	2"
150A	1/0	#6	2 1/2"
175A	2/0	#6	2 1/2"
200A	3/0	#6	2 1/2"
225A	4/0	#4	2 1/2"
250A	250 MCM	#4	3"
300A	350 MCM	#4	3 1/2"
350A	500 MCM	#3	4"
400A	2 SETS- 3/0	#3	2 1/2"
500A	2 SETS- 250 MCM	#2	3"
600A	2 SETS- 350 MCM	#1	3 1/2"
700A	3 SETS- 250 MCM	1/0	3"
800A	3 SETS- 300 MCM	1/0	3 1/2"
1000A	3 SETS- 400 MCM	2/0	3 1/2"

1. CONDUCTOR PER POLE PLUS NEUTRAL PER SET. E.C. TO VERIFY NECESSITY OF NEUTRAL FOR EACH CIRCUIT. NEUTRAL MAY BE DELETED IF NOT REQUIRED FOR INDIVIDUAL PIECES.

LIGHT FIXTURE SCHEDULE										
MARK	DESCRIPTION	LOUVER/LENS	LAMPS		VOLTAGE	INPUT WATTAGE	MOUNTING	REMARKS	MFG	MODEL
			TYPE	CCT						
A	2X4 LED LOW PROFILE TROFFER	ACRYLIC	LED	4000K	277	40	LAY-IN	2	LITHONIA	2BLT4-48L-ADP-MVOLT-LP840
AE	2X4 LED LOW PROFILE TROFFER W/ BACKUP	ACRYLIC	LED	4000K	277	40	LAY-IN	2	LITHONIA	2BLT4-48L-ADP-MVOLT-LP840-E10W
B	6" LED RECESSED CAN	-	LED	4000K	277	15	RECESSED	2	LITHONIA	LDN6-40/10/LO6-AR-MVOLT-GZ10
C	LINEAR HIGH BAY LED	ACRYLIC	LED	4000K	277	211	PENDANT - 27' AFF	3	COOPER LIGHTING	OHB-36SE-MFL-UNV-L940-CD-U
C1E	LINEAR HIGH BAY LED W/ BACKUP BATTERY	ACRYLIC	LED	4000K	277	211	PENDANT - 27' AFF	1,3	COOPER LIGHTING	OHB-36SE-MFL-UNV-L940-CD-U-EL20
EX	LED EXIT SIGN	ACRYLIC	LED	N/A	MVOLT	2	VARIES	1	EELP	XE2RW-EM-SD
EXH	LED EXIT/EMERGENCY COMBO	ACRYLIC	LED	N/A	MVOLT	2	VARIES	1	EELP	XC-LED-2-R-W-SD
EM	DUAL HEAD EMERGENCY FIXTURE	ACRYLIC	LED	N/A	MVOLT	2	VARIES	1	LITHONIA	ELM2L-SDRT
OE	EXTERIOR LIGHT	ACRYLIC	LED	N/A	MVOLT	2	VARIES	1	EELP	DEM-EM

1. FIXTURE SHALL HAVE BATTERY BACKUP FOR 90 MINUTE ILLUMINATION.
2. OR EQUAL BY COOPER, MOBERN, OR CURRENT BY GE LIGHTING
3. LIGHT EXISTING TO REMAIN

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY KILIAN ENGINEERING, INC. No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WESTER

PRINCIPAL IN CHARGE
[redacted]

ELECTRICAL SCHEDULES

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	02/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

E-201

© 2025 STRATUS®

PANEL MDPD				
CKT	LOAD	BKR	LOAD kVA	PH
1	PANEL M41D	200/3	13.27	A
			13.54	B
			12.50	C
2	PANEL L41D	100/3	3.68	A
			4.65	B
			3.17	C
3	STEP-DOWN XFMER FOR PANEL P21D1	175/3	39.64	A
			37.15	B
			36.00	C
4	SPARE	400/3	0.00	A
			0.00	B
			0.00	C
5	SPARE	200/3	0.00	A
			0.00	B
			0.00	C
6	SPARE	200/3	0.00	A
			0.00	B
			0.00	C
7	SPARE	100/3	0.00	A
			0.00	B
			0.00	C
		AMPS	KVA	PH
		204.3	56.59	A
		199.8	55.34	B
		186.5	51.67	C

VOLTAGE/PHASE	480Y/277V, 3P, 4W
BUS RATING	400 AMB
MAIN CIRCUIT BREAKER RATING	400 AMP MB
AIC RATING	18K
SERVICE ENTRANCE RATED	NO
ENCLOSURE	NEMA 1
MOUNTING	SURFACE

PANEL L41D								
CKT	LOAD	BKR	LOAD kVA	PH	LOAD kVA	BKR	LOAD	CKT
*1	LTG - ROOM 108	20/1	3.32	A	0.36	20/1	RESTROOM/MOTHERS ROOM LTS	2
*3	LTG - ROOM 108	20/1	3.17	B	1.48	20/1	OFFICE/STORAGE/SERVER LTS	4
*5	LTG - ROOM 108	20/1	3.17	C	0.00	20/1	SPARE	6
7	SPARE	20/1	0.00	A	0.00	20/1	SPARE	8
9	SPARE	20/1	0.00	B	0.00	20/1	SPARE	10
11	SPARE	20/1	0.00	C	0.00	20/1	SPARE	12
13	SPARE	20/1	0.00	A	0.00	20/1	SPARE	14
15	SPARE	20/1	0.00	B	0.00	20/1	SPARE	16
17	SPARE	20/1	0.00	C	0.00	20/1	SPARE	18
19	SPARE	20/1	0.00	A	0.00	20/1	SPARE	20
21	SPARE	20/1	0.00	B	0.00	20/1	SPARE	22
23	SPARE	20/1	0.00	C	0.00	20/1	SPARE	24
25	SPARE	20/1	0.00	A	0.00	20/1	SPARE	26
27	SPARE	20/1	0.00	B	0.00	20/1	SPARE	28
29	SPD	30/3	0.00	C	0.00	20/1	SPARE	30
31			0.00	A	0.00	20/1	SPARE	32
33			0.00	B	0.00	20/1	SPARE	34
35	SPACE		0.00	C	0.00		SPACE	36
37	SPACE		0.00	A	0.00		SPACE	38
39	SPACE		0.00	B	0.00		SPACE	40
41	SPACE		0.00	C	0.00		SPACE	42
			PH	kVA	AMPS			
			A	3.68	13.285			
			B	4.65	16.787			
			C	3.17	11.444			

VOLTAGE/PHASE	480Y/277V, 3P, 4W
BUS RATING	100 AMP
MAIN CIRCUIT BREAKER RATING	MLO
AIC RATING	18K
SERVICE ENTRANCE RATED	NO
ENCLOSURE	NEMA 1
MOUNTING	SURFACE

* - LOAD BASED ON EXISTING SEALED PLANS DATED 5/23/25

PANEL M41D								
CKT	LOAD	BKR	LOAD kVA	PH	LOAD kVA	BKR	LOAD	CKT
*1	STEP-DOWN XFMER FOR PANEL M21D	70/3	1.27	A	2.00	20/3	EF-20	*2
*3			1.54	B	2.00			*4
*5			0.50	C	2.00			*6
*7	EF-21	20/3	2.00	A	2.00	20/3	EF-22	*8
*9			2.00	B	2.00			*10
*11			2.00	C	2.00			*12
*13	EF-23	20/3	2.00	A	0.00	20/3	SPARE	14
*15			2.00	B	0.00			16
*17			2.00	C	0.00			18
19	WH-1	30/3	4.00	A	0.00	20/1	SPARE	20
21			4.00	B	0.00	20/1	SPARE	22
23			4.00	C	0.00	20/1	SPARE	24
25	SPARE	20/1	0.00	A	0.00	20/1	SPARE	26
27	SPARE	20/1	0.00	B	0.00	20/1	SPARE	28
29	SPARE	20/1	0.00	C	0.00	20/1	SPARE	30
31	SPARE	20/1	0.00	A	0.00	20/1	SPARE	32
33	SPARE	20/1	0.00	B	0.00	20/1	SPARE	34
35	SPACE		0.00	C	0.00		SPACE	36
37	SPACE		0.00	A	0.00		SPACE	38
39	SPACE		0.00	B	0.00		SPACE	40
41	SPACE		0.00	C	0.00		SPACE	42
			PH	kVA	AMPS			
			A	1.27	47.906			
			B	13.54	48.881			
			C	12.50	45.126			

VOLTAGE/PHASE	480Y/277V, 3P, 4W
BUS RATING	250 AMP
MAIN CIRCUIT BREAKER RATING	250 AMP MB
AIC RATING	18K
SERVICE ENTRANCE RATED	NO
ENCLOSURE	NEMA 1
MOUNTING	SURFACE

* - LOAD BASED ON EXISTING SEALED PLANS DATED 5/23/25

PANEL M21D								
CKT	LOAD	BKR	LOAD kVA	PH	LOAD kVA	BKR	LOAD	CKT
1	SPACE		0.00	A	0.00	20/1	SPARE	2
3	SPARE	20/1	0.00	B	0.00	20/1	SPARE	4
5	SPARE	40/1	0.00	C	0.50	20/1	MODS	*6
*7	MODS	20/1	0.50	A	0.77	20/1	GUH-10	*8
*9	GUH-11	20/1	0.77	B	0.00	20/1	SPARE	10
11	SPARE	20/2	0.00	C	0.00	20/1	SPARE	12
13			0.00	A	0.00	20/1	SPARE	14
*15	GUH-9	20/1	0.77	B	0.00	20/1	SPARE	16
17	SPARE	20/1	0.00	C	0.00	20/1	SPARE	18
19	SPARE	20/1	0.00	A	0.00	20/1	SPARE	20
21	SPARE	20/1	0.00	B	0.00	20/1	SPARE	22
23	SPARE	20/1	0.00	C	0.00	20/1	SPARE	24
25	SPARE	20/1	0.00	A	0.00	20/1	SPARE	26
27	SPARE	20/1	0.00	B	0.00	20/1	SPARE	28
29	SPARE	20/1	0.00	C	0.00	20/1	SPARE	30
31	SPARE	20/1	0.00	A	0.00	20/1	SPARE	32
33	SPARE	20/1	0.00	B	0.00	20/1	SPARE	34
35	SPACE		0.00	C	0.00		SPACE	36
37	SPACE		0.00	A	0.00		SPACE	38
39	SPACE		0.00	B	0.00		SPACE	40
41	SPACE		0.00	C	0.00		SPACE	42
			PH	kVA	AMPS			
			A	1.27	10.583			
			B	1.54	12.833			
			C	0.50	4.1667			

VOLTAGE/PHASE	208Y/120V, 3P, 4W
BUS RATING	250 AMPS
MAIN CIRCUIT BREAKER RATING	250 AMP MB
AIC RATING	18K
SERVICE ENTRANCE RATED	NO
ENCLOSURE	NEMA 1
MOUNTING	SURFACE

* - LOAD BASED ON EXISTING SEALED PLANS DATED 5/23/25

PANEL P21D1								
CKT	LOAD	BKR	LOAD kVA	PH	LOAD kVA	BKR	LOAD	CKT
1	PANEL P21D2	100/3	11.48	A	10.53	100/3	PANEL P21D3	2
3			11.47	B	10.69			4
5			11.41	C	8.48			6
*7	RECP- ROOM 108	20/1	0.54	A	0.00	100/3	PANEL C21D	8
*9			1.15	B	0.00			10
*11	PWR - OVERHEAD DOOR RM 108	20/3	1.15	C	0.00			12
*13			1.15	A	0.72	20/1	RECP- ROOM 108	*14
*15	RECP- ROOM 108	20/1	0.72	B	1.15	20/3	PWR - OVERHEAD DOOR RM 108	*16
*17	RECP- ROOM 108	20/1	0.90	C	1.15			*18
*19	PWR - OVERHEAD DOOR RM 108	20/3	1.15	A	1.15			*20
*21			1.15	B	1.15			*22
*23			1.15	C	1.15	20/3	PWR - OVERHEAD DOOR RM 108	*24
*25	PWR - OVERHEAD DOOR RM 108	20/3	1.15	A	1.15			*26
*27			1.15	B	1.15			*28
*29			1.15	C	1.15	20/3	PWR - OVERHEAD DOOR RM 108	*30
*31	PWR - FUTURE TENANT SIGN	20/3	0.06	A	1.15			*32
*33			0.06	B	0.10	20/1	PWR - DOOR ACS	*34
*35			0.06	C	0.14	20/1	PWR - DOOR ACS	*36
*37	PWR - OVERHEAD DOOR RM 108	20/3	1.15	A	0.10	20/1	PWR - DOOR ACS	*38
*39			1.15	B	0.18	20/1	PWR - OIL/WATER SEPARATOR	*40
*41			1.15	C	6.96			42
43	SPARE	20/1	0.00	A	8.16	100/3	PANEL SR	44
45	SPARE	20/1	0.00	B	5.88			46
47	SPARE	20/1	0.00	C	0.00	20/1	SPARE	48
49	SPACE		0.00	A	0.00		SPACE	50
51	SPACE		0.00	B	0.00		SPACE	52
53	SPACE		0.00	C	0.00		SPACE	54
			PH	kVA	AMPS			
			A	39.64	330.33			
			B	37.15	309.58			
			C	36.00	300			

VOLTAGE/PHASE	208Y/120V, 3P, 4W
BUS RATING	400 AMP
MAIN CIRCUIT BREAKER RATING	400 AMP MB
AIC RATING	18K
SERVICE ENTRANCE RATED	NO
ENCLOSURE	NEMA 1
MOUNTING	SURFACE

* - LOAD BASED ON EXISTING SEALED PLANS DATED 5/23/25

NEC ELECTRIC DEMAND SUMMARY 480Y/277V, 3P, 4W							
EQUIPMENT	DEMAND FACTOR	kVA A	kVA B	kVA C	LOAD kVA	NEC REFERENCE	NOTES/CALCULATIONS
LIGHTING	100%	5.95	5.95	5.95	17.84	220.12	14865 SF X 1.2 VA/SF
RECEPTACLES < 10 kVA	100%	3.33	3.33	3.33	10.00	220.44	
RECEPTACLES > 10 kVA	50%	3.82	0.76	1.93	6.52	220.44	
HVAC	100%	20.72	31.76	18.51	70.99	--	BASED ON MCA
WATER HEATER	125%	5.00	5.00	5.00	15.00	422.13	STORAGE TANK < 120 GAL @ 125%
OVERHEAD DOORS	100%	8.15	8.15	8.19	24.49	--	
SIGN	100%	0.06	0.06	0.06	0.18	220.14(F)	
EQUIPMENT	100%	18.60	11.34	13.06	43.00	- -	
DEMAND kVA PER PHASE		65.63	66.35	56.03			
DEMAND AMPS PER PHASE		236.93	239.53	202.28			

*THE CALCULATED LIGHTING LOAD EXCEEDS THE CONNECTED LIGHTING LOAD.

1 PANEL SCHEDULES

Scale: NONE

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY KILIAN ENGINEERING, INC. No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. LIGHTER

PRINCIPAL IN CHARGE
[redacted]

ELECTRICAL PANEL SCHEDULES

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	03/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

E-301

© 2025 STRATUS®

PANEL P21D2

CKT	LOAD	BKR	LOAD kVA	PH	LOAD kVA	BKR	LOAD	CKT
1	RESTROOM RECEPTS	20/1	0.90	A	0.72	20/1	FLIGHT ROOM RECEPTS	2
3	TRAINING ROOM RECEPTS	20/1	0.72	B	0.54	20/1	MANAGEMENT OFFICE RECEPTS	4
5	MANAGEMENT OFFICE RECEPTS	20/1	0.54	C	0.60	20/3	ERV-1	6
7	VENDING MACHINE	20/1	0.54	A	0.60			8
9	VENDING MACHINE	20/1	0.54	B	0.60			10
11	ACMX STORAGE RECEPTS	20/1	0.72	C	0.36	20/1	MOTHERS ROOM RECEPTS	12
13	COORIDOR RECEPTS	20/1	0.54	A	0.36	20/1	SERVICE RECEPTS	14
15	AHU-1	45/2	4.25	B	2.12	30/2	HP-1	16
17			4.25	C	2.12			18
19	ACMX STORAGE RECEPTS	20/1	0.72	A	0.72	20/1	ACMX STORAGE RECEPTS	20
21	ACMX STORAGE RECEPTS	20/1	0.90	B	0.90	20/1	ACMX STORAGE RECEPTS	22
23	TECH REF RECEPTS	20/1	0.90	C	0.72	20/1	ACMX NON-CLI STORAGE RECEPTS	24
25	ACMX NON-CLI STORAGE RECEPTS	20/1	0.54	A	0.54	20/1	ACMX NON-CLI STORAGE RECEPTS	26
27	WATER COOLER	20/1	0.36	B	0.54	20/1	MOTHERS ROOM UC FRIDGE	28
29	UNI./MOTH./SHOWER PLUMB. SENSORS	20/1	1.20	C	0.00	20/1	SPARE	30
31	ICE MAKER	20/1	0.54	A	0.54	20/1	BREAK AREA RECEPTS	32
33	SPARE	20/1	0.00	B	0.00	20/1	SPARE	34
35	SPARE	20/1	0.00	C	0.00	20/1	SPARE	36
37	HOT WATER RECIRC LOOP	20/1	0.50	A	0.00	20/1	TECH RE TV RCEPT	38
39	SPARE	20/1	0.00	B	0.00	20/1	SPARE	40
41	SPACE		0.00	C	0.00		SPACE	42
43	FLIGHT TV RCEPT	20/1	0.54	A	1.20	20/1	XRAY MACHINE	44
45	SPACE		0.00	B	0.00		SPACE	46
47	SPACE		0.00	C	0.00		SPACE	48
49	SECURITY ENTRANCE RECEPTS	20/1	0.54	A	1.44	20/1	MEN/WOMEN PLUB. SENSORS	50
51	SPACE		0.00	B	0.00		SPACE	52
53	SPACE		0.00	C	0.00		SPACE	54
			PH	kVA	AMPS			
			A	11.48	95.67			
			B	11.47	95.58			
			C	11.41	95.08			

VOLTAGE/PHASE		208Y/120V, 3P, 4W
BUS RATING		100 AMP
MAIN CIRCUIT BREAKER RATING		MLO
AIC RATING		18K
SERVICE ENTRANCE RATED		NO
ENCLOSURE		NEMA 1
MOUNTING		SURFACE

PANEL P21D3

CKT	LOAD	BKR	LOAD kVA	PH	LOAD kVA	BKR	LOAD	CKT
1	AHU-2	45/2	4.25	A	2.12	30/2	HP-2	2
3			4.25	B	2.12			4
5	GSE AIR COMPRESSOR	80/2	4.16	C	0.72	20/1	GSE RECEPT	6
7			4.16	A	0.00	20/1	SPARE	8
9	GSE RECEPT	20/1	0.72	B	3.60	50/2	GSE WEILDER	10
11	SPARE	20/1	0.00	C	3.60			12
13	SPARE	20/1	0.00	A	0.00	20/1	SPARE	14
15	SPARE	20/1	0.00	B	0.00	20/1	SPARE	16
17	SPARE	20/1	0.00	C	0.00	20/1	SPARE	18
19	SPARE	20/1	0.00	A	0.00	20/1	SPARE	20
21	SPARE	20/1	0.00	B	0.00	20/1	SPARE	22
23	SPARE	20/1	0.00	C	0.00	20/1	SPARE	24
25	SPARE	20/1	0.00	A	0.00	20/1	SPARE	26
27	SPARE	20/1	0.00	B	0.00	20/1	SPARE	28
29	SPARE	20/1	0.00	C	0.00	20/1	SPARE	30
			PH	kVA	AMPS			
			A	10.53	87.75			
			B	10.69	89.083			
			C	8.48	70.667			

VOLTAGE/PHASE		208Y/120V, 3P, 4W
BUS RATING		100 AMP
MAIN CIRCUIT BREAKER RATING		MLO
AIC RATING		18K
SERVICE ENTRANCE RATED		NO
ENCLOSURE		NEMA 1
MOUNTING		SURFACE

PANEL C21D

CKT	LOAD	BKR	LOAD kVA	PH	LOAD kVA	BKR	LOAD	CKT
1	GSE WEILDER	50/2	3.60	A	3.60	50/2	GSE WEILDER	2
3			3.60	B	3.60			4
5	GSE WEILDER	50/2	3.60	C	0.00	20/1	SPARE	6
7			3.60	A	0.00	20/1	SPARE	8
9	SPARE	20/1	0.00	B	0.00	20/1	SPARE	10
11	SPARE	20/1	0.00	C	0.00	20/1	SPARE	12
13	SPARE	20/1	0.00	A	0.00	20/1	SPARE	14
15	SPARE	20/1	0.00	B	0.00	20/1	SPARE	16
17	SPARE	20/1	0.00	C	0.00	20/1	SPARE	18
19	EXISITING SPD	30/3	0.00	A	0.00	20/1	SPARE	20
21			0.00	B	0.00	20/1	SPARE	22
23			0.00	C	0.00	20/1	SPARE	24
25	SPACE		0.00	A	0.00		SPACE	26
27	SPACE		0.00	B	0.00		SPACE	28
29	SPACE		0.00	C	0.00		SPACE	30
			PH	kVA	AMPS			
			A	10.80	90			
			B	7.20	60			
			C	3.60	30			

VOLTAGE/PHASE		208Y/120V, 3P, 4W
BUS RATING		100 AMP
MAIN CIRCUIT BREAKER RATING		MLO
AIC RATING		18K
SERVICE ENTRANCE RATED		NO
ENCLOSURE		NEMA 1
MOUNTING		SURFACE


PANEL SR

CKT	LOAD	BKR	LOAD kVA	PH	LOAD kVA	BKR	LOAD	CKT
1	TSG SERVER RECEPTS	20/1	0.72	A	0.18	20/1	TSG SERVER RACK RECEPT	2
3	TSG SERVER RACK RECEPT	20/1	0.18	B	0.18	20/1	TSG SERVER RACK RECEPT	4
5	TSG SERVER RACK RECEPT	20/1	0.18	C	0.18	20/1	TSG SERVER RACK RECEPT	6
7	TSG SERVER RACK RECEPT	20/1	0.18	A	0.18	20/1	TSG SERVER RACK RECEPT	8
9	TSG SERVER RACK RECEPT	20/1	0.18	B	0.18	20/1	TSG SERVER RACK RECEPT	10
11	TSG SERVER RACK RECEPT	20/1	0.18	C	1.80	30/1	TSG SERVER RACK RECEPT	12
13	TSG SERVER RACK RECEPT	30/1	1.80	A	0.36	20/1	PHONE BOARD QUAD	14
15	MS-1	35/2	3.54	B	0.36	20/1	PHONE BOARD QUAD	16
17			3.54	C	0.00	20/1	SPARE	18
19	MS-2	35/2	3.54	A	0.00	20/1	SPARE	20
21			3.54	B	0.00	20/1	SPARE	22
23	SPARE	20/1	0.00	C	0.00	20/1	SPARE	24
25	SPARE	20/1	0.00	A	0.00	20/1	SPARE	26
27	SPARE	20/1	0.00	B	0.00	20/1	SPARE	28
29	SPARE	20/1	0.00	C	0.00	20/1	SPARE	30
			PH	kVA	AMPS			
			A	6.96	58.00			
			B	8.16	68.00			
			C	5.88	49.00			

VOLTAGE/PHASE		208Y/120V, 3P, 4W
BUS RATING		100 AMP
MAIN CIRCUIT BREAKER RATING		100 AMP MB
AIC RATING		18K
SERVICE ENTRANCE RATED		NO
ENCLOSURE		NEMA 1
MOUNTING		SURFACE

1 PANEL SCHEDULES

Scale: NONE



GENERAL FEEDER SCHEDULE		
MARK	WIRE AND CONDUIT	AMPS
1	4 - #3 CU, 1 - #8 CU GRND, 1 1/2" CONDUIT	100

2 POWER RISER

Scale: NONE

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY KILIAN ENGINEERING, INC. No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338
DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WATTS

PRINCIPAL IN CHARGE
[redacted]

ELECTRICAL PANEL SCHEDULES AND POWER RISER

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	02/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

E-302


© 2025 STRATUS®

FIRE PROTECTION PLAN HEX NOTES

1. EXISTING UPRIGHT HEAD TO BE DEMO'D. REPLACE WITH PENDANT SPRINKLER ON SPRIG IN EXISTING OUTLET.
2. EXISTING UPRIGHT HEAD TO BE RELOCATED TO THIS LOCATION AS SHOWN.
3. SPRINKLER LINES GOING THROUGH STORAGE ROOM TO BE REROUTED AROUND SERVER RACKS. FIRE PROTECTION CONTRACTOR TO COORDINATE WITH OWNER/ EQUIPMENT VENDOR ON PRECISE LOCATIONS.
4. CUT EXISTING BRANCH LINE WITH FIRELOCK DB65 MECHANICAL T BOLTED COUPLING WITH SPRINKLER OUTLET.

FIRE PROTECTION PLAN GENERAL NOTES

- HEAD LAYOUT SHOWN FOR INFORMATIONAL PURPOSES ONLY.
- REFER TO FIRE PROTECTION SHOP DRAWINGS FOR HYDRAULIC CALCULATIONS, FINAL LINE AND HEAD LOCATIONS.
- FLEXIBLE PENDANT HEAD CONNECTIONS TO BE UTILIZED FOR SIMPLICITY OF INSTALLATION PER FIRE PROTECTION CONTRACTORS SUBMITTAL.



SPRINKLER LEGEND								
SYMBOL	MANUF.	TYPE	SIN#	TEMP	K.FACTOR	ORIF.	NPT	NET TOTAL
◎	VICTAULIC	QR-PENDANT	V2708	155°	5.6	1/2	1/2	33
REMOVED 31 UPRIGHT SPRINKLERS								+2

1 FIRE PROTECTION SUGGESTED HEAD LAYOUT

Scale: 1/8" = 1'-0"

———	NEW FIRE PROTECTION LINE
-·-·-·-	EXISTING FIRE PROTECTION LINE
⊗	EXISTING UPRIGHT SPRINKLER
⊗	RELOCATED UPRIGHT SPRINKLER
◍	NEW PENDANT SPRINKLER (SEE SCHEDULE)

KILIAN
A Stratus Team Company
[redacted]
www.kilianengineering.com | (P) 252.438.8778
[redacted]
GEORGIA CERTIFICATE OF AUTHORITY — KILIAN ENGINEERING, INC. — No. PEF007969
UNITED PARCEL SERVICE INC.
STRATUS®
3715 NORTHSIDE PARKWAY NW
BUILDING 300, SUITE 200
[redacted]
FIRM REG. #Z26110338

DES: BSL CHK: CSL/REW DRW: BSL

2025-1073

Seal

GEORGIA REGISTERED No. PE042886 PROFESSIONAL ENGINEER CHARLES S. WATTS

PRINCIPAL IN CHARGE
[redacted]

FIRE PROTECTION SUGGESTED HEAD LAYOUT

UPS SAV TENANT INPROVEMENT

REV:	DATE:	NOTE:
A	02/18/2026	ADDENDUM A

02/20/2026
ISSUED FOR CONSTRUCTION

FP-101